

BOQ FOR FENCING

ITEM	DESCRIPTION	QTY	UNIT	RATE Leones	AMOUNT Leones
A	<u>SITE CLEARANCE</u>				
	Carefully clear the whole site off unwanted material and cart away all debris from site		Item		
B	<u>EXCAVATION AND EARTHWORKS</u>				
1	Excavate trench for foundation commencing from ground level depth not exceeding 1200mm deep.	25	m ³		
2	Excavate pit for column base commencing from site strip level not exceeding 300mm deep	10	m ³		
3	Ditto Extra excavation in rock	5	m ³		
4	Disposed excavated materials in spoil heap for re-use	14.5	m ³		
	TOTAL				
C	<u>FORMWORK AND EARTHWORK SUPPORT</u>				
	Formwork and support to vertical faces of				
1	Columns	455	m ²		
2	Retaining wall	161	m ²		
	TOTAL				

ITEM	DESCRIPTION	QTY	UNIT	RATE Leones	AMOUNT Leones
D	<u>CONCRETE WORK</u>				
	In-situ concrete in normal mix 1:2:4 - 20mm/aggr. Pour in				
1	base	2.5	m ³		
2	Columns:	7.56	m ³		
3	Coping	7	m ³		
	TOTAL				
E	<u>REINFORCEMENT</u>				
1	12mm dia. Rod in:				
2	Column bases and columns	0.5	Ton		
3	Coping	0.5	Ton		
4	6mm diameter steel rod as stirrup in columns	0.3	Ton		
	TOTAL				
F	<u>BLOCKWORK</u>				
1	cement and sand mortar average mix: 1:6 , 150mm thick	200	m ²		
	TOTAL				
G	<u>ANCILLARY WORKS</u>				
1	Provide and installation complete with hinges,locks and tower bolts steel gate	1	nr		
2	Provide and fix razor wire and Y-bars on perimeter fence	180	m		
	TOTAL				
H	<u>GATEHOUSE</u>				
1	SUPPLY GATE		Item		
	TOTAL				