

### **BoQ of Work Station Area & Small Meeting Room (Annex B)**

Item No	Description of Items	Unit	Quantity
Civil & Interior Works			
01	Dry Partition (3" Thick)	sft	826
	3" thick Dry partition making with Gorjon Wooden frame and 1/2" thick Plain Partex, Surface finish with Plastic paint up to ceiling (Height 10'-0"). At the places of Glass partition, the height of dry partition would be up to 7'-0" from ceiling.		
02	Glass Partition	sft	693
	10mm thick Imported glass with top and bottom S.S channel including security paper pasted up to 7'-0" height from floor.		
03	Glass Door	Nos	3
	7'-0"X4'-0" 10mm Tempered glass door with all VVP hardwares, accessories and regular SS Handle, frosted paper on surface.		
04	False Ceiling	sft	2600
	Supply, Fitting & Fixing of Gypsum False Ceiling with Powder coated channel and necessary Hardware up to 8'-0" from ceiling.		
Office Furniture			
01	Work Station (Junior officer)	Nos	10
	Supply, Fitting and Fixing of Workstations made with imported PVC frame and Work top made with 1" thick melamine Board. Surafec will be finished with fabric of approved color up to 3'-0" from bottom and glass at top 1'-0".		
2	Low Height Cabinet (16" Deep)	sft	90
	Made 18 mm thick Melamine (Star Particle) board with necessary fittings.		
3	Low Height Cabinet (25" Deep)	sft	18
	Made 18 mm thick Melamine (Star Particle) board with necessary fittings at Dinning area.		
4	Roller Blinds	sft	375
	7'-6" high and 3mm thick Supply, Fitting & Fixing of Roller Blinds and windows and Outside Doors.		
Electrical Works			
	Cable Works		
01	2.5 rm Cable	Coil	6
	Supply, Fitting & Fixing of 2.5 rm BYA cable for wiring of Power Sockets at Meetin Table (BRB/Equivalent).		
	1.5 re Cable		

02	Supply, Fitting & Fixing of 1.5 re BYA cable for earthing wiring of Power Sockets at Meeting Table (BRB/Equivalent).	Coil	3
03	<b>4.0 rm Cable</b> Supply, Fitting & Fixing of 4.0rm BYA cable for wiring of AC (BRB/Equivalent).	Coil	6
04	<b>2.5 re Cable</b> Supply, Fitting & Fixing of 2.5 re BYA cable for earthing wiring of AC (BRB/Equivalent).	Coil	3
	<b>Electrical Socket</b>		
01	<b>13A Multi Socket</b> Supply, Fitting & Fixing of 13A multi Socket at Meeting Table (MK Enland/Equivalent).	Nos	24

Item No	Description of Items	Unit	Quantity
01	<b>20 Amp Circuit Breaker</b>	Nos	1
	Supply, Fitting & Fixing of 20 Amp TP MCCB Circuit Breaker for Power Sockets & AC (Legrend -Italy/Equivalent).		
02	<b>60 Amp Circuit Breaker</b>	Nos	1
	Supply, Fitting & Fixing of 60 AmpTP MCCB Main Circuit Breaker.(Legrend - Italy/Equivalent).		
	<b>Others</b>		
01	<b>Square Chanel</b>	rft	200
	Supply, Fitting & Fixing of 1/2" white square channel for electrical wiring (Aziz/Lira/Equivalent).		
02	<b>SDB Borad</b>	Nos	1
	Supply & installation Sub Distribution Electrical Board for Described Circuit Breakers and other accessories including all necessary accessories such as screw, nuts surface mounting box/ conceal box etc. with mechanism for fixing on the wall, column and wherever necessary as per drawing & direction of Engineer in Charge.		
<b>Air Conditioner</b>			
01	<b>Split Type Air Conditioner</b>	Nos	4
	Supply, Fitting & Fixing of Split type 2 Ton (24000 BTU) Air Conditioner of General/Carrier/Equivalent Brand with all necessary hardware & Copper Pipe.		
<b>WiFi Router With Wiring</b>			
01	<b>WiFi Router</b>	Nos	1
	Supply, Fitting & Fixing of WiFi router of coverage range 300 square meter area with a maximum link rate of 450Mbps on the 2.4GHz band and 1,300Mbps on the 5GHz band is considered an AC1750 router.		
02	<b>CAT 6 Cable</b>	Box	1
	Supply, Fitting & Fixing of LINKBASIC/SYSTEMAX Cat6 UTP Solid Cable 23AWG 305m/box with connector.		