



Empowered lives.  
Resilient nations.

### UNDP Operations Service Center, Erbil - Iraq

Reference: ITB- 220-17- Hamrren Dam Side Slopes Protection System, Diyala Governorate

Additional Clarification to Bidders Responses (ITB 220/17)		
#	Query	Clarification
1	Special conditions; page 45; Item # 4.1 Security: kindly advise if UNDP personnel & property should be covered by the contractor; if yes, please advise the level of security required.	Contractor will cover for the security of their personnel and property only.
2	Section 3a; Schedule of Requirements and Technical Specifications; page 27; Item # 2 scope of works: kindly advise location for disposal the excavated materials.	Location for disposal of excavated materials can be adjacent or close to the site works in coordination with end user monitoring engineering committee.
3	General Conditions; page 62; Item # 29 Interference with Adjoining Properties: Please advise if the adjacent land located at station 6+250 left side can be used for installing the site campus including site offices, services, lay down area, stock pile area etc.	Yes, or any adjacent surrounding area in coordination with end user monitoring engineering committee.
4	Section 3a; Schedule of Requirements and Technical Specifications; page 27; Item # 2 scope of works: kindly advise the requirements for the Employer & the Engineer office facilities on site.	Should be complete the office with all facilitates to accommodate around 15-20 employers & engineers with complete communication & furniture.
5	Data Sheet; page 24; Item # 30 Maximum Expected duration of contract of 10 months; kindly note that 10 months will not be sufficient for executing the project; specially with long procurement period of long lead items of up to 10 weeks; please advise if longer execution time would be acceptable. Your response will be highly appreciated.	The duration of the project of 10 months is feasible. It would require a good detailed work plan and work on multiple locations at the same time.  Company should be able to procure the long delivery items during the period of preparation and earth works. Longer execution time would not be generally accepted. Minor deviations in the completion time may be tolerated as long as they are in line with valid contract.
6	UNDP is tax exempted. Is this exemption applied on the tax & customs that paid at port of importation when importing the Geosynthetic materials.	UNDP will facilitate in issuing a letter to the contractor to whom the contract is awarded for obtaining tax/customs exemption at the port for goods/equipment required under the UNDP contract.

Additional Clarification to Bidders Responses (ITB 220/17)		
#	Query	Clarification
		The import documents should be in the name of UNDP and must be submitted to UNDP at least 15 days prior to the shipment.
7	After reviewing the bidding documents there is no reference to the dimensions of woven geotextile Anchor Tube. kindly advise us the required dimensions.	The anchor tube shall be prefabricated and as an integral part of the woven geotextile and shall be of a diameter 0.6 meter which will end up around 1 meter flat 0.4-meter-high elliptical shape.
8	Please confirm the bid documents (BOQ, technical proposal, copy of bid security, Company profile and others) must be send to your email or through the e-tendering website?	All documents must be submitted through UNDP e_tendering tool.
9	the contractor has the right to installing the concrete patch plant at the site location?	The contractor has the right to install patch plant in coordination with End-User resident office.
10	Do we have to submit the Origin and technical data sheet for Admixtures, mineral fillers, pigments and Self-Compacting Concrete with bid documents?	You can submit the origin and technical data sheet for Admixtures, mineral fillers....etc for self-compacting concrete as supporting documents.