



Empowered lives.
Resilient nations.

REQUEST FOR QUOTATION (RFQ) for

Renovation of Notary Building in Qayarh -Outside Mosul

IRQ-RFQ 034-18	January 21, 2018
Renovation of Notary Building in Qayarh - Outside Mosul	REFERENCE: IRQ-RFQ 034-18

Dear Sir / Madam:

We kindly request you to submit your quotation for **Renovation of Notary Building in Qayarh -Outside Mosul**, as detailed in **Annex 1** of this RFQ. When preparing your quotation, please be guided by the form attached hereto as **Annex 2**.

The bidders are advised to conduct the physical site visit for complete understanding of Scope of Work prior sending the formal bid to UNDP. The site visit will be conducted on **24 January 2017** between **10:00 a.m. until 01.00 p.m. (Iraq Time)**.

Focal Person: Engineer Saad Ahmed, email: saad2007hmd@yahoo.com; Cell: 07508207840

Documents uploaded in the system as part of your quotation must be free from any form of virus or corrupted contents, or the quotations shall be rejected.

It shall remain your responsibility to ensure that your quotation is submitted on or before the deadline [**2:00 PM (Iraq Local Time), Sunday, February 04, 2018**] indicated by UNDP in the e-Tendering system. Bids must be submitted in the online e-Tendering system in the following link: <https://etendering.partneragencies.org> using your username and password. If you have not registered in the system before, you can register now by logging in using

username: event.guest

password: why2change

And follow the registration steps as specified in the system user guide uploaded along with the Tender notice

Please take note of the following requirements and conditions pertaining to the supply of the abovementioned good/s:

Delivery Terms; [INCOTERMS 2010] <i>(Pls. link this to price schedule)</i>	DAP
Exact Address/es of Delivery Location/s (identify all, if multiple)	As detailed in the Scope of Work (SOW) under Annex 1
Latest Expected Delivery Date and Time; <i>(if delivery time exceeds this, quote may be rejected by UNDP)</i>	<input checked="" type="checkbox"/> Within 60 Calendar Days from the date of signing the Contract.
Preferred Currency of Quotation:	<input checked="" type="checkbox"/> United States Dollars.
After-sales services required:	<input checked="" type="checkbox"/> Warranty for a minimum period of 1 Year for supplied Equipment's; <input checked="" type="checkbox"/> Defect Liability Period for 6 months from the date of issuance of substantial completion certificate inclusive executing the outstanding snag list, if any.
Deadline for the Submission of Quotation:	<p>Date and Time: 2:00 PM (Iraq Local Time), Sunday, February 04, 2018</p> <p>PLEASE NOTE: -</p> <p>1. Date and time visible on the main screen of event (on e-tendering portal) will be final and prevail over any other closing time indicated elsewhere, in case they are different. It is the responsibility of the bidder to make sure bids are submitted within this deadline. UNDP will not accept any bid that is not submitted directly in the system.</p> <p>2. Submit your bid a day prior or well before the closing time. Do not wait until last minute. If you face any issue submitting your bid at the last minute, UNDP may not be able to assist.</p>
All documentations, including catalogs, instructions and operating manuals, shall be in this language:	<input checked="" type="checkbox"/> English.
Documents to be submitted:	<input checked="" type="checkbox"/> Company Profile , which should not exceed fifteen (15) pages, including the list of completed projects and on-going projects with CVs of required personnel; <input checked="" type="checkbox"/> Certificate of Registration of the business , including Articles of Incorporation, or equivalent document if Bidder is a corporation; <input checked="" type="checkbox"/> Properly filled-in and stamped Price Schedules (Annex-II) with signature . The bidders are also required to submit the soft copy in Excel however, in case of error, the signed copy will prevail; <input checked="" type="checkbox"/> Duly completed and stamped compliance sheet along with requested documentation ; <input checked="" type="checkbox"/> Implementation Timetable of the projects by 60 Calendar Days . <input checked="" type="checkbox"/> List of previous contracts and projects executed with values and name of client ;

	<input checked="" type="checkbox"/> Completed & Signed CVs to substantiate the Qualifications of the proposed Key personnel to be assigned to the contract As below: <ul style="list-style-type: none">• Project Manager with a degree in Civil engineering and at least 5 years of experience in which 2 similar projects implemented. CV should be attached• One Electrical Engineer with a degree in Electrical engineering and at least 3 years of experience in which 2 similar projects implemented. CV should be attached.• One Mechanical Engineer with a degree in Mechanical engineering and at least 3 years of experience in which 2 similar projects implemented. CV should be attached.														
Period of Validity of Quotes starting the Submission Date:	<input checked="" type="checkbox"/> 90 days. In exceptional circumstances, UNDP may request the Vendor to extend the validity of the Quotation beyond what has been initially indicated in this RFQ. The Proposal shall then confirm the extension in writing, without any modification whatsoever on the Quotation.														
Manner of Submitting Bid:	Online bidding in E-tendering module; https://etendering.partneragencies.org														
Partial Quotes:	<input checked="" type="checkbox"/> Not allowed.														
Payment Terms:	<table><tr><th>SN</th><th>Item / Description / Milestone</th><th>Percentage of Payment</th></tr><tr><td>1</td><td>Payment upon completion of substantial works, duly certified by the UNDP Engineer.</td><td>90%</td></tr><tr><td>2</td><td>Retention money will be deducted from the payment and will be return upon Certificate of final completion (Completion of Defects Liability Period) inclusive executing the outstanding snag list, if any.</td><td>10%</td></tr><tr><td colspan="2">Total</td><td>100%</td></tr></table>			SN	Item / Description / Milestone	Percentage of Payment	1	Payment upon completion of substantial works, duly certified by the UNDP Engineer.	90%	2	Retention money will be deducted from the payment and will be return upon Certificate of final completion (Completion of Defects Liability Period) inclusive executing the outstanding snag list, if any.	10%	Total		100%
SN	Item / Description / Milestone	Percentage of Payment													
1	Payment upon completion of substantial works, duly certified by the UNDP Engineer.	90%													
2	Retention money will be deducted from the payment and will be return upon Certificate of final completion (Completion of Defects Liability Period) inclusive executing the outstanding snag list, if any.	10%													
Total		100%													
Liquidated Damages:	0.5% of the contract value for one-week delay to maximum 10% of the contract value with possibility to cancel the Purchase Order.														
Evaluation Criteria	<input checked="" type="checkbox"/> Minimum 5 years’ experience in similar works like construction/renovation; <input checked="" type="checkbox"/> Technical responsiveness/Full compliance to BOQ requirements; <input checked="" type="checkbox"/> Technical responsiveness/Full compliance of equipment part of BOQ; <input checked="" type="checkbox"/> Minimum 2 similar works completed successfully. (Please provide the name and contract details for reference check); <input checked="" type="checkbox"/> Annex-1 Form duly completed and signed for the entire requirement. <input checked="" type="checkbox"/> Full acceptance of the Contract General Terms and Conditions [this is mandatory criteria and cannot be deleted regardless of the nature of services required; <input checked="" type="checkbox"/> Full Compliance with delivery timeframe of 60 calendar days. <input checked="" type="checkbox"/> Signed CVs of proposed key personnel as per the requirement.														
UNDP will award to:	<input checked="" type="checkbox"/> One Supplier.														
Type of Contract to be Signed:	<input checked="" type="checkbox"/> Contract for Civil Works.														

Conditions for Release of Payment:	<input checked="" type="checkbox"/> 100 % upon successful completion of all services and acceptance by UNDP and end user.
Annexes to this RFQ:	<input checked="" type="checkbox"/> Scope of Work, BOQ and related design drawings (<i>Annex 1</i>); <input checked="" type="checkbox"/> Form for Submission of Quotation (<i>Annex 2</i>); <input checked="" type="checkbox"/> General Terms and Conditions / Special Conditions (<i>Annex 3</i>). Non-acceptance of the terms of the General Terms and Conditions (GTC) shall be grounds for disqualification from this procurement process.
Contact Person for Inquiries; (Written inquiries only)	Mostaq Ahmed Procurement Analyst mostaq.ahmed@undp.org Any delay in UNDP's response shall be not used as a reason for extending the deadline for submission, unless UNDP determines that such an extension is necessary and communicates a new deadline to the Proposers.

¹ UNDP reserves the right not to award the contract to the lowest priced offer, if the second lowest price among the responsive offer is found to be significantly more superior, and the price is higher than the lowest priced compliant offer by not more than 10%, and the budget can sufficiently cover the price difference. The term "more superior" as used in this provision shall refer to offers that have exceeded the pre-determined requirements established in the specifications.

² Where the information is available in the web, a URL for the information may simply be provided.

3- This contact person and address is officially designated by UNDP. If inquiries are sent to other person/s or address/es, even if they are UNDP staff, UNDP shall have no obligation to respond nor can UNDP confirm that the query was received.

Goods and works offered shall be reviewed based on completeness and compliance of the quotation with the minimum specifications described above and any other annexes providing details of UNDP requirements.

The quotation that complies with all of the specifications, requirements and offers the lowest price, as well as all other evaluation criteria indicated, shall be selected. Any offer that does not meet the requirements shall be rejected.

Any discrepancy between the unit price and the total price (obtained by multiplying the unit price and quantity) shall be re-computed by UNDP. The unit price shall prevail and the total price shall be corrected. If the supplier does not accept the final price based on UNDP's re-computation and correction of errors, its quotation will be rejected.

After UNDP has identified the lowest price offer, UNDP reserves the right to award the contract based only on the prices of the goods in the event that the transportation cost (freight and insurance) is found to be higher than UNDP's own estimated cost if sourced from its own freight forwarder and insurance provider.

At any time during the validity of the quotation, no price variation due to escalation, inflation, fluctuation in exchange rates, or any other market factors shall be accepted by UNDP after it has received the quotation. At the time of award of Contract or Purchase Order, UNDP reserves the right to vary (increase or decrease) the quantity of services and/or goods, by up to a maximum twenty-five per cent (25%) of the total offer, without any change in the unit price or other terms and conditions.

Any Purchase Order that will be issued as a result of this RFQ shall be subject to the General Terms and Conditions attached hereto. The mere act of submission of a quotation implies that the vendor accepts without question the General Terms and Conditions of UNDP herein attached as Annex IV.

UNDP is not bound to accept any quotation, nor award a contract/Purchase Order, nor be responsible for any costs associated with a Supplier's preparation and submission of a quotation, regardless of the outcome or the manner of conducting the selection process. Please be advised that UNDP's vendor protest procedure is intended to afford an opportunity to appeal for persons or firms not awarded a purchase order or contract in a competitive procurement process. In the event that you believe you have not been fairly treated, you can find detailed information about vendor protest procedures in the following link:

<http://www.undp.org/content/undp/en/home/operations/procurement/protestandsanctions/>

UNDP encourages every prospective Vendor to avoid and prevent conflicts of interest, by disclosing to UNDP if you, or any of your affiliates or personnel, were involved in the preparation of the requirements, design, specifications, cost estimates, and other information used in this RFQ. UNDP implements a zero tolerance on fraud and other proscribed practices, and is committed to identifying and addressing all such acts and practices against UNDP, as well as third parties involved in UNDP activities. UNDP expects its suppliers to adhere to the UN Supplier Code of Conduct found in this link: http://www.un.org/depts/ptd/pdf/conduct_english.pdf

Thank you and we look forward to receiving your quotation.

Sincerely your



Anas Fayyad Qarman,
Operations Manager, Service Center
UNDP, Iraq.

1.1. SCOPE of WORK (SOW)

1.2. BILL OF QUANTITY (BOQ)

1.3. DRAWINGS

1.1. SCOPE OF WORK (SOW):

Renovation of Notary Building in Qayarh -Outside Mosul

1.1.1. Project background

The purpose of the renovation Notary building is to bring legal life to its origin, the Notary building will serve the related ministry of justice in Qayyra and will help residents on issuing of all necessary legal documents.

1.1.2. Location

The project located in (Qayara), Ninewa Governorate.
And the coordinate is (35.79115,43.29130)

1.1.3. Brief description of the building

Notary building has been built on a plot of land of around 500 m2, with a 2m height fence, the building is made up of two large rooms, 6 rooms, with two office room, also it includes two sets of toilets, the building made of concrete block walls with concrete slab for the roof,

1.1.4. Brief description of the damage

The Notary building exposed to gunfire during the war, were Most of its walls and fence have cracks, steel doors and wooden doors were removed or damaged, the bathrooms needs cleaning, most of the suspended ceiling fallen or collapsed and need replacement, the building need re-painting from inside to outside, the sanitary units is damaged or looted, need new provision, the main gate is missing and other minor defects that can be repaired by gypsum or cement plastering.

1.1.5. Brief description of the Works

The scope of work includes, repairing for the cracks on the walls by cement plastering and gypsum plastering, later to be painted by emulsion and skirting by oil paint as this building serve huge number of population, missing and/or damaged doors will be repaired and replaced, steel windows need to be repaired by cleaning, replacing broken clear glass with oil painting after removing the damaged parts, new suspended ceiling to be installed for the damaged areas, sanitations such as water tanks, lavatory stands with valves need to be installed, a new cabin for the guards was added to secure the building. And as indicated in the B.O.Q.

1.2. BILL OF QUANTITY (BOQ):

Renovation of Notary Building in Qayarh

General Specification

- 1- All the materials supplied by the contractor must be according to Iraq's standard Specifications
- 2- The contractor must provide samples, catalogues and specification of materials for testing and approval by the site engineer
- 3- Contractor must pay the cost for samples including any laboratory tests, both inside and outside the country as required
- 4- The price of works includes all job requirements as per Iraq's standard specification.
- 5- The contractor must provide PPE (Personal Protective Equipment) for all laborer's, personnel, engineers and possible visitors to the site

	Item Description	Unit	Qty
	CIVIL WORKS		
1	Site preparation: Supply of materials, tools, machineries and manpower for site preparation by cleaning and dumping of all debris and rubble to a site approved by local authorities. All needed works to complete the job, shall be included within the price	LS	1
2	Masonry works (walls): Supply of materials, tools and manpower to build walls, by using solid blocks (15x20x40cm), width 20cm and cement mortar (1:3). The wall shall be leveled vertically and horizontally. All needed works to complete the job will be included within the price.	m ²	40
3	Gypsum plastering: Supply of all necessary materials, tools and manpower to remove damaged and burned gypsum plastering of internal walls & roofs and re-plaster with new gypsum plastering in 2 layers minimum thickness 15mm. The work includes repairing of wall cracks by removing the damaged gypsum plastering 25cm at each side of the crack, then filling the cracks with cement mortar 1:3 and using SBR at a rate of 200gr per m ² , later putting a layer of plastic mesh on the area under the gypsum plastering. All needed works to complete the job, will be included within the price.	m ²	100
4	Cement plastering: Supply materials, tools and manpower to repair wall cracks. The work includes removal of damaged cement plastering on external walls & fence, 25cm at each side of the crack, filling the cracks with crack filler and cement mortar 1:3 by using SBR at a rate of 200gr per m ² . Including applying a layer of chicken wire on the area with 3 layers of cement plastering 1:3 mix ratio. Price of the work shall include all requirements to complete the job.	m ²	400
5	Emulsion painting: Supply of materials, tools and manpower to paint the interior walls and ceilings, with 3 layers of emulsion painting. The job includes cleaning the walls and ceilings, removing the dirt and dust, repairing all the cracks and filling all the holes before painting. All needed works to complete the job, shall be included within the price	m ²	600
6	Plastic painting: Supply of materials, tools and manpower to paint walls from outside, with three layers of plastic (silicon water proof) paint. The job includes cleaning the walls and ceilings, removing the dirt and dust, repairing all the cracks and filling all the holes before painting. All needed works to complete the job, shall be included within the price.	m ²	1,500
7	Oil Painting: Supply of materials, tools and manpower to paint the steel doors, windows, and internal walls with a paint (1.20m height) for skirting using 3 layers of oil paint.	m ²	400

	The job includes cleaning the walls and ceilings, removing the dirt and dust, repairing all the cracks and filling all the holes before painting. All needed works to complete the job shall be included within the price.		
8	Limestone frame: Supply of materials, tools and manpower to install limestone frame for doors and windows, width 40cm and thickness 5cm, by using cement mortar 1:3 and including horizontal and vertical levelling. The price includes dumping of all debris and rubble to a site approved by local authorities, as well as all needed works to complete the job.	ml	110
9	PVC windows with burglar: Supply of materials, tools and manpower to install PVC windows (frames of minimum 60 mm width). The price of works includes anti-insects wire mesh, handles, crystal clear class 4mm thickness, antirust painting and two layers of oil painting, steel burglar made by square steel bar of 12mm every 15cm and the outer frame of angle section 50x50x2mm. All needed work to complete the job will be included within the price.	m ²	40
10	Repairing of roofing system: Supply of materials, tools and manpower to remove all the damaged roofing layers and dumping of all the rubble to a site approved by local authorities, and providing the roofing layers as follows (applying water-proofing flint coats, two layers of bitumen felt 4mm, water-proofing flint coats, laying of compressed Styrofoam 5cm and applying the concrete roof tiles (mosaic 30x30cm), refilling the joints with mastic and giving the slope for water drainage. All needed work to complete the job will be included within the price. See attached drawing.	m ²	300
11	PVC Doors with Frame (H2.1xW1.0)m: Supply of materials, tools and manpower to install PVC doors with frame. The PVC section should be wide section. The lower 1.0m portion of the door to be covered by PVC sheets and the upper portion will be covered by frosted glass 6mm. The price includes hinges, handles, locks and frosted glass (6mm) . All needed works to complete the job, will be included within the price. See attached drawing.	EA	3
12	Granite steps/treads for stair: Supply of materials, tools and manpower for removing old steps and placing new granite steps, 3 cm thickness for the tread, riser of 2cm thickness, 30cm width and 1.2m length. By using cement mortar (1:3) and filling joints with white cement mortar. All needed works to complete the job, will be included within the price.	EA	15
13	Plastic wall coverings : Supply of materials, tools and manpower to install plastic sheet of 30cm width, for walls covering. Including U, L sections and all necessary accessories. All needed works to complete the job, will be included within the price.	m ²	80
14	Steel door (W1.1xH2.1m): Supply of materials, tools and manpower to install steel door, double face doors (W1.1xH2.1m), by using plate gauge 16(1.58mm) and steel frame (25x25x3)mm, with a layer of styropore to be placed between the two faces. The price includes door lock, mortise, fixing a stopper on the floor or the wall, painting by using 2 layers anti-rust and 3 layers of oil painting, accesories and all needed works to complete the job. See attached drawings	EA	3
15	Sliding steel door (W5xH2m): Supply of materials, tools and manpower to install sliding steel gate of dimensions (W5xH2m), consisting on two parts, by using plate gauge 18 and steel pipe 50x50x2mm. Including door handles and railing chanel. Price of the work shall include painting of steel door with anti-rust and two coats of oil paints with all requirements to complete the job. See attached drawing	EA	1
16	Aluminum Handrails: Supplying and installation of aluminum handrails (height of 80cm) with all accessories. The price includes removing the old steel handrails and providing bigger column sections at the beginning, turning and at the ends. All needed work to complete the job will be included within the price. See attached annex.	ml	60

1 7	Ceramic for walls: Supply of materials, tools and manpower to place a new ceramic 30x60 cm with cement mortar. The price of works includes expansion joints, the removal of old damaged ceramic, gypsum plastering, horizontal and vertical leveling, and dumping of all debris to a site approved by local authorities, in case it is needed, as well as all needed works to complete the job.	m ²	125
1 8	Wooden doors (W1xH2.1m): Supply tools, materials and manpower to remove damaged wooden doors and to install new wooden doors of dimensions (1x2.1m). Price of works shall include painting with 2 layers of painting, installation of Frame ,install cover on the frame , door handles and locks, as well as all needed works to complete the job. See attached drawings	EA	6
1 9	Skirting: Supply of materials, tools and manpower to place ceramic skirting of 10cm height by using cement mortar. The price includes filling the joints with white cement. All needed work to complete the job will be included within the price.	ml	150
2 0	Ceramic for flooring: Supply of materials, tools and manpower to place a new anti-slip ceramic tiles of dimensions 60x60 cm with cement mortar. The price of works includes expansion joints, levelling and the removal of old damaged ceramic and dumping of all debris to a site approved by local authorities, in case it is needed, as well as all needed works to complete the job.	m ²	350
2 1	Plastic suspended ceiling Supply materials, tools and manpower to install false ceiling 60x60 cm (plastic boards), 10 mm thickness, by using necessary accessories L, T sections, galvanized steel wire 2mm for fixing with the roof by screws The price includes the removal of old damaged false ceiling, dumping of all debris to a site approved by local authorities, in case it is needed, as well as all needed works to complete the job. See attached drawings	m ²	300
2 2	Flag pole : Supply materials , tools and man power to install Flag pole of 6 m high by using 2.5" (64cm) pipe. Price of the work shall include anti rust and three layers oil painting, as well as all needed works to complete the job.	EA	1
2 3	Billboard: Supply of materials, tools and manpower to install billboard made of frame of size 3x1 m, including LED printed sticker. The frame shall be made of square pipe section 4x4cm. Price of the work shall include all requirements to complete the job.	EA	1
SUB TOTAL FOR CIVIL WORKS			
SANITARY WORKS			
1	Water tank: Supply of necessary materials, tools and manpower for installing galvanized water tank of 1400 liter of capacity. Cylindrical shape and with plate gauge 16, supported by steel base made with 50mm (2") angle shape,painting 2 layer with anti-rust and oil paint ,including the connection of the inlet and outlet pipes. The price of works includes all piping and fittings, valves, float valves, accessories as well as all needed works to complete the job.	EA	4
2	Wash basin: Supply of materials , tools and manpower to install ceramic wash basin with stand, mixer taps, valves, mirror (60x50cm) and all fittings with complete water connections. All needed work to complete the job will be included within the price.	EA	4


3	Eastern toilet: Supply of materials, tools and manpower to remove the damaged eastern toilet pan and to install new ceramic eastern toilet. Including siphon(flush tank), gully trap Ø100mm (4"), flexible hose and water connections. All needed work to complete the job will be included within the price.	EA	2
4	Galvanized iron water pipes (1/2") and (3/4)": Supply and install galvanized water pipes (½)"and (¾)"diameter. The price includes all fittings and accessories, excavation, backfilling, manhole, painting the pipes by using anti rust then isolate all hot water pipes by using arm flex and thermal tape and Teflon seal for connections of cold and hot water pipes. All needed works to complete the job will be included within the price.	LS	1
5	PVC pipe 4" (Ø 100mm): Supply, installation, testing and commissioning of PVC 4"(100mm) 6 bar for drainage and ventilation pipes down to manholes with all required fittings including excavation, back filling, incasing with sulphate resistant cement concrete and roof vent caps. All needed works to complete the job, will be included within the price.	LS	1
6	Roof Drain: Supply of materials, tools and manpower to remove damaged water drain and install new galvanized steel pipe 73mm (3") with all connections and accessories to fix with the roof and wall. All needed works to complete the job, will be included within the price. See attached drawings	ml	30
7	Water pump: Supply materials, tools and manpower to connect water pump (1hp), Q=3m³/Hrs., H=60m with, ball valve and all fitting and accessories for connection. The price of works includes all accessories needed, as well as all needed works to complete the job.	EA	1
8	Septic Tank: Supply of materials, tools and manpower to build septic tank. The price of works includes soil excavations, casting the foundation using (C25Mpa) concrete. 20 cm thickness and by using caliphate resistant cement, build the walls of 40 cm width with solid blocks (15x20x40cm) and cement mortar (1:3), casting reinforced concrete slab (20cm) with two layers of 12mmØ spaced @20cm both directions and installation of two manhole steel covers of (60 x 60) cm and supplying maintenance ladders. All needed work to complete the job will be included within the price. See attached drawing	EA	1
SUB TOTAL FOR MECHANICAL WORKS			
ELECTRICAL WORKS			
The following items shall include supply, replace, install, connect and commission lighting points and power socket outlets, including PVC conduits and fittings, laying wires/ cables, switches or socket outlet up to its sub-panel board. In case the conduits and /or wires are already exist than contractor must ensure to check thoroughly and make proper replacement for defective items if any. All the necessary equipment/items (if any) must be earthed properly with specific wire/cable size.			
1	Socket Switch(13A): Supplying & fixing of combine 13A, 5 pin universal switch-socket with shuttered & indicator outlet, on PVC molded tough surface box, with 1.0kV grade, 3x 2.5 mm² PVC insulated copper conductor laying through PVC conduit (Dia 20 mm) pipe with all accessories. The price includes supplying, installing, connecting, laying and commissioning drilling, cutting to complete works as required.	EA	40
2	Light Switch: Supply, install, connect and commission of (230VAC/6A) (single, double, triple and quadruple) light switches using single core wire (2*1.5mm²) laid inside PVC pipe (20mm dia) with all accessories. The price includes supplying, installing, connecting, laying and commissioning drilling, cutting to complete works as required.	EA	5

3	Fluorescent Lighting: Supplying, Installation, testing and commissioning of prewired fluorescent fittings of all pendant type complete set and tube rod 19mm dia(4feet) connecting 6 Amps switch with 1.0 kV grade, 2x 1.5 mm ² PVC insulated copper cable laid through PVC conduit/casing capping with all accessories. The price includes supplying, installing, connecting, laying and commissioning drilling, cutting to complete works as required.	EA	24
4	Ceiling Fan: Supply, connect and install 230 VAC ceiling fan size 60x60 cm (for false ceiling) with remote control and multi speeds, connecting with 2 x 1.5 mm ² 1.0KV grade PVC insulated copper conductor with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	6
5	Bracket waterproof wall: Supplying & Installing of bracket waterproof wall prewired outdoor lighting luminaries suitable for GLS lamp 230VAC/23 watts complete with all accessories such as base, LED drive & LED bulb, glass, reflector, louvered, connecting with one way 6 Amps switch and 1.0KV grade 2 x 1.5 mm ² PVC insulated copper conductor with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	10
6	Main Board: Supply, install, test, commission prefabricated Main Distribution Board (MDB) (80cm x 60cm x 40cm) incorporated in DIN bar with following incoming and outgoing as below: The price includes supplying, installing, connecting, laying and commissioning to complete works as required. A - [(1 No.) 100A, MCCB type, breaking capacity 36KA, 4 pole 415 volt A.C]. B - [(1 No.) 25A, 1Ph. MCB type]. C - (1 No.) Voltmeter (0- 400 V) with selector switch (all Ph-Ph and Ph -N). D - (1 Set) Ammeter (0 -200 A), 100/5A with required CTs. E - (1 No.)Hertz meter (48- 52)Hz. F - (1 No.) selector switch. (ON & OFF position) G - (3 No.) Indicator lamp 220VAC. H - Three-phase, four wires Kilowatt-hour meter I - (4 strips Copper Bus-Bar 60 cm length 200A., for three phase lines and neutral) with separate earth strip	EA	1
7	Exhaust fan: Supplying, fixing and connecting of exhaust fan 240 volt A.C 1400 rpm & 450mm sweep (30-35cm) price includes using 1.0KV grade 2x1.5 mm ² PVC insulated copper conductor, one way 6 A/220VAC switch with all accessories for necessary cutting, drilling, testing etc. to complete works as required.	EA	2
8	Sub Distribution Boards: Supplying, installing, testing and commissioning of for 24 ways, TPN DB (DIN type, horizontal/vertical) with single door complete set to accommodate incoming miniature circuit breaker (MCB) triple pole, 1 x 100 Amps, 415-volt A.C 16 kA, and outgoing SP MCB 24 x 32 Amps on/in prefabricated MS surface /MS cubical control panel board with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	1
9	Electrical water boiler: Supply, install, connect, and commission electrical heater 250 Liter capacity 3 kW, with complete fittings & accessories connecting 1.0kV grade, 3x4mm ² PVC insulated copper conductor with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	2
10	Electrical bell: Supplying and Installing of electrical call bell 230 VAC/5 W connecting with 2x 1.5 mm ² , 1.0KV grade cable, PVC insulated copper conductor in PVC surface conduit and one way 6 Amps bell switch with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	1


1 1	Power Cable (4x25 mm²): Supplying, laying and connecting 1.0KV grade, 4 core 25 mm ² PVC insulated and sheathed power copper, un-armoured extend from the main pole to the main board as required. Price includes supplying, installing, laying, testing and commissioning, include (cable termination with lugs at both end) to complete the work as required.	ml	75
1 2	Split Unit Air-Conditioning: Supply, install, connect and commission wall mounted Split unit Air-conditioning (Cool & Heat) 2 ton(24000btuh) using 1.0 kV grade, PVC insulated copper cable 2x2.5mm ²), laid through PVC conduit pipe (20 mm dia)/cable tray with one way 25 A/230VAC switch with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required. (Attached GTP/Compliance sheet)	EA	7
1 3	Spot Lighting: Supply, install, connect and commission spot lighting fixtures, LED (230VAC/18 W), LED type, metal shape (water proof). The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	60
1 4	Power Cable (4X35 mm²): Supply, install, test and lay (4X35 mm ²) PVC sheath, Un-Armoured copper conductors.(From the Generator Main board to the main board of the building (laid through PVC pipe (4" dia) with cable termination lugs in both sides with all accessories. Price includes supplying, installing, laying, testing and commissioning, include (cable termination with lugs at both end) to complete the work as required.	ml	50
SUB TOTAL FOR ELECTRICAL WORKS			

1.3. DRAWINGS


1.3.1. Detail of Roofing System



1.3.2 Detail of PVC Doors



1.3.3. Detail of Double face Steel Door & External Doors



The drawing illustrates the main frame and internal frame of a sliding door. The main frame is shown in two views: a top view and a side view. The top view shows a rectangular frame with a width of 2.50m and a height of 2.00m. The side view shows the frame's profile with a height of 2.00m. The internal frame is shown in a side view with a height of 2.00m. The main frame is labeled 'Main Frame Rec. Tube 75x50x3mm' and the internal frame is labeled 'Internal Frame Rec. Tube 50x50x3mm'. The main frame is shown with a green textured area representing the door panel. The side view shows the door panel with a green textured area and a white area representing the door's edge. The main frame is shown with a green textured area and a white area representing the door's edge. The side view shows the door panel with a green textured area and a white area representing the door's edge. The main frame is shown with a green textured area and a white area representing the door's edge. The side view shows the door panel with a green textured area and a white area representing the door's edge.

Channel section 80x45x6mm to be fixed with the walls

Galvanized steel sheet (page 18(1.41mm)) for both faces

Channel section 80x45x6mm to be fixed with the floor

ball bearing

ball bearing

ball bearing

ball bearing

2.50

2.00

2.50

2.00

Main Frame Rec. Tube 75x50x3mm

Internal Frame Rec. Tube 50x50x3mm


Main Frame of the sliding door

Typical Drawings for Renovation	
Drawn by: Soran Rostum Aziz	
Sheet Title:	
Detail of Sliding Doors, Dx2.0m	
Scale: NTS	Date:
DWG No.	


1.3.5. Photo of Stair




1.3.6. Detail of Single Wooden Door



1.3.7. Detail of Suspended Ceilings



1.3.9. Detail of Roof Drain



A. Garman

Anas Fayyad Garman
Operations Manager-Service Center
UNDP Iraq

FORM FOR SUBMITTING SUPPLIER'S QUOTATION¹*(This Form must be submitted only using the Supplier's Official Letterhead/Stationery²)*

We, the undersigned, hereby accept in full the UNDP General Terms and Conditions, and hereby offer to supply the items listed below in conformity with the specification and requirements of UNDP as per RFQ Reference No. **IRQ_RFQ-034/2018**:

TABLE 1: Offer to Comply with Other Conditions and Related Requirements

Information pertaining to our Quotation are as follows:	Your Responses		
	<i>Yes, we will comply</i>	<i>No, we cannot comply</i>	<i>If you cannot comply, pls. indicate counter proposal</i>
Contract Duration: Substantial Completion: 60 Calendar Days from the issuance of the contract Defect Liability Period: 06 Months from the Issuance of Substantial Completion Certificate			
Delivery Term of 60 days: DAP			
Validity of Quotation: 90 Days			
Warranty: Minimum one (1) year warranty for supplied equipment			
Printed brochures and product catalogues and specification relevant to the goods			
Acceptance of all Provisions of the UNDP General Terms and Conditions:			
We confirm that our company is not included in the UN 1267/1989 List or the UN Ineligibility List or in all of UNDP's list of suspended and removed vendors.			

Company Stamp and Signature: -----

Official E-mails of the Company: -----

Date: -----

¹ This serves as a guide to the Supplier in preparing the quotation and price schedule.

² Official Letterhead/Stationery must indicate contact details – addresses, email, phone and fax numbers – for verification purposes

TABLE 2: Offer to Supply Goods Compliant with Technical Specifications and Requirements

Renovation of Notary Building in Qayarh					
General Specification 1- All the materials supplied by the contractor must be according to Iraq's standard Specifications 2- The contractor must provide samples, catalogues and specification of materials for testing and approval by the site engineer 3- Contractor must pay the cost for samples including any laboratory tests, both inside and outside the country as required 4- The price of works includes all job requirements as per Iraq's standard specification. 5- The contractor must provide PPE (Personal Protective Equipment) for all laborer's, personnel, engineers and possible visitors to the site					
	Item Description	Unit	Qty	Price\$	Total \$
	CIVIL WORKS				
1	Site preparation: Supply of materials, tools, machineries and manpower for site preparation by cleaning and dumping of all debris and rubble to a site approved by local authorities. All needed works to complete the job, shall be included within the price	LS	1		
2	Masonry works (walls): Supply of materials, tools and manpower to build walls, by using solid blocks (15x20x40cm), width 20cm and cement mortar (1:3). The wall shall be leveled vertically and horizontally. All needed works to complete the job will be included within the price.	m ²	40		
3	Gypsum plastering: Supply of all necessary materials, tools and manpower to remove damaged and burned gypsum plastering of internal walls & roofs and re-plaster with new gypsum plastering in 2 layers minimum thickness 15mm. The work includes repairing of wall cracks by removing the damaged gypsum plastering 25cm at each side of the crack, then filling the cracks with cement mortar 1:3 and using SBR at a rate of 200gr per m ² , later putting a layer of plastic mesh on the area under the gypsum plastering. All needed works to complete the job, will be included within the price.	m ²	100		
4	Cement plastering: Supply materials, tools and manpower to repair wall cracks. The work includes removal of damaged cement plastering on external walls & fence, 25cm at each side of the crack, filling the cracks with crack filler and cement mortar 1:3 by using SBR at a rate of 200gr per m ² . Including applying a layer of chicken wire on the area with 3 layers of cement plastering 1:3 mix ratio. Price of the work shall include all requirements to complete the job.	m ²	400		
5	Emulsion painting: Supply of materials, tools and manpower to paint the interior walls and ceilings, with 3 layers of emulsion painting. The job includes cleaning the walls and ceilings, removing the dirt and dust, repairing all the cracks and filling all the holes before painting. All needed works to complete the job, shall be included within the price	m ²	600		
6	Plastic painting: Supply of materials, tools and manpower to paint walls from outside, with three layers of plastic (silicon water proof) paint. The job includes cleaning the walls and ceilings, removing the dirt and dust, repairing all the cracks and filling all the holes	m ²	1,500		

	before painting. All needed works to complete the job, shall be included within the price.				
7	Oil Painting: Supply of materials, tools and manpower to paint the steel doors, windows, and internal walls with a paint (1.20m height) for skirting using 3 layers of oil paint. The job includes cleaning the walls and ceilings, removing the dirt and dust, repairing all the cracks and filling all the holes before painting. All needed works to complete the job shall be included within the price.	m ²	400		
8	Limestone frame: Supply of materials, tools and manpower to install limestone frame for doors and windows, width 40cm and thickness 5cm, by using cement mortar 1:3 and including horizontal and vertical levelling. The price includes dumping of all debris and rubble to a site approved by local authorities, as well as all needed works to complete the job.	ml	110		
9	PVC windows with burglar: Supply of materials, tools and manpower to install PVC windows (frames of minimum 60 mm width). The price of works includes anti-insects wire mesh, handles, crystal clear class 4mm thickness, anti-rust painting and two layers of oil paint, steel burglar made by square steel bar of 12mm every 15cm and the outer frame of angle section 50x50x2mm. All needed work to complete the job will be included within the price.	m ²	40		
10	Repairing of roofing system: Supply of materials, tools and manpower to remove all the damaged roofing layers and dumping of all the rubble to a site approved by local authorities, and providing the roofing layers as follows (applying water-proofing flint coats, two layers of bitumen felt 4mm, water-proofing flint coats, laying of compressed Styrofoam 5cm and applying the concrete roof tiles (mosaic 30x30cm), refilling the joints with mastic and giving the slope for water drainage. All needed work to complete the job will be included within the price. See attached drawing.	m ²	300		
11	PVC Doors with Frame (H2.1xW1.0) m: Supply of materials, tools and manpower to install PVC doors with frame. The PVC section should be wide section. The lower 1.0m portion of the door to be covered by PVC sheets and the upper portion will be covered by frosted glass 6mm. The price includes hinges, handles, locks and frosted glass (6mm). All needed works to complete the job, will be included within the price. See attached drawing.	EA	3		
12	Granite steps/treads for stair: Supply of materials, tools and manpower for removing old steps and placing new granite steps, 3 cm thickness for the tread, riser of 2cm thickness, 30cm width and 1.2m length. By using cement mortar (1:3) and filling joints with white cement mortar. All needed works to complete the job, will be included within the price.	EA	15		
13	Plastic wall coverings: Supply of materials, tools and manpower to install plastic sheet of 30cm width, for walls covering. Including U, L sections and all necessary accessories. All needed works to complete the job, will be included within the price.	m ²	80		

14	Steel door (W1.1xH2.1m): Supply of materials, tools and manpower to install steel door, double face doors (W1.1xH2.1m), by using plate gauge 16(1.58mm) and steel frame (25x25x3) mm, with a layer of styropore to be placed between the two faces. The price includes door lock, mortise, fixing a stopper on the floor or the wall, painting by using 2 layers anti-rust and 3 layers of oil painting, accesories and all needed works to complete the job. See attached drawings	EA	3		
15	Sliding steel door (W5xH2m): Supply of materials, tools and manpower to install sliding steel gate of dimensions (W5xH2m), consisting on two parts, by using plate gauge 18 and steel pipe 50x50x2mm. Including door handles and railing chanel. Price of the work shall include painting of steel door with anti-rust and two coats of oil paints with all requirements to complete the job. See attached drawing	EA	1		
16	Aluminum Handrails: Supplying and installation of aluminum handrails (height of 80cm) with all accessories. The price includes removing the old steel handrails and providing bigger column sections at the beginning, turning and at the ends. All needed work to complete the job will be included within the price. See attached annex.	ml	60		
17	Ceramic for walls: Supply of materials, tools and manpower to place a new ceramic 30x60 cm with cement mortar. The price of works includes expansion joints, the removal of old damaged ceramic, gypsum plastering, horizontal and vertical leveling, and dumping of all debris to a site approved by local authorities, in case it is needed, as well as all needed works to complete the job.	m ²	125		
18	Wooden doors (W1xH2.1m): Supply tools, materials and manpower to remove damaged wooden doors and to install new wooden doors of dimensions (1x2.1m). Price of works shall include painting with 2 layers of painting, installation of Frame, install cover on the frame , door handles and locks, as well as all needed works to complete the job. See attached drawings	EA	6		
19	Skirting: Supply of materials, tools and manpower to place ceramic skirting of 10cm height by using cement mortar. The price includes filling the joints with white cement. All needed work to complete the job will be included within the price.	ml	150		
20	Ceramic for flooring: Supply of materials, tools and manpower to place a new anti-slip ceramic tiles of dimensions 60x60 cm with cement mortar. The price of works includes expansion joints, levelling and the removal of old damaged ceramic and dumping of all debris to a site approved by local authorities, in case it is needed, as well as all needed works to complete the job.	m ²	350		
21	Plastic suspended ceiling Supply materials, tools and manpower to install false ceiling 60x60 cm (plastic boards), 10 mm thickness, by using necessary accessories L, T sections, galvanized steel wire 2mm for fixing with the roof by screws the price includes the removal of old damaged false ceiling, dumping of all debris to a site approved by local authorities, in case it is needed, as well as all needed works to complete the job. See attached drawings	m ²	300		

22	Flag pole : Supply materials , tools and man power to install Flag pole of 6 m high by using 2.5" (64cm) pipe. Price of the work shall include anti rust and three layers oil painting, as well as all needed works to complete the job.	EA	1		
23	Billboard: Supply of materials, tools and manpower to install billboard made of frame of size 3x1 m, including LED printed sticker. The frame shall be made of square pipe section 4x4cm. Price of the work shall include all requirements to complete the job.	EA	1		
SUB TOTAL FOR CIVIL WORKS					
SANITARY WORKS					
1	Water tank: Supply of necessary materials, tools and manpower for installing galvanized water tank of 1400 liter of capacity. Cylindrical shape and with plate gauge 16, supported by steel base made with 50mm (2") angle shape, painting 2 layer with anti-rust and oil paint ,including the connection of the inlet and outlet pipes. The price of works includes all piping and fittings, valves, float valves, accessories as well as all needed works to complete the job.	EA	4		
2	Wash basin: Supply of materials, tools and manpower to install ceramic wash basin with stand, mixer taps, valves, mirror (60x50cm) and all fittings with complete water connections. All needed work to complete the job will be included within the price.	EA	4		
3	Eastern toilet: Supply of materials, tools and manpower to remove the damaged eastern toilet pan and to install new ceramic eastern toilet. Including siphon (flush tank), gully trap Ø100mm (4"), flexible hose and water connections. All needed work to complete the job will be included within the price.	EA	2		
4	Galvanized iron water pipes (1/2") and (3/4)": Supply and install galvanized water pipes (½)" and (¾)" diameter. The price includes all fittings and accessories, excavation, backfilling, manhole, painting the pipes by using anti rust then isolate all hot water pipes by using arm flex and thermal tape and Teflon seal for connections of cold and hot water pipes. All needed works to complete the job will be included within the price.	LS	1		
5	PVC pipe 4" (Ø 100mm): Supply, installation, testing and commissioning of PVC 4"(100mm) 6 bar for drainage and ventilation pipes down to manholes with all required fittings including excavation, back filling, incasing with sulphate resistant cement concrete and roof vent caps. All needed works to complete the job, will be included within the price.	LS	1		
6	Roof Drain: Supply of materials, tools and manpower to remove damaged water drain and install new galvanized steel pipe 73mm (3") with all connections and accessories to fix with the roof and wall. All needed works to complete the job, will be included within the price. See attached drawings	ml	30		
7	Water pump: Supply materials, tools and manpower to connect water pump (1hp), Q=3m³/Hrs., H=60m with, ball valve and all fitting and accessories for connection. The price of works includes all accessories needed, as well as all needed works to complete the job.	EA	1		

8	Septic Tank: Supply of materials, tools and manpower to build septic tank. The price of works includes soil excavations, casting the foundation using (C25Mpa) concrete. 20 cm thickness and by using sulphate resistant cement, build the walls of 40 cm width with solid blocks (15x20x40cm) and cement mortar (1:3), casting reinforced concrete slab (20cm) with two layers of 12mmØ spaced @20cm both directions and installation of two manhole steel covers of (60 x 60) cm and supplying maintenance ladders. All needed work to complete the job will be included within the price. See attached drawing	EA	1		
SUB TOTAL FOR MECHANICAL WORKS					
ELECTRICAL WORKS					
	The following items shall include supply, replace, install, connect and commission lighting points and power socket outlets, including PVC conduits and fittings, laying wires/ cables, switches or socket outlet up to its sub-panel board. In case the conduits and /or wires are already exist than contractor must ensure to check thoroughly and make proper replacement for defective items if any. All the necessary equipment/items (if any) must be earthed properly with specific wire/cable size.				
1	Socket Switch(13A): Supplying & fixing of combine 13A, 5 pin universal switch-socket with shuttered & indicator outlet, on PVC molded tough surface box, with 1.0kV grade, 3x 2.5 mm² PVC insulated copper conductor laying through PVC conduit (Dia 20 mm) pipe with all accessories. The price includes supplying, installing, connecting, laying and commissioning drilling, cutting to complete works as required.	EA	40		
2	Light Switch: Supply, install, connect and commission of (230VAC/6A) (single, double, triple and quadruple) light switches using single core wire (2*1.5mm²) laid inside PVC pipe (20mm dia) with all accessories. The price includes supplying, installing, connecting, laying and commissioning drilling, cutting to complete works as required.	EA	5		
3	Fluorescent Lighting: Supplying, Installation, testing and commissioning of prewired fluorescent fittings of all pendant type complete set and tube rod 19mm dia (4feet) connecting 6 Amps switch with 1.0 kV grade, 2x 1.5 mm² PVC insulated copper cable laid through PVC conduit/casing capping with all accessories. The price includes supplying, installing, connecting, laying and commissioning drilling, cutting to complete works as required.	EA	24		
4	Ceiling Fan: Supply, connect and install 230 VAC ceiling fan size 60x60 cm (for false ceiling) with remote control and multi speeds, connecting with 2 x 1.5 mm² 1.0KV grade PVC insulated copper conductor with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	6		
5	Bracket waterproof wall: Supplying & Installing of bracket waterproof wall prewired outdoor lighting luminaries suitable for GLS lamp 230VAC/23 watts complete with all accessories such as base, LED drive & LED bulb, glass, reflector, louvered, connecting with one way 6 Amps switch and 1.0KV grade 2 x 1.5 mm² PVC insulated copper conductor with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	10		

6	Main Board: Supply, install, test, commission prefabricated Main Distribution Board (MDB) (80cm x 60cmx 40cm) incorporated in DIN bar with following incoming and outgoing as below: The price includes supplying, installing, connecting, laying and commissioning to complete works as required. A - [(1 No.) 100A, MCCB type, breaking capacity 36KA, 4 pole 415 volt A.C]. B - [(1 No.) 25A, 1Ph. MCB type]. C - (1 No.) Voltmeter (0- 400 V) with selector switch (all Ph-Ph and Ph -N). D - (1 Set) Ammeter (0 -200 A), 100/5A with required CTs. E - (1 No.) Hertz meter (48- 52)Hz. F - (1 No.) selector switch. (ON & OFF position) G - (3 No.) Indicator lamp 220VAC. H - Three-phase, four wires Kilowatt-hour meter I - (4 strips Copper Bus-Bar 60 cm length 200A., for three phase lines and neutral) with separate earth strip	EA	1		
7	Exhaust fan: Supplying, fixing and connecting of exhaust fan 240-volt A.C 1400 rpm & 450mm sweep (30-35cm) price includes using 1.0KV grade 2x1.5 mm ² PVC insulated copper conductor, one way 6 A/220VAC switch with all accessories for necessary cutting, drilling, testing etc. to complete works as required.	EA	2		
8	Sub Distribution Boards: Supplying, installing, testing and commissioning of for 24 ways, TPN DB (DIN type, horizontal/vertical) with single door complete set to accommodate incoming miniature circuit breaker (MCB) triple pole, 1 x 100 Amps, 415-volt A.C 16 kA, and outgoing SP MCB 24 x 32 Amps on/in prefabricated MS surface /MS cubical control panel board with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	1		
9	Electrical water boiler: Supply, install, connect, and commission electrical heater 250 Liter capacity 3 kW, with complete fittings & accessories connecting 1.0kV grade, 3x4mm ² PVC insulated copper conductor with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	2		
10	Electrical bell: Supplying and Installing of electrical call bell 230 VAC/5 W connecting with 2x 1.5 mm ² , 1.0KV grade cable, PVC insulated copper conductor in PVC surface conduit and one way 6 Amps bell switch with all accessories. The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	1		
11	Power Cable (4x25 mm²): Supplying, laying and connecting 1.0KV grade, 4 core 25 mm ² PVC insulated and sheathed power copper, un-armoured extend from the main pole to the main board as required. Price includes supplying, installing, laying, testing and commissioning, include (cable termination with lugs at both end) to complete the work as required.	ml	75		
12	Split Unit Air-Conditioning: Supply, install, connect and commission wall mounted Split Unit Air-conditioning (Cool & Heat) 2 ton. (24000btuh) using 1.0 kV grade, PVC insulated copper cable 2x2.5mm ² , laid through PVC conduit pipe (20 mm dia)/cable tray with one way 25 A/230VAC switch with all accessories. The price includes supplying,	EA	7		

	installing, connecting, laying and commissioning to complete works as required. (Attached GTP/Compliance sheet)				
13	Spot Lighting: Supply, install, connect and commission spot lighting fixtures, LED (230VAC/18 W), LED type, metal shape (water proof). The price includes supplying, installing, connecting, laying and commissioning to complete works as required.	EA	60		
14	Power Cable (4X35 mm²): Supply, install, test and lay (4X35 mm ²) PVC sheath, Un-Armoured copper conductors. (From the Generator Main board to the main board of the building (laid through PVC pipe (4" dia) with cable termination lugs in both sides with all accessories. Price includes supplying, installing, laying, testing and commissioning, include (cable trmination with lugs at both end) to complete the work as required.	ml	50		
	SUB TOTAL FOR ELECTRICAL WORKS				0.00
	TOTAL SUMMARY				0.00

TABLE 3: Compliance Sheet for Electrical Equipment (2 Ton AC Unit) - The following Technical data shall be furnished and filled by the bidders:

2 Ton AC unit

No.	Description	Required Specifications	Bidders Offered specification
1	A-C split unit	Wall Type	
2	Make		
3	Brand Name		
4	Tonnage Range	2.0 TR	
5	Power Supply	220 V/single/50HZ	
6	Compressor	DC Inverter / T3	
7	Refrigerant Gas	R410A	
8	Cooling Capacity	24000 BTUH	
9	Filter Type	Micro dust protection filter washable	
10	Starting current:	To be field	
11	Running current	To be field	
12	Operation Range	(-10 to +55) °C	
13	Remote Control	Wireless /LCD type	
14	Noise Level	30 - 35 -40 db	
15	Max ambient temp.	T3	

All other information that we have not provided automatically implies our full compliance with the requirements, terms and conditions of the RFQ.

[Name and Signature of the Supplier's Authorized Person]
[Designation]
[Date]

General Conditions of Contract for Civil Works

1. Definitions
2. Singular and Plural
3. Headings or Notes
4. Legal Relationships
5. General Duties/Powers of Engineer
6. Contractor's General Obligations/Responsibilities
7. Assignment and Subcontracting
8. Drawings
9. Work Book
10. Performance Security
11. Inspection of Site
12. Sufficiency of Tender
13. Programme of Work to be Furnished
14. Weekly Site Meeting
15. Change Orders
16. Contractor's Superintendence
17. Contractor's Employees
18. Setting-Out
19. Watching and Lighting
20. Care of Works
21. Insurance of Works, Etc.
22. Damage to Persons and Property
23. Liability Insurance
24. Accident or Injury to Workmen
25. Remedy on Contractor's Failure to Insure
26. Compliance with Statutes, Regulations, Etc.
27. Fossils, Etc.
28. Copyright, Patents and Other Proprietary Rights, and Royalties
29. Interference with Traffic and Adjoining Properties
30. Extraordinary Traffic and Special Loads
31. Opportunities for Other Contractors
32. Contractor to Keep Site Clean
33. Clearance of Site on Substantial Completion
34. Labour
35. Returns of Labour, Plant, Etc.
36. Materials, Workmanship and Testing
37. Access to Site
38. Examination of Work Before Covering Up
39. Removal of Improper Work and Materials
40. Suspension of Work
41. Possession of Site
42. Time for Completion
43. Extension of Time for Completion
44. Rate of Progress
45. Liquidated Damages for Delay
46. Certificate of Substantial Completion
47. Defects Liability
48. Alterations, Additions and Omissions
49. Plant, Temporary Works and Materials

50. Approval of Materials, Etc., Not Implied
51. Measurement of Works
52. Liability of the Parties
53. Authorities
54. Urgent Repairs
55. Increase and Decrease of Costs
56. Taxation
57. Blasting
58. Machinery
59. Temporary Works and Reinstatement
60. Photographs and Advertising
61. Prevention of Corruption
62. Date Falling on Holiday
63. Notices
64. Language, Weights and Measures
65. Records, Accounts, Information and Audit
66. Force Majeure
67. Suspension by the UNDP
68. Termination by the UNDP
69. Termination by the Contractor
70. Rights and Remedies of the UNDP
71. Settlement of Disputes
72. Privileges and Immunities
73. Security
74. Audit and Investigation
75. Anti-Terrorism

Appendix I: Formats of Performance Security
 Performance Bank Guarantee
 Performance Bond

1. DEFINITIONS

For the purpose of the Contract Documents the words and expressions below shall have the following meanings:

- a) "Employer" means the United Nations Development Programme (UNDP).
- b) "Contractor" means the person whose tender has been accepted and with whom the Contract has been entered into.
- c) "Engineer" means the person whose services have been engaged by UNDP to administer the Contract as provided therein, as will be notified in writing to the Contractor.
- d) "Contract" means the written agreement between the Employer and the Contractor, to which these General Conditions are annexed.
- e) "The Works" means the works to be executed and completed under the Contract.
- f) "Temporary Works" shall include items to be constructed which are not intended to be permanent and form part of the Works.
- g) "Drawings" and "Specifications" mean the Drawings and Specifications referred to in the Contract and any modification thereof or addition thereto furnished by the Engineer or submitted by the Contractor and approved in writing by the Engineer in accordance with the Contract.

- h) "Bill of Quantities" is the document in which the Contractor indicates the cost of the Works, on the basis of the foreseen quantities of items of work and the fixed unit prices applicable to them.
- i) "Contract Price" means the sum agreed in the Contract as payable to the Contractor for the execution and completion of the Works and for remedying of any defects therein in accordance with the Contract.
- j) "Site" means the land and other places on, under, in or through which the Works or Temporary Works are to be constructed.

1. SINGULAR AND PLURAL

Words importing persons or parties shall include firms or companies and words importing the singular only shall also include the plural and vice versa where the context requires.

2. HEADINGS OR NOTES

The headings or notes in the Contract Documents shall not be deemed to be part thereof or be taken into consideration in their interpretation.

3. LEGAL RELATIONSHIPS

The Contractor and the sub-contractor(s), if any, shall have the status of an independent contractor vis-à-vis the Employer. The Contract Documents shall not be construed to create any contractual relationship of any kind between the Engineer and the Contractor, but the Engineer shall, in the exercise of his duties and powers under the Contract, be entitled to performance by the Contractor of its obligations, and to enforcement thereof. Nothing contained in the Contract Documents shall create any contractual relationship between the Employer or the Engineer and any subcontractor(s) of the Contractor.

4. GENERAL DUTIES/POWERS OF ENGINEER

- a) The Engineer shall provide administration of Contract as provided in the Contract Documents. In particular, he shall perform the functions hereinafter described.
- b) The Engineer shall be the Employer's representative vis-à-vis the Contractor during construction and until final payment is due. The Engineer shall advise and consult with the Employer. The Employer's instructions to the Contractor shall be forwarded through the Engineer. The Engineer shall have authority to act on behalf of the Employer only to the extent provided in the Contract Documents as they may be amended in writing in accordance with the Contract. The duties, responsibilities and limitations of authority of the Engineer as the Employer's representative during construction as set forth in the Contract shall not be modified or extended without the written consent of the Employer, the Contractor and the Engineer.
- c) The Engineer shall visit the Site at intervals appropriate to the stage of construction to familiarize himself generally with the progress and quality of the Works and to determine in general if the Works are proceeding in accordance with the Contract Documents. On the basis of his on-site observations as an Engineer, he shall keep the Employer informed of the progress of the Works.
- d) The Engineer shall not be responsible for and will not have control or charge of construction means, methods, techniques, sequences or procedures, or for safety precautions and programs in connection with the Works or the Temporary Works. The Engineer shall not be responsible for or have control or charge over the acts or omissions of the Contractor (including the Contractor's failure to carry out the Works in accordance with the Contract) and of Sub-contractors or any of their agents or employees, or any other persons performing services for the Works, except if such acts or omissions are caused by the Engineer's failure to perform his functions in accordance with the contract between the Employer and the Engineer.
- e) The Engineer shall at all times have access to the Works wherever and whether in preparation or progress. The Contractor shall provide facilities for such access so that the Engineer may perform his functions under the Contract.

- f) Based on the Engineer's observations and an evaluation of the documentation submitted by the Contractor together with the invoices, the Engineer shall determine the amounts owed to the Contractor and shall issue Certificates for Payment as appropriate.
- g) The Engineer shall review and approve or take other appropriate action upon the Contractor's submittals such as Shop Drawings, Product Data and Samples, but only for conformity with the design concept of the Works and with the provisions of the Contract Documents. Such action shall be taken with reasonable promptness so as to cause no delay. The Engineer's approval of a specific item shall not indicate approval of an assembly of which the item is a component.
- h) The Engineer shall interpret the requirements of the Contract Documents and judge the performance thereunder by the Contractor. All interpretations and orders of the Engineer shall be consistent with the intent of and reasonably inferable from the Contract Documents and shall be in writing or in the form of drawings. Either party may make a written request to the Engineer for such interpretation. The Engineer shall render the interpretation necessary for the proper execution of the Works with reasonable promptness and in accordance with any time limit agreed upon. Any claim or dispute arising from the interpretation of the Contract Documents by the Engineer or relating to the execution or progress of the Works shall be settled as provided in Clause 71 of these General Conditions.
- i) Except as otherwise provided in the Contract, the Engineer shall have no authority to relieve the Contractor of any of his obligations under the Contract nor to order any work involving delay in completion of the Works or any extra payment to the Contractor by the Employer, or to make any variations to the Works.
- j) In the event of termination of the employment of the Engineer, the Employer shall appoint another suitable professional to perform the Engineer's duties.
- k) The Engineer shall have authority to reject work which does not conform to the Contract Documents. Whenever, in his opinion, he considers it necessary or advisable for the implementation of the intent of the Contract Documents, he will have authority to require special inspection or testing of the work whether or not such work be then fabricated, installed or completed. However, neither the Engineer's authority to act nor any reasonable decision made by him in good faith either to exercise or not to exercise such authority shall give rise to any duty or responsibility of the Engineer to the Contractor, any subcontractor, any of their agents or employees, or any other person performing services for the Works.
- l) The Engineer shall conduct inspections to determine the dates of Substantial Completion and Final Completion, shall receive and forward to the Employer for the Employer's review written warranties and related documents required by the Contract and assembled by the Contractor, and shall issue a final Certificate for Payment upon compliance with the requirements of Clause 47 hereof and in accordance with the Contract.
- m) If the Employer and Engineer so agree, the Engineer shall provide one or more Engineer's Representative(s) to assist the Engineer in carrying out his responsibilities at the site. The Engineer shall notify in writing to the Contractor and the Employer the duties, responsibilities and limitations of authority of any such Engineer's Representative(s).

5. CONTRACTOR'S GENERAL OBLIGATIONS/RESPONSIBILITIES

6.1. Obligation to Perform in Accordance with Contract

The Contractor shall execute and complete the Works and remedy any defects therein in strict accordance with the Contract, with due care and diligence and to the satisfaction of the Engineer, and shall provide all labor, including the supervision thereof, materials, Constructional Plant and all other things, whether of a temporary or permanent nature, required in and for such execution, completion and remedying of defects, as far as the necessity for providing the same is specified in or is reasonably to be inferred from the Contract. The Contractor shall comply with and adhere strictly to the Engineer's instructions and directions on any matter, touching or concerning the Works.

6.2 Responsibility for Site Operations

The Contractor shall take full responsibility for the adequacy, stability and safety of all site operations and methods of construction, provided that the Contractor shall not be responsible, except as may be expressly

provided in the Contract, for the design or specification of the Permanent Works or of any Temporary Works prepared by the Engineer.

6.3. Responsibility for Employees

The Contractor shall be responsible for the professional and technical competence of his employees and will select for work under this Contract, reliable individuals who will perform effectively in the implementation of the Contract, respect local customs and conform to a high standard of moral and ethical conduct.

6.4. Source of Instructions

The Contractor shall neither seek nor accept instructions from any authority external to the Employer, the Engineer or their authorized representatives in connection with the performance of his services under this Contract. The Contractor shall refrain from any action which may adversely affect the Employer and shall fulfill his commitments with fullest regard for the interest of the Employer.

6.5. Officials Not to Benefit

The Contractor warrants that no official of the Employer has been or shall be admitted by the Contractor to any direct or indirect benefit arising from this Contract or the award thereof. The Contractor agrees that breach of this provision is a breach of an essential term of the Contract.

6.6. Use of Name, Emblem or Official Seal of UNDP or the United Nations

The Contractor shall not advertise or otherwise make public the fact that he is performing, or has performed services for the Employer or use the name, emblem or official seal of the Employer or the United Nations or any abbreviation of the name of the Employer or the United Nations for advertising purposes or any other purposes.

6.7. Confidential Nature of Documents

All maps, drawings, photographs, mosaics, plans, reports, recommendations, estimates, documents and all other data compiled by or received by the Contractor under the Contract shall be the property of the Employer, shall be treated as confidential and shall be delivered only to the duly authorized representative of the Employer on completion of the Works; their contents shall not be made known by the Contractor to any person other than the personnel of the Contractor performing services under this Contract without the prior written consent of the Employer.

6. ASSIGNMENT AND SUBCONTRACTING

7.1. Assignment of Contract

The Contractor shall not, except after obtaining the prior written approval of the Employer, assign, transfer, pledge or make other disposition of the Contract or any part thereof or of any of the Contractor's rights, claims or obligations under the Contract.

7.2. Subcontracting

In the event the Contractor requires the services of subcontractors, the Contractor shall obtain the prior written approval of the Employer for all such subcontractors. The approval of the Employer shall not relieve the Contractor of any of his obligations under the Contract, and the terms of any subcontract shall be subject to and be in conformity with the provisions of the Contract.

7.3. Assignment of Subcontractor's Obligations

In the event of a subcontractor having undertaken towards the Contractor in respect of the work executed or the goods, materials, Plant or services supplied by such subcontractor for the Works, any continuing obligation extending for a period exceeding that of the Defects Liability Period under the Contract, the Contractor shall at any time after the expiration of such Period, assign to the Employer, at the Employer's request and cost, the benefit of such obligation for the unexpired duration thereof.

7. DRAWINGS

8.1. Custody of drawings

The drawings shall remain in the sole custody of the Employer but two (2) copies thereof shall be furnished to the Contractor free of cost. The Contractor shall provide and make at his own expense any further copies required by him. At the completion of the Works, the Contractor shall return to the Employer all drawings provided under the Contract.

8.2. One copy of Drawings to be kept on Site

One copy of the Drawings furnished to the Contractor as aforesaid shall be kept by the Contractor on the Site and the same shall at all reasonable times be available for inspection and use by the Engineer and by any other person authorized in writing by the Engineer.

8.3. Disruption of Progress

The Contractor shall give written notice to the Engineer whenever planning or progress of the Works is likely to be delayed or disrupted unless any further drawing or order, including a direction, instruction or approval, is issued by the Engineer within a reasonable time. The notice shall include details of drawing or order required and of why and by when it is required and of any delay or disruption likely to be suffered if it is late.

8. WORK BOOK

The Contractor shall maintain a Work Book at the Site with numbered pages, in one original and two copies. The Engineer shall have full authority to issue new orders, drawings and instructions to the Contractor, from time to time and as required for the correct execution of the Works. The Contractor shall be bound to follow such orders, drawings and instructions.

Every order shall be dated and signed by the Engineer and the Contractor, in order to account for its receipt.

Should the Contractor want to refuse an order in the Work Book, he shall so inform the Employer, through the Engineer, by means of an annotation in the Work Book made within three (3) days from the date of the order that the Contractor intends to refuse. Failure by the Contractor to adhere to this procedure shall result in the order being deemed accepted with no further possibility of refusal.

The original of the Work Book shall be delivered to the Employer at the time of Final Acceptance of the Works. A copy shall be kept by the Engineer and another copy by the Contractor.

9. PERFORMANCE SECURITY

- a) As guarantee for his proper and efficient performance of the Contract, the Contractor shall on signature of the Contract furnish the Employer with a Performance Security issued for the benefit of the Employer. The amount and character of such security (bond or guarantee) shall be as indicated in the Contract.
- b) The Performance Bond or Bank Guarantee must be issued by an acceptable insurance company or accredited bank, in the format included in Appendix I to these General Conditions, and must be valid up to twenty-eight days after issuance by the Engineer of the Certificate of Final Completion. The Performance Bond or Bank Guarantee shall be returned to the Contractor within twenty-eight days after the issuance by the Engineer of the Certificate of Final Completion, provided that the Contractor shall have paid all money owed to the Employer under the Contract.
- c) If the surety of the Performance Bond or Bank Guarantee is declared bankrupt or becomes insolvent or its right to do business in the country of execution of the Works is terminated, the Contractor shall within five (5) days thereafter substitute another bond or guarantee and surety, both of which must be acceptable to the Employer.

10. INSPECTION OF SITE

The Contractor shall be deemed to have inspected and examined the site and its surroundings and to have satisfied himself before submitting his Tender and signing the Contract as to all matters relative to the nature of the land and subsoil, the form and nature of the Site, details and levels of existing pipe lines, conduits, sewers, drains, cables or other existing services, the quantities and nature of the work and materials necessary for the completion of the Works, the means of access to the Site, and the accommodation he may require, and in general to have himself obtained all necessary information as to risk contingencies, climatic, hydrological and natural conditions and other circumstances which may influence or affect his Tender, and no claims will be entertained in this connection against the Employer.

11. SUFFICIENCY OF TENDER

The Contractor shall be deemed to have satisfied himself before tendering as to the correctness and sufficiency of his Tender for the construction of the Works and of the rates and prices, which rates and prices shall, except in so far as it is otherwise provided in the Contract, cover all his obligations under the Contract and all matters and things necessary for the proper execution and completion of the Works.

12. PROGRAMME OF WORK TO BE FURNISHED

Within the time limit specified in the Contract, the Contractor shall submit to the Engineer for his consent a detailed Programme of Work showing the order of procedure and the method in which he proposes to carry out the Works. In preparing his Programme of Work the Contractor shall pay due regard to the priority required by certain works. Should the Engineer, during the progress of work, require further modifications to the Programme of Work, the Contractor shall review the said program. The Contractor shall also whenever required by the Engineer submit particulars in writing of the Contractor's arrangements for carrying out the Works and of the Constructional Plant and Temporary Works which the Contractor intends to supply, use or construct as the case may be. The submission of such program, or any modifications thereto, or the particulars required by the Engineer, shall not relieve the Contractor of any of his duties or obligations under the Contract nor shall the incorporation of any modification to the Programme of Work either at the commencement of the contract or during its course entitle the Contractor to any additional payments in consequence thereof.

13. WEEKLY SITE MEETING

A weekly site meeting shall be held between the UNDP Project Coordinator or engineer, if any, the representative of the Contractor and the Engineer or the Engineer's Representative, in order to verify that the Works are progressing normally and are executed in accordance with the Contract.

14. CHANGE ORDERS

- a) The Engineer may instruct the Contractor, with the approval of the Employer and by means of Change Orders, all variations in quantity or quality of the Works, in whole or in part, that are deemed necessary by the Engineer.
- b) Processing of change orders shall be governed by clause 48 of these General Conditions.

15. CONTRACTOR'S SUPERINTENDENCE

The Contractor shall provide all necessary superintendence during the execution of the Works and as long thereafter as the Engineer may consider necessary for the proper fulfillment of the Contractor's obligations under the Contract. The Contractor or a competent and authorized agent or representative of the Contractor approved in writing by the Engineer, which approval may at any time be withdrawn, shall be constantly on the site and shall devote his entire time to the superintendence of the Works. Such authorized agent or representative shall receive on behalf of the Contractor directions and instructions from the Engineer. If the approval of such agent or representative shall be withdrawn by the Engineer, as provided in Clause 17(2) hereinafter, or if the removal of such agent or representative shall be requested by the Employer under Clause 17(3) hereinafter, the Contractor shall as soon as it is practicable after receiving notice of such withdrawal remove the agent or representative from the Site, and replace him by another agent or representative approved by the Engineer. Notwithstanding the provision of Clause 17(2) hereinafter, the Contractor shall not thereafter employ, in any capacity whatsoever, a removed agent or representative again on the Site.

16. CONTRACTOR'S EMPLOYEES

- a) The Contractor shall provide and employ on the Site in connection with the execution and completion of the Works and the remedying of any defects therein:
 - i. Only such technical assistants as are skilled and experienced in their respective callings and such sub-agent foremen and leading hands as are competent to give proper supervision to the work they are required to supervise, and
 - ii. Such skilled, semi-skilled, and unskilled labour as is necessary for the proper and timely execution and completion of the Works.
- b) The Engineer shall be at liberty to object to and require the Contractor to remove forthwith from the Works any person employed by the Contractor in or about the execution or completion of the Works, who in the opinion of the Engineer is misconducting himself, or is incompetent or negligent in the proper performance of his duties, or whose employment is otherwise considered reasonably by the Engineer to be undesirable, and such person shall not be again employed on the Site without the written permission of the Engineer. Any person so removed from the Works shall be replaced as soon as reasonably possible by a competent substitute approved by the Engineer.

- c) Upon written request by the Employer, the Contractor shall withdraw or replace from the Site any agent, representative or other personnel who does not conform to the standards set forth in paragraph (1) of this Clause. Such request for withdrawal or replacement shall not be considered as termination in part or in whole of this Contract. All costs and additional expenses resulting from any withdrawal or replacement for whatever reason of any of the Contractor's personnel shall be at the Contractor's expense.

17. SETTING-OUT

The Contractor shall be responsible for the true and proper setting out of the Works in relation to original points, lines and levels of reference given by the Engineer in writing and for the correctness of the position, levels, dimensions and alignment of all parts of the Works and for the provision of all necessary instruments, appliances and labor in connection therewith. If, at any time during the progress of the Works, any error shall appear or arise in the position, levels, dimensions or alignment of any part of the Works, the Contractor, on being required so to do by the Engineer, shall, at his own cost, rectify such error to the satisfaction of the Engineer.

18. WATCHING AND LIGHTING

The Contractor shall in connection with the Works provide and maintain at his own cost all lights, guards, fencing and watching when and where necessary or required by the Engineer or by any duly constituted authority for the protection of the Works and the materials and equipment utilized therefor or for the safety and convenience of the public or others.

19. CARE OF WORKS

- a) From the commencement date of the Works to the date of substantial completion as stated in the Certificate of Substantial Completion, the Contractor shall take full responsibility for the care thereof and of all Temporary Works. In the event that any damage or loss should happen to the Works or to any part thereof or to any Temporary Works from any cause whatsoever (save and except as shall be due to Force Majeure as defined in Clause 66 of these General Conditions), the Contractor shall at his own cost repair and make good the same so that, at completion, the Works shall be in good order and condition and in conformity in every respect with the requirements of the Contract and the Engineer's instructions. The Contractor shall also be liable for any damage to the Works occasioned by him in the course of any operations carried out by him for the purpose of complying with his obligations Clause 47 hereof.
- b) The Contractor shall be fully responsible for the review of the Engineering design and details of the Works and shall inform the Employer of any mistakes or incorrectness in such design and details which would affect the Works.

20. INSURANCE OF WORKS, ETC.

Without limiting his obligations and responsibilities under Clause 20 hereof, the Contractor shall insure immediately following signature of this Contract, in the joint names of the Employer and the Contractor (a) for the period stipulated in Clause 20(1) hereof, against all loss or damage from whatever cause arising, other than cause of Force majeure as defined in clause 66 of these General Conditions, and (b) against loss or damage for which the Contractor is responsible, in such manner that the Employer and the Contractor are covered for the period stipulated in Clause 20 (1) hereof and are also covered during the Defects Liability Period for loss or damage arising from a cause occurring prior to the commencement of the Defects Liability Period and for any loss or damage occasioned by the Contractor in the course of any operations carried out by him for the purpose of complying with his obligations under Clause 47 hereof:

- a) The Works, together with the materials and Plant for incorporation therein, to their full replacement cost, plus an additional sum of ten (10) per cent of such replacement cost, to cover any additional costs of and incidental to the rectification of loss or damage including professional fees and the cost of demolishing and removing any part of the Works and of removing debris of whatsoever nature;
- b) The Contractor's equipment and other things brought on to the Site by the Contractor to the replacement value of such equipment and other things;
- c) An insurance to cover the liabilities and warranties of Section 52(4);

Such insurance shall be effected with an insurer and in terms approved by the Employer, which approval shall not be unreasonably withheld, and the Contractor shall, whenever required, produce to the Engineer the policy or policies of insurance and the receipts for payment of the current premiums.

21. DAMAGE TO PERSONS AND PROPERTY

The Contractor shall (except if and so far as the Contract provides otherwise) indemnify, hold and save harmless and defend at his own expense the Employer, its officers, agents, employees and servants from and against all suits, claims, demands, proceedings, and liability of any nature or kind, including costs and expenses, for injuries or damages to any person or any property whatsoever which may arise out of or in consequence of acts or omissions of the Contractor or its agents, employees, servants or subcontractors in the execution of the Contract. The provision of this Clause shall extend to suits, claims, demands, proceedings and liability in the nature of workmen's compensation claims and arising out of the use of patented inventions and devices. Provided always that nothing herein contained shall be deemed to render the Contractor liable for or in respect of or with respect to:

- a) The permanent use or occupation of land by the Works or any part thereof;
- b) The right of the Employer to construct the Works or any part thereof on, over, under, or through any land.
- c) Interference whether temporary or permanent with any right of light, airway or water or other easement or quasi-easement which is the unavoidable result of the construction of the Works in accordance with the Contract.
- d) Death, injuries or damage to persons or property resulting from any act or neglect of the Employer, his agents, servants or other contractors, done or committed during the validity of the Contract.

22. LIABILITY INSURANCE

22.1. Obligation to take out Liability Insurance

Before commencing the execution of the Works, but without limiting his obligations and responsibility under Clause 20 hereof, the Contractor shall insure against his liability for any death, material or physical damage, loss or injury which may occur to any property, including that of the Employer or to any person, including any employee of the Employer by or arising out of the execution of the Works or in the carrying out of the Contract, other than due to the matters referred to in the proviso to Clause 22 hereof.

22.2. Minimum Amount of Liability Insurance

Such insurance shall be effected with an insurer and in terms approved by the Employer, which approval shall not be unreasonably withheld, and for at least the amount specified in the contract. The Contractor shall, whenever required by the Employer or the Engineer, produce to the Engineer the policy or policies of insurance and the receipts for payment of the current premiums.

22.3. Provision to Indemnify Employer

The insurance policy shall include a provision whereby, in the event of any claim in respect of which the Contractor would be entitled to receive indemnity under the policy, being brought or made against the Employer, the insurer shall indemnify the Employer against such claims and any costs, charges and expenses in respect thereof.

23. ACCIDENT OR INJURY TO WORKMEN

- a) The Employer shall not be liable for or in respect of any damages or compensation payable at law in respect of or in consequence of any accident or injury to any workman or other person in the employment of the Contractor or any sub-Contractor, save and except an accident or injury resulting from any act or default of the Employer, his agents or servants. The Contractor shall indemnify, hold and save harmless the Employer against all such damages and compensation, save and except as aforesaid, and against all claims, proceedings, costs, charges and expenses whatsoever in respect thereof or in relation thereto.

- b) Insurance Against Accident, etc., to Workmen

The Contractor shall insure against such liability with an insurer approved by the Employer, which approval shall not be unreasonably withheld, and shall continue such insurance during the whole of the time that any persons are employed by him for the Works and shall, when required, produce to the Engineer such policy of insurance and the receipt for payment of the current premium. Provided always that, in respect of any persons employed by any subcontractor, the Contractor's obligation to insure as aforesaid under this sub-clause shall be satisfied if the subcontractor shall have insured against the liability in respect of such persons in such manner that the Employer is indemnified under the policy but the Contractor shall require such subcontractor to produce to the Engineer when

required such policy of insurance and the receipt for the current premium, and obtain the insertion of a provision to that effect in its contract with the subcontractor.

24. REMEDY ON CONTRACTOR'S FAILURE TO INSURE

If the Contractor shall fail to effect and keep in force any of the insurances referred to in Clauses 21, 23 and 24 hereof, or any other insurance which he may be required to effect under the terms of the Contract, the Employer may in any such case effect and keep in force any such insurance and pay such premium as may be necessary for that purpose and from time to time deduct the amount so paid by the Employer as aforesaid from any monies due or which may become due to the Contractor, or recover the same as a debt due from the Contractor.

25. COMPLIANCE WITH STATUTES, REGULATIONS, ETC.

- a) The Contractor shall give all notices and pay all fees and charges required to be given or paid by any national or State Statutes, Ordinances, Laws, Regulations or By-laws, or any local or other duly constituted authority in relation to the execution of the Works or of any Temporary Works and by the Rules and Regulations of all public bodies and companies whose property or rights are affected or may be affected in any way by the Works or any Temporary Works.
- b) The Contractor shall conform in all respects with any such Statutes, Ordinances, Laws, Regulations, By-laws or requirements of any such local or other authority which may be applicable to the Works and shall keep the Employer indemnified against all penalties and liabilities of every kind for breach of any such Statutes, Ordinances, Laws, Regulations, By-laws or requirements.

27. FOSSILS, ETC.

All fossils, coins, articles of value or antiquity and structures and other remains or things of geological or archaeological interest discovered on the Site of the Works shall as between the Employer and the Contractor be deemed to be the absolute property of the Employer and the Contractor shall take reasonable precautions to

prevent his workmen or any other persons from removing or damaging any such article or thing and shall immediately upon discovery thereof and before removal acquaint the Employer of such discovery and carry out at the expense of the Employer the Engineer's orders as to the disposal of the same.

28. COPYRIGHT, PATENT AND OTHER PROPRIETARY RIGHTS, AND ROYALTIES

- a) The Contractor shall hold harmless and fully indemnify the Employer from and against all claims and proceedings for or on account of infringement of any patent rights, design trademark or name or other protected rights in respect of any Plant, equipment, machine, work or material used for or in connection with the Works or Temporary Works and from and against all claims, demands proceedings, damages, costs, charges and expenses whatsoever in respect thereof or in relation thereto, except where such infringement results from compliance with the design or Specification provided by the Engineer.
- b) Except where otherwise specified, the Contractor shall pay all tonnage and other royalties, rent and other payments or compensation, if any, for getting stone, sand, gravel, clay or other materials required for the Works or Temporary Works.

29. INTERFERENCE WITH TRAFFIC AND ADJOINING PROPERTIES

All operations necessary for the execution of the Works and for the Construction of any Temporary Works shall, so far as compliance with the requirements of the Contract permits, be carried on so as not to interfere unnecessarily or improperly with the public convenience, or the access to, use and occupation of, public or private roads and footpaths to or of properties whether in the possession of the Employer or of any other person. The Contractor shall hold harmless and indemnify the Employer in respect of all claims, demands, proceedings, damages, costs, charges and expenses whatsoever arising out of or in relation to any such matters in so far as the Contractor is responsible therefor.

30. EXTRAORDINARY TRAFFIC AND SPECIAL LOADS

- a) The Contractor shall use every reasonable means to prevent any of the roads or bridges communicating with or on the routes to the Site from being damaged by any traffic of the Contractor or any of his sub-contractors and, in particular, shall select routes, choose and use vehicles and restrict and distribute loads so that any such extraordinary traffic as will inevitably arise from the moving of plant and material from and to the Site shall be

limited as far as reasonably possible and so that no unnecessary damage may be occasioned to such roads and bridges.

- b) Should it be found necessary for the Contractor to move any load of Constructional Plant, machinery, preconstructed units or parts of units of work, or other thing, over part of a road or bridge, the moving whereof is likely to damage any such road or bridge unless special protection or strengthening is carried out, then the Contractor shall before moving the load on to such road or bridge, save insofar as the Contract otherwise provide, be responsible for and shall pay for the cost of strengthening any such bridge or altering or improving any such road to avoid such damage, and the Contractor shall indemnify and keep the Employer indemnified against all claims for damage to any such road or bridge caused by such movement, including such claim as may be made directly against the Employer, and shall negotiate and pay all claims arising solely out of such damage.

31. OPPORTUNITIES FOR OTHER CONTRACTORS

The Contractor shall in accordance with the requirements of the Engineer afford all reasonable opportunities for carrying out their work to any other contractors employed by the Employer and their workmen and to the workmen of the Employer and of any other duly constituted authorities who may be employed in the execution on or near the Site of any work not included in the Contract or of any contract which the Employer may enter into in connection with or ancillary to the Works. If work by other contractors of the Employer as above-mentioned involves the Contractor in any direct expenses as a result of using his Site facilities, the Employer shall consider payment to the Contractor of such sum or sums as may be recommended by the Engineer.

32. CONTRACTOR TO KEEP SITE CLEAN

During the progress of the Works, the Contractor shall keep the Site reasonably free from all unnecessary obstruction and shall store or dispose of any Constructional Plant and surplus materials and clear away and remove from the Site any wreckage, rubbish or Temporary Works no longer required.

33. CLEARANCE OF SITE ON SUBSTANTIAL COMPLETION

On the substantial completion of the Works, the Contractor shall clear away and remove from the Site all Constructional Plant surplus materials, rubbish and Temporary Works of every kind and leave the whole of the Site and Works clean and in a workmanlike condition to the satisfaction of the Engineer.

34. LABOUR

34.1Engagement of Labour

The Contractor shall make his own arrangements for the engagement of all labour local or otherwise.

34.2Supply of Water

The Contractor shall provide on the Site to the satisfaction of the Engineer an adequate supply of drinking and other water for the use of the Contractor's staff and work people.

34.3Alcoholic Drinks or Drugs

The Contractor shall comply with Government laws and regulations and orders in force as regards the import, sale, barter or disposal of alcoholic drinks or narcotics and he shall not allow or facilitate such importation, sale, gift, barter or disposal by his sub-contractors, agents or employees.

34.4Arms and Ammunition

The restrictions specified in clause 34.3 above shall include all kinds of arms and ammunition.

34.5Holiday and Religious Customs

The Contractor shall in all dealings with labour in his employ have due regard to all holiday, recognized festivals and religious or other customs.

34.6Epidemics

In the event of any outbreak of illness of an epidemic nature the Contractor shall comply with and carry out such regulations, orders, and requirements as may be made by the Government or the local medical or sanitary authorities for the purpose of dealing with and overcoming the same.

34.7Disorderly Conduct, etc.

The Contractor shall at all times take all reasonable precautions to prevent any unlawful riotous or disorderly conduct by or amongst his employees and for the preservation of peace and the protection of persons and property in the neighborhood of the Works against the same.

34.8 Observance by Sub-Contractors

The Contractor shall be considered responsible for the observance of the above provisions by his Sub-Contractors.

34.9 Legislation applicable to Labour

The Contractor shall abide by all applicable legislation and regulation with regard to labour.

35 RETURNS OF LABOUR, PLANT, ETC.

The Contractor shall, if required by the Engineer, deliver to the Engineer at his office, a return in detail in the form and at such intervals as the Engineer may prescribe showing the supervisory staff and the numbers of the several classes of labour from time to time employed by the Contractor on the Site and such information respecting Constructional plant as the Engineer may require.

36 MATERIALS, WORKMANSHIP AND TESTING

36.1 Materials and Workmanship

- a) All materials and workmanship shall be of the respective kinds described in the Contract and in accordance with the Engineer's instructions and shall be subjected from time to time to such tests as the Engineer may direct at the place of manufacture or fabrication, or on the Site or at all or any of such places. The Contractor shall provide such assistance, instruments, machines, labour and materials as are normally required for examining, measuring and testing any work and the quality, weight or quantity of any materials used and shall supply samples of materials before incorporation in the Works for testing as may be selected and required by the Engineer. All testing equipment and instruments provided by the Contractor shall be used only by the Engineer or by the Contractor in accordance with the instructions of the Engineer.
- b) No material not conforming with the Specifications in the Contract may be used for the Works without prior written approval of the Employer and instruction of the Engineer, provided always that if the use of such material results or may result in increasing the Contract Price, the procedure in Clause 48 shall apply.

36.2 Cost of Samples

All samples shall be supplied by the Contractor at his own cost unless the supply thereof is clearly intended in the Specifications or Bill of Quantities to be at the cost of the Employer. Payment will not be made for samples which do not comply with the Specifications.

36.3 Cost of Tests

The Contractor shall bear the costs of any of the following tests:

- a) Those clearly intended by or provided for in the Contract Documents.
- b) Those involving load testing or tests to ensure that the design of the whole of the Works or any part of the Works is appropriate for the purpose which it was intended to fulfill.

37 ACCESS TO SITE

The Employer and the Engineer and any persons authorized by either of them shall, at all times, have access to the Works and to the Site and to all workshops and places where work is being prepared or whence materials, manufactured articles or machinery are being obtained for the Works and the Contractor shall afford every facility for and every assistance in or in obtaining the right to such access.

38 EXAMINATION OF WORK BEFORE COVERING UP

No work shall be covered up or put out of view without the approval of the Engineer and the Contractor shall afford full opportunity for the Engineer to examine and measure any work which is about to be covered up or put out of view and to examine foundations before permanent work is placed thereon. The Contractor shall give due notice to the Engineer whenever any such work or foundations is or are ready or about to be ready for examination and the Engineer shall without unreasonable delay unless he considers it unnecessary and advises the Contractor accordingly attend for the purpose of examining and measuring such work or of examining such foundations.

39 REMOVAL OF IMPROPER WORK AND MATERIALS

39.1 Engineer's power to order removal

The Engineer shall during the progress of the Works have power to order in writing from time to time, and the Contractor shall execute at his cost and expense, the following operations:

- a) The removal from the Site within such time or times as may be specified in the order of any materials which in the opinion of the Engineer are not in accordance with the Contract;
- b) The substitution of proper and suitable materials; and
- c) The removal and proper re-execution (notwithstanding any previous test thereof or interim payment therefore) of any work which in respect of materials or workmanship is not in the opinion of the Engineer in accordance with the Contract.

39.2 Default of Contractor in carrying out Engineer's Instructions

In case of default on the part of the Contractor in carrying out an instruction of the Engineer, the Employer shall be entitled to employ and pay other persons to carry out the same and all expenses consequent thereon or incidental thereto shall be borne by the Contractor and shall be recoverable from him by the Employer and may be deducted by the Employer from any monies due or which may become due to the Contractor.

40 SUSPENSION OF WORK

The Contractor shall on the written order of the Engineer suspend the progress of the Works or any part thereof for such time or times and in such manner as the Engineer may consider necessary and shall, during such suspension, properly protect and secure the Works so far as it is necessary in the opinion of the Engineer. The Employer should be notified and his written approval should be sought for any suspension of work in excess of three (3) days.

41 POSSESSION OF SITE

41.1 Access to Site

The Employer shall with the Engineer's written order to commence the Works, give to the Contractor possession of so much of the Site as may be required to enable the Contractor to commence and proceed with the construction of the Works in accordance with the Programme referred to in Clause 13 hereof and otherwise in accordance with such reasonable proposals of the Contractor as he shall make to the Engineer by notice in writing, and shall from time to time as the Works proceed give to the Contractor possession of such further portions of the Site as may be required to enable the Contractor to proceed with the construction of the Works with due dispatch in accordance with the said Programme or proposals, as the case may be.

41.2 Wayleaves, etc.

The Contractor shall bear all expenses and charges for special temporary wayleaves required by him in connection with access to the Site. The Contractor shall also provide at his own cost any additional accommodation outside the Site required by him for the purpose of the Works.

41.3 Limits of the Site

Except as defined below, the limits of the Site shall be as defined in the Contract. Should the Contractor require land beyond the Site, he shall provide it entirely at his own expense and before taking possession shall supply the Engineer with a copy of the necessary permits. Access to the Site is available where the Site adjoins a public road but it is not provided unless shown on the Drawings. When necessary for the safety and convenience of workmen, public or livestock or for the protection of the Works, the Contractor shall, at his own expense, provide adequate temporary fencing to the whole or part of the Site. The Contractor shall not disturb, damage or pull down any hedge, tree or building within the Site without the written consent of the Engineer.

42 TIME FOR COMPLETION

- a) Subject to any requirement in the Contract as to completion of any section of the Works before completion of the whole, the whole of the Works shall be completed, in accordance with the provisions of Clause 46 and 47 hereof, within the time stated in the Contract.

- b) The completion time includes weekly rest days, official holidays, and days of inclement weather.

43 EXTENSION OF TIME FOR COMPLETION

If, subject to the provisions of the Contract, the Engineer orders alterations or additions in the Works in accordance with Clause 48 hereof, or if circumstances constituting force majeure as defined in the Contract have occurred, the Contractor shall be entitled to apply for an extension of the time for completion of the Works specified in the Contract. The Employer shall, upon such application, determine the period of any such extension of time; provided that in the case of alterations or additions in the Works, the application for such an extension must be made before the alterations or additions in the Works are undertaken by the Contractor.

44 RATE OF PROGRESS

The whole of the materials, plant and labour to be provided by the Contractor and the mode, manner and speed of execution and completion of the Works are to be of a kind and conducted in a manner to the satisfaction of the Engineer. Should the rate of progress of the Works or any part thereof be at any time in the opinion of the Engineer too slow to ensure the completion of the Works by the prescribed time or extended time for completion, the Engineer shall so notify the Contractor in writing and the Contractor shall thereupon take such steps as the Contractor may think necessary and the Engineer may approve to expedite progress so as to complete the Works by the prescribed time or extended time for completion. If the work is not being carried on by day and by night and the Contractor shall request permission to work by night as well as by day, then, if the Engineer shall grant such permission, the Contractor shall not be entitled to any additional payment. All work at night shall be carried out without unreasonable noise and disturbance. The contractor shall indemnify the Employer from and against any claims or liability for damages on account of noise or other disturbance created while or in carrying out the work and from and against all claims, demands, proceedings, costs and expenses whatsoever in regard or in relation to such noise or other disturbance. The Contractor shall submit in triplicate to the Engineer at the end of each month signed copies of explanatory Drawings or any other material showing the progress of the Works.

45 LIQUIDATED DAMAGES FOR DELAY

- a) If the Contractor shall fail to complete the Works within the time for completion prescribed in the Contract, or any extended time for completion in accordance with the Contract, then the Contractor shall pay to the Employer the sum specified in the Contract as liquidated damages, for the delay between the time prescribed in the Contract or the extended time for completion, as the case may be, and the date of substantial completion of the Works as stated in the Certificate of Substantial Completion, subject to the applicable limit stated in the Contract. The said sum shall be payable by the sole fact of the delay without the need for any previous notice or any legal proceedings, or proof of damage, which shall in all cases be considered as ascertained. The Employer may, without prejudice to any other method of recovery, deduct the amount of such liquidated damages from any monies in its hands due or which may become due to the Contractor. The payment or deduction of such damages shall not relieve the Contractor from his obligation to complete the Works or from any other of his obligations and liabilities under the Contract.
- b) If, before the time for completion of the whole of the Works or of a Section of the Works, a Certificate of Substantial Completion has been issued for any part or Section of the Works, the liquidated damages for delay in completion of the remainder of the Works or of that Section may, for any period of delay after the date stated in such Certificate of Substantial Completion, and in the absence of alternative provisions in the Contract, be reduced in the proportion which the value of the part or Section so certified bears to the total value of the whole of the Works or Section, as applicable. The provisions of this Sub-Clause shall only apply to the rate of liquidated damages and shall not affect the limit thereof.

46 CERTIFICATE OF SUBSTANTIAL COMPLETION

46.1 Substantial Completion of the Works

When the whole of the Works have been substantially completed and have satisfactorily passed any test on completion prescribed by the Contract, the Contractor may give a notice to that effect to the Engineer accompanied by an undertaking to finish any outstanding work during the Defects Liability Period. Such notice and undertaking shall be in writing and shall be deemed to be a request by the Contractor, for the Engineer to issue a Certificate of Substantial Completion in respect of the Works. The Engineer shall, within twenty-one (21) days of the date of delivery of such notice either issue to the Contractor, with a copy to the Employer, a Certificate of Substantial Completion stating the date on which, in his opinion, the Works were substantially completed in accordance with

the Contract or give instructions in writing to the Contractor specifying all the work which, in the Engineer's opinion, requires to be done by the Contractor before the issuance of such Certificate. The Engineer shall also notify the Contractor of any defects in the Works affecting substantial completion that may appear after such instructions and before completion of the work specified therein. The Contractor shall be entitled to receive such Certificate of Substantial Completion within twenty-one (21) days of completion, to the satisfaction of the Engineer, of the work so specified and making good any defect so notified. Upon issuance of the Certificate of Substantial Completion of the Works, the Contractor shall be deemed to have undertaken to complete with due expedition any outstanding work during the Defects Liability Period.

46.2 Substantial Completion of Sections or Parts of the Works

In accordance with the procedure in Sub-Clause (1) of this Clause and on the same conditions as provided therein, the Contractor may request the Engineer to issue, and the Engineer may issue, a Certificate of Substantial Completion in respect of any Section or part of the Works which has been substantially completed and has satisfactorily passed any tests on completion prescribed by the Contract, if:

- a) a separate time for completion is provided in the Contract in respect of such Section or part of the Works;
- b) such Section or part of the Works has been completed to the satisfaction of the Engineer and is required by the Employer for his occupation or use.

Upon the issuance of such Certificate, the Contractor shall be deemed to have undertaken to complete any outstanding work during the Defects Liability Period.

47 DEFECTS LIABILITY

47.1 Defects Liability Period

The expression "Defects Liability Period" shall mean the period of twelve (12) months, calculated from the date of completion of the Works stated in the Certificate of Substantial Completion issued by the Engineer or, in respect of any Section or part of the Works for which a separate Certificate of Substantial Completion has been issued, from the date of completion of that Section or part as stated in the relevant Certificate. The expression "the Works" shall, in respect of the Defects Liability Period, be construed accordingly.

47.2 Completion of Outstanding Work and Remedying of Defects

During the Defects Liability Period, the Contractor shall finish the work, if any, outstanding at the date of the Certificate of Substantial Completion, and shall execute all such work of repair, amendment, reconstruction, rectification and making good defects, imperfections, shrinkages or other faults as may be required of the Contractor in writing by the Engineer during the Defects Liability Period and within fourteen (14) days after its expiration, as a result of an inspection made by or on behalf of the Engineer prior to expiration of the Defects Liability Period.

47.3 Cost of Execution of Work of Repair, etc.

All such outstanding work shall be carried out by the Contractor at his own expense if the necessity thereof shall, in the opinion of the Engineer, be due to the use of material or workmanship not in accordance with the Contract, or to neglect or failure on the part of the Contractor to comply with any obligation expressed or implied, on the Contractor's part under the Contract.

47.4 Remedy on Contractor's Failure to Carry Out Work Required

If the Contractor shall fail to do any such work outstanding on the Works, the Employer shall be entitled to employ and pay other persons to carry out the same, and all expenses consequent thereon or incidental thereto shall be recoverable from the Contractor by the Employer, and may be deducted by the Employer from any monies due or which may become due to the Contractor.

47.5 Certificate of Final Completion

Upon satisfactory completion of the work outstanding on the Works, the Engineer shall within twenty eight (28) days of the expiration of the Defects Liability period issue a Certificate of Final Completion to the Contractor. The Contract shall be deemed to be completed upon issuance of such Certificate, provided that the provisions of the Contract which remain unperformed and the Settlement of Disputes provision in the Contract shall remain in force for as long as is necessary to dispose of any outstanding matters or issues between the Parties.

48 ALTERATIONS, ADDITIONS AND OMISSIONS

1 Variations

The Engineer may within his powers introduce any variations to the form, type or quality of the Works or any part thereof which he considers necessary and for that purpose or if for any other reasons it shall, in his opinion be desirable, he shall have power to order the Contractor to do and the Contractor shall do any of the following:

- (a) increase or decrease the quantity of any work under the Contract;
- (b) omit any such work;
- (c) change the character or quality or kind of any such work;
- (d) change the levels, lines, positions and dimensions of any part of the Works;
- (e) execute additional work of any kind necessary for the completion of the Works, and no such variation shall in any way vitiate or invalidate the Contract.

2 Variations Increasing Cost of Contract or altering the Works.

The Engineer shall, however, obtain the written approval of the Employer before giving any order for any variations which may result in an increase of the Contract Price or in an essential alteration of the quantity, quality or character of the Works.

3 Orders for Variations to be in Writing

No variations shall be made by the Contractor without an order in writing from the Engineer. Variations requiring the written approval of the Employer under paragraph (2) of this Clause shall be made by the Contractor only upon written order from the Engineer accompanied by a copy of the Employer's approval. Provided that, subject to the provisions of the Contract, no order in writing shall be required for any increase or decrease in the quantity of any work where such increase or decrease is not the result of an order given under this Clause but is the result of the quantities exceeding or being less than those stated in the Bill of Quantities.

4 Valuation of Variations

The Engineer shall estimate to the Employer the amount to be added or deducted from the Contract Price in respect of any variation, addition or omission. In the case of any variation, addition or omission which may result in an increase of the Contract Price, the Engineer shall communicate such estimate to the Employer together with his request for the Employer's written approval of such variation, addition or omission. The value of any variation, addition or omission shall be calculated on the basis of the unit prices contained in the Bill of Quantities.

49 PLANT, TEMPORARY WORKS AND MATERIALS

1 Plant, etc., Exclusive Use for the Works

All Constructional Plant, Temporary Works and Materials provided by the Contractor shall, when brought on the Site, be deemed to be exclusively intended for the construction and completion of the Works and the Contractor shall not remove the same or any part thereof (save for the purpose of moving it from one part of the Site to another) without the consent in writing of the Engineer which shall not be unreasonably withheld.

2 Removal of Plant, etc.

Upon completion of the Works the Contractor shall remove from the Site all the said Constructional Plant and Temporary Works remaining thereon and any unused materials provided by the Contractor.

3 Employer not liable for Damage to Plant

The Employer shall not be at any time liable for the loss of any of the said Constructional plant, Temporary Works or Materials save if such loss results from the act or neglect of the Employer, its employees or agents.

4 Ownership of paid material and work

All material and work covered by payments made by the Employer to the Contractor shall thereupon become the sole property of the Employer, but this provision shall not be construed as relieving the Contractor from the sole responsibility for all material and work upon which payments have been made or the restoration of any damaged work or as waiving the right of the Employer to require the fulfillment of all of the terms of the Contract.

5 Equipment and supplies furnished by Employer

Title to any equipment and supplies which may be furnished by the Employer shall rest with the Employer and any such equipment and supplies shall be returned to the Employer at the conclusion of the Contract or when no longer needed by the Contractor. Such equipment when returned to the Employer, shall be in the same condition as when delivered to the Contractor, subject to normal wear and tear.

50 APPROVAL OF MATERIALS ETC., NOT IMPLIED

The operation of Clause 49 hereof shall not be deemed to imply any approval by the Engineer of the materials or other matters referred to therein nor shall it prevent the rejection of any such materials at any time by the Engineer.

51 MEASUREMENT OF WORKS

The Engineer shall, when he requires any part or parts of the Works to be measured, give notice to the Contractor or the Contractor's authorized agent or representative who shall forthwith attend or send a qualified agent to assist the Engineer in making such measurement and shall furnish all particulars required by either of them. Should the Contractor not attend or neglect or omit to send such agent, then the measurement made by the Engineer or approved by him shall be taken to be the correct measurement of the work. The purpose of measuring is to ascertain the volume of work executed by the Contractor and therefore determine the amount of the monthly payments.

52 LIABILITY OF THE PARTIES

- 1 The Works shall not be considered as completed until a Certificate of Final Completion shall have been signed by the Engineer and delivered to the Employer stating that the Works have been completed and that the Contractor has fulfilled all his obligations under Clause 47 to his satisfaction.
- 2 The Employer shall not be liable to the Contractor for any matter arising out of or in connection with the Contract or the execution of the Works unless the Contractor shall have made a claim in writing in respect thereof before the giving of the Certificate of Final Completion and in accordance with the Contract.

3 Unfulfilled Obligations

Notwithstanding the issue of the Certificate of Final Completion, the Contractor shall remain liable for the fulfillment of any obligation incurred under the provisions of the Contract prior to the issuance of the Certificate of Final Completion and which remains unperformed at the time such Certificate is issued. For the purpose of determining the nature and extent of any such obligation the Contract shall be deemed to remain in force between the parties hereto.

4 Contractor Responsible

Notwithstanding any other provisions in the Contract documents, the Contractor shall be totally responsible for and shall bear any and all risks of loss or damage to or failure of the Works or any part thereof for a period of ten years after issuance of the Certificate of Final Completion, provided always that such risks, damage or failure result from acts, defaults and negligence of the Contractor, his agents, employees or workmen and such contractors.

53 AUTHORITIES

- 1 The Employer shall have the right to enter upon the Site and expel the Contractor therefrom without thereby voiding the Contract or releasing the Contractor from any of his obligations or liabilities under the Contract or affecting the rights and powers conferred on the Employer and the Engineer by the Contract in any of the following cases:
 - a. If the Contractor is declared bankrupt or claims bankruptcy or court protection against his creditors or if the Contractor is a company or member of a company which was dissolved by legal action;

- b. If the Contractor makes arrangements with his creditors or agrees to carry out the Contract under an inspection committee of his creditors;
- c. If the Contractor withdraws from the Works or assigns the Contract to others in whole or in part without the Employer's prior written approval;
- d. If the Contractor fails to commence the Works or shows insufficient progress to the extent which in the opinion of the Engineer will not enable him to meet the target completion date of the Works;
- e. If the Contractor suspends the progress of the Works without due cause for fifteen (15) days after receiving from the Engineer written notice to proceed;
- f. If the Contractor fails to comply with any of the Contract conditions or fails to fulfill his obligations and does not remedy the cause of his failure within fifteen (15) days after being notified to do so in writing;
- g. If the Contractor is not executing the work in accordance with standards of workmanship specified in the Contract;
- h. If the Contractor gives or promises to give a present or loan or reward to any employee of the Employer or of the Engineer.

Then the Employer may himself complete the Works or may employ any other contractor to complete the Works and the Employer or such other contractor may use for such completion so much of Constructional Plant, Temporary Works and Materials, which have been deemed to be reserved exclusively for the construction and completion of the Works under the provision of the Contract as he or they may think proper and the Employer may at any time sell any of the said Constructional Plant, Temporary Works and unused materials and apply the proceeds of sale in or towards the satisfaction of any sums due or which may become due to him from the Contractor under the Contract.

2 Evaluation after Re-entry

The Engineer shall as soon as may be practicable after any such entry and expulsion by the Employer notify the Contractor to attend the necessary evaluation of the Works. In the event that for any reason the Contractor does not attend such evaluation the Engineer shall undertake the said evaluation in the absence of the Contractor and shall issue a certificate stating the sum, if any, due to the Contractor for work done in accordance with the Contract up to the time of entry and expulsion by the Employer which has been reasonably accumulated to the Contractor in respect of the Works he has executed in such case in accordance with the Contract. The Engineer shall indicate the value of the materials whether unused or partially used and the value of construction equipment and any part of the Temporary Works.

3 Payment After Re-entry

If the Employer shall enter and expel the Contractor under this Clause he shall not be liable to pay the Contractor any money on account of the Contract until the expiration of the Defects Liability Period, and thereafter until the costs of completion and making good any defects of the Works, damages for delay in completion (if any), and all other expenses incurred by the Employer have been ascertained and their amount certified by the Engineer. The Contractor shall then be entitled to receive only such sum or sums (if any) as the Engineer may certify would have been due to him upon due completion by him after deducting the said amount. But if such amount shall exceed the sum which would have been payable to the Contractor on due completion by him, then the Contractor shall upon demand pay to the Employer the amount of such excess. The Employer in such case may recover this amount from any money due to the Contractor from the Employer without the need to resort to legal procedures.

54 URGENT REPAIRS

If by reason of any accident or failure or other event occurring to, in or in connection with the Works or any part thereof either during the execution of the Works or during the Defects Liability Period any remedial or other work or repair shall in the opinion of the Engineer be urgently necessary for security and the Contractor is unable or unwilling at once to do such work or repair, the Employer may by his own or other workmen do such work or repair as the Engineer may consider necessary. If the work or repair so done by the Employer is work which in the opinion

of the Engineer the Contractor was liable to do at his own expense under the Contract, all costs and charges properly incurred by the Employer in so doing shall on demand be paid by the Contractor to the Employer or may be deducted by the Employer from any monies due or which may become due to the Contractor provided always that the Engineer shall as soon after the occurrence of any such emergency as may be reasonably practicable notify the Contractor thereof in writing.

55 INCREASE AND DECREASE OF COSTS

Except if otherwise provided by the Contract, no adjustment of the Contract Price shall be made in respect of fluctuations of market, prices of labour, materials, plant or equipment, neither due to fluctuation in interest rates nor devaluation or any other matters affecting the Works.

56 TAXATION

The Contractor shall be responsible for the payment of all charges and taxes in respect of income including value added tax, all in accordance with and subject to the provisions of the income tax laws and regulations in force and all amendments thereto. It is the Contractor's responsibility to make all the necessary inquiries in this respect and he shall be deemed to have satisfied himself regarding the application of all relevant tax laws.

57 BLASTING

The Contractor shall not use any explosives without the written permission of the Engineer who shall require that the Contractor has complied in full with the regulations in force regarding the use of explosives. However, the Contractor, before applying to obtain these explosives, has to provide well arranged storage facilities. The Engineer's approval or refusal to permit the use of explosives shall not constitute ground for claims by the Contractor.

58 MACHINERY

The Contractor shall be responsible for coordinating the manufacture, delivery, erection and commissioning of plant machinery and equipment which are to form a part of the Works. He shall place all necessary orders as soon as possible after the signing of the Contract. These orders and their acceptance shall be produced to the Engineer on request. The Contractor shall also be responsible for ensuring that all sub-contractors adhere to such programs as are agreed and are needed to ensure completion of the Works within the period for completion. Should any sub-contracted works be delayed, the Contractor shall initiate the necessary action to speed up such completion. This shall not prejudice the Employer's right to exercise his remedies for delay in accordance with the Contract.

59 TEMPORARY WORKS AND REINSTATEMENT

The Contractor shall provide and maintain all temporary roads and tracks necessary for movement of plant and materials and clear same away at completion and make good all works damaged or disturbed. The Contractor shall submit drawings and full particulars of all Temporary Works to the Engineer before commencing same. The Engineer may require modifications to be made if he considers them to be insufficient and the Contractor shall give effect to such modifications but shall not be relieved of his responsibilities. The Contractor shall provide and maintain weather-proof sheds for storage of material pertinent to the Works both for his own use and for the use of the Employer and clear same away at the completion of the Works. The Contractor shall divert as required, at his own cost and subject to the approval of the Engineer, all public utilities encountered during the progress of the Works, except those specially indicated on the drawings as being included in the Contract. Where diversions of services are not required in connection with the Works, the Contractor shall uphold, maintain and keep the same in working order in existing locations. The Contractor shall make good, at his own expense, all damage to telephone, telegraph and electric cable or wires, sewers, water or other pipes and other services, except where the Public Authority or Private Party owning or responsible for the same elects to make good the damage. The costs incurred in so doing shall be paid by the Contractor to the Public Authority or Private Party on demand.

60 PHOTOGRAPHS AND ADVERTISING

The Contractor shall not publish any photographs of the Works or allow the Works to be used in any form of advertising whatsoever without the prior approval in writing from the Employer.

61 PREVENTION OF CORRUPTION

The Employer shall be entitled to cancel the Contract and to recover from the Contractor the amount of any loss resulting from such cancellation, if the Contractor has offered or given any person any gift or consideration of any kind as an inducement or reward for doing or intending to do any action in relation to the obtaining or the execution of the Contract or any other contract with the Employer or for showing or intending to show favour or disfavour to any person in relation to the Contract or any other contract with the Employer, if the like acts shall have been done by any persons employed by him or acting on his behalf whether with or without the knowledge of the Contractor in relation to this or any other Contract with the Employer.

62 DATE FALLING ON HOLIDAY

Where under the terms of the Contract any act is to be done or any period is to expire upon a certain day and that day or that period fall on a day of rest or recognized holiday, the Contract shall have effect as if the act were to be done or the period to expire upon the working day following such day.

63 NOTICES

- 1 Unless otherwise expressly specified, any notice, consent, approval, certificate or determination by any person for which provision is made in the Contract Documents shall be in writing. Any such notice, consent, approval, certificate or determination to be given or made by the Employer, the Contractor or the Engineer shall not be
- 2 unreasonably withheld or delayed.
- 3 Any notice, certificate or instruction to be given to the Contractor by the Engineer or the Employer under the terms of the Contract shall be sent by post, cable, telex or facsimile at the Contractor's principal place of business specified in the Contract or such other address as the Contractor shall nominate in writing for that purpose, or by
- 4 delivering the same at the said address against an authorized signature certifying the receipt.
- 5 Any notice to be given to the Employer under the terms of the Contract shall be sent by post, cable, telex or facsimile at the Employer's address specified in the Contract, or by delivering the same at the said address against an authorized signature certifying the receipt.
- 6 Any notice to be given to the Engineer under the terms of this Contract shall be sent by post, cable, telex or facsimile at the Engineer's address specified in the Contract, or by delivering the same at the said address against an authorized signature certifying the receipt.

64 LANGUAGE, WEIGHTS AND MEASURES

Except as may be otherwise specified in the Contract, English shall be used by the Contractor in all written communications to the Employer or the Engineer with respect to the services to be rendered and with respect to all documents procured or prepared by the Contractor pertaining to the Works. The metric system of weights and measures shall be used in all instances.

65 RECORDS, ACCOUNTS, INFORMATION AND AUDIT

The Contractor shall maintain accurate and systematic records and accounts in respect of the work performed under this Contract.

The Contractor shall furnish, compile or make available at all times to the UNDP any records or information, oral or written, which the UNDP may reasonably request in respect of the Works or the Contractor's performance thereof.

The Contractor shall allow the UNDP or its authorized agents to inspect and audit such records or information upon reasonable notice.

66 FORCE MAJEURE

Force majeure as used herein means Acts of God, war (whether declared or not), invasion, revolution, insurrection or other acts or events of a similar nature or force.

In the event of and as soon as possible after the occurrence of any cause constituting force majeure, the Contractor shall give notice and full particulars in writing to the UNDP and to the Engineer of such force majeure if the Contractor is thereby rendered unable, wholly or in part, to perform its obligations and meet its responsibilities

under this Contract. Subject to acceptance by the UNDP of the existence of such force majeure, which acceptance shall not be unreasonably withheld, the following provisions shall apply:

- (a) The obligations and responsibilities of the Contractor under this Contract shall be suspended to the extent of his inability to perform them and for as long as such inability continues. During such suspension and in respect of work suspended, the Contractor shall be reimbursed by the UNDP substantiated costs of maintenance of the Contractor's equipment and of per diem of the Contractor's permanent personnel rendered idle by such suspension;
- (b) The Contractor shall within fifteen (15) days of the notice to the UNDP of the occurrence of the force majeure submit a statement to the UNDP of estimated costs referred to in sub-paragraph (a) above during the period of suspension followed by a complete statement of actual expenditures within thirty (30) days after the end of the suspension;
- (c) suspension;
- (d) The term of this Contract shall be extended for a period equal to the period of suspension taking however into account any special condition which may cause the additional time for completion of the Works to be different from the period of suspension;
- (e) If the Contractor is rendered permanently unable, wholly or in part, by reason of force majeure, to perform his obligations and meet his responsibilities under the Contract, the UNDP shall have the right to terminate the Contract on the same terms and conditions as provided for in Clause 68 of these General Conditions, except that the period of notice shall be seven (7) days instead of fourteen (14) days, and
- (f) For the purpose of the preceding sub-paragraph, the UNDP may consider the Contractor permanently unable to perform in case of any suspension period of more than ninety (90) days.

67 SUSPENSION BY THE UNDP

The UNDP may by written notice to the Contractor suspend for a specified period, in whole or in part, payments to the Contractor and/or the Contractor's obligation to continue to perform the Works under this Contract, if in the UNDP's sole discretion:

- (a) any conditions arise which interfere, or threaten to interfere with the successful execution of the Works or the accomplishment of the purpose thereof, or
- (b) the Contractor shall have failed, in whole or in part, to perform any of the terms and conditions of this Contract.

After suspension under sub-paragraph (a) above, the Contractor shall be entitled to reimbursement by the UNDP of such costs as shall have been duly incurred in accordance with this Contract prior to the commencement of the period of such suspension.

The term of this Contract may be extended by the UNDP for a period equal to any period of suspension, taking into account any special conditions which may cause the additional time for completion of the Works to be different from the period of suspension.

68 TERMINATION BY THE UNDP

The UNDP may, notwithstanding any suspension under Clause 67 above, terminate this Contract for cause or convenience in the interest of the UNDP upon not less than fourteen (14) days written notice to the Contractor.

Upon termination of this Contract:

- (a) The Contractor shall take immediate steps to terminate his performance of the Contract in a prompt and orderly manner and to reduce losses and to keep further expenditures to a minimum, and
- (b) The Contractor shall be entitled (unless such termination has been occasioned by the Contractor's breach of this Contract), to be paid for the part of the Works satisfactorily completed and for the materials and equipment properly delivered to the Site as of the date of termination for incorporation to the Works, plus substantiated costs resulting from commitments entered into prior to the date of termination as well as any reasonable

substantiated direct costs incurred by the Contractor as a result of the termination, but shall not be entitled to receive any other or further payment or damages.

69 TERMINATION BY THE CONTRACTOR

In the case of any alleged breach by the UNDP of the Contract or in any other situation which the Contractor reasonably considers to entitle him to terminate his performance of the Contract, the Contractor shall promptly give written notice to the UNDP detailing the nature and the circumstances of the breach or other situation. Upon acknowledgement in writing by the UNDP of the existence of such breach and the UNDP' inability to remedy it, or upon failure of the UNDP to respond to such notice within twenty (20) days of receipt thereof, the Contractor shall be entitled to terminate this Contract by giving 30 days written notice thereof. In the event of disagreement between the Parties as to the existence of such breach or other situation referred to above, the matter shall be resolved in accordance with Clause 71 of these General Conditions.

Upon termination of this Contract under this Clause the provisions of sub-paragraph (b) of Clause 68 hereof shall apply.

70 RIGHTS AND REMEDIES OF THE UNDP

Nothing in or relating to this Contract shall be deemed to prejudice or constitute a waiver of any other rights or remedies of the UNDP.

The UNDP shall not be liable for any consequences of, or claim based upon, any act or omission on the part of the Government.

71 SETTLEMENT OF DISPUTES

In the case of any claim, controversy or dispute arising out of, or in connection with this Contract or any breach thereof, the following procedure for resolution of such claim, controversy or dispute shall apply.

1 Notification

The aggrieved party shall immediately notify the other party in writing of the nature of the alleged claim, controversy or dispute, not later than seven (7) days from awareness of the existence thereof.

2 Consultation

On receipt of the notification provided above, the representatives of the Parties shall start consultations with a view to reaching an amicable resolution of the claim, controversy or dispute without causing interruption of the Works.

3 Conciliation

Where the representatives of the Parties are unable to reach such an amicable settlement, either party may request the submission of the matter to conciliation in accordance with the UNCITRAL Rules of Conciliation then obtaining.

4 Arbitration

Any claim, controversy or dispute which is not settled as provided under clauses 71.1 through 3 above shall be referred to arbitration in accordance with the UNCITRAL Arbitration Rules then obtaining. The Parties shall be bound by the arbitration award rendered in accordance with such arbitration as the final adjudication of any such controversy or claim.

72 PRIVILEGES AND IMMUNITIES

Nothing in or relating to this Contract shall be deemed a waiver of any of the privileges and immunities of the United Nations of which the UNDP is an integral part.

73 SECURITY

The Contractor shall:

- (a) put in place an appropriate security plan and maintain the security plan, taking into account the security situation in the country where the services are being provided;
- (b) assume all risks and liabilities related to the Contractor's security, and the full implementation of the security plan.

UNDP reserves the right to verify whether such a plan is in place, and to suggest modifications to the plan when necessary. Failure to maintain and implement an appropriate security plan as required hereunder shall be deemed a breach of this contract. Notwithstanding the foregoing, the Contractor shall remain solely responsible for the security of its personnel and for UNDP's property in its custody as set forth in paragraph 4.1 above.

74 AUDIT AND INVESTIGATIONS

Each invoice paid by UNDP shall be subject to a post-payment audit by auditors, whether internal or external, of UNDP or the authorized agents of the UNDP at any time during the term of the Contract and for a period of three (3) years following the expiration or prior termination of the Contract. The UNDP shall be entitled to a refund from the Contractor for any amounts shown by such audits to have been paid by the UNDP other than in accordance with the terms and conditions of the Contract. Should the audit determine that any funds paid by UNDP have not been used as per contract clauses, the company shall reimburse such funds forthwith. Where the company fails to reimburse such funds, UNDP reserves the right to seek recovery and/or to take any other action as it deems necessary.

The Contractor acknowledges and agrees that, at any time, UNDP may conduct investigations relating to any aspect of the Contract, the obligations performed under the Contract, and the operations of the Contractor generally. The right of UNDP to conduct an investigation and the Contractor's obligation to comply with such an investigation shall not lapse upon expiration or prior termination of the Contract. The Contractor shall provide its full and timely cooperation with any such inspections, post-payment audits or investigations. Such cooperation shall include, but shall not be limited to, the Contractor's obligation to make available its personnel and any documentation for such purposes and to grant to UNDP access to the Contractor's premises. The Contractor shall require its agents, including, but not limited to, the Contractor's attorneys, accountants or other advisers, to reasonably cooperate with any inspections, post-payment audits or investigations carried out by UNDP hereunder.

75 ANTI-TERRORISM

The Contractor agrees to undertake all reasonable efforts to ensure that none of the UNDP funds received under this Contract are used to provide support to individuals or entities associated with terrorism and that the recipients of any amounts provided by UNDP hereunder do not appear on the list maintained by the Security Council Committee established pursuant to resolution 1267 (1999). The list can be accessed via <http://www.un.org/Docs/sc/committees/1267/1267ListEng.htm>. This provision must be included in all sub-contracts or sub-agreements entered into under this Contract.