

Name of Project: Rehabilitation of Janzour High School

Location : Janzour Municipality

Objective Services / (Scope of Work)

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

1) School Building:

- Approximate size - " Medium" - 60 m x 30m.
- Approximate floor area – 1800 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete central staircase for access from ground floor to another up floors.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden .
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 1 male, 1 female, 1.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical / lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

Name of Project: Rehabilitation of Al Watan Al Arabi School

Location : Janzour Municipality

Objective Services / (Scope of Work)

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

2) School Building:

- Approximate size - " Medium" - 60 m x 30m.
- Approximate floor area – 1800 m2.

- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete basement over the full building area.
- Reinforced concrete central staircase for access from ground floor to another up floors.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden .
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 1 male, 1 female, 1.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical / lighting: Concealed conduits, fluorescent lighting throughout.

Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows

Name of Project: Rehabilitation of West Janzour School

Location : Janzour Municipality

Objective Services / (Scope of Work)

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

3) School Building:

- Approximate size - "Small" – 20 m x 20 m.
- Approximate floor area – 350 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete basement over the full building area.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden .
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab with thick concrete layer for rain sewage
- Toilets: 1 male, 1 female.

- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical / lighting: Concealed conduits, fluorescent lighting throughout.

Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.