



KINGDOM OF SAUDI ARABIA
THE SAUDI FUND FOR DEVELOPMENT (SFD)

PROJECT NAME

Reconstruction and repair works of more than 150 effected houses for non-refugees and
Rehabilitation and Furniture for field playgrounds and a culture center

Lot#11-C

Covering for the spectatpr in Palestine and Beit hanoun playgrounds

DONATED BY

Kingdom of Saudi Arabia through the Saudi Fund for Development (SFD)

EMPLOYER

United Nations Releif and Works Agency (UNRWA)
Through United Nations Development Programme (UNDP/PAPP)

EMPLOYER

United Nations Releif and Works Agency (UNRWA)
Through United Nations Development Programme (UNDP/PAPP)



B.O.Q



*Empowered lives.
Resilient nations.*

SECTION 8
PRICE SCHEDULE
(Bill of Quantities)

- 1 .The Price Schedule must provide a detailed cost breakdown for each item.
2. Technical descriptions for each proposed item must provide sufficient detail to
3. All prices/rates quoted must be exclusive of all taxes, since the United Nations,
4. In addition to the hard copy, if possible please provide also the information on

Item No.	Description	Unit	Quantity	Unit Rate US \$ (Numbers)	Total Amount US \$
	<p>the contractor shall visit the site and take into consideration all – direct and indirect works and expenses required for the completion of the coming items.</p> <p>All works must be according to drawings, specification and engineer instructions. Rates shall include :</p> <p>"1.Submitting samples for approval of material, accerrories, color , shop drawings and method statement.</p> <p>2. the contractor shall consider the privacy of each site and the Engineer will approve the method statement according to circumstances of each site.</p> <p>3. in case there is a need to remove any obstical in the site to access the equipments and machinery, the contractor shall remove the obstical after the engineer approval and must restore the status quo at the contractor expense.</p> <p>4. take all precautions to keep the adjacent buildings and existing infrastructure utilities safe. And repair any damage that may occur in the site. Any damages to any utility or structure will be repaired at the contractor's expense."</p> <p>5. Cleaning the site and removing all debris and rubbles to approved dump site.</p> <p>"6. All required Tests should be accommodated by an approved lab.</p> <p>7. more than one contractor may work in the site. the contractor responsibility is to coordinate with the other contractors."</p> <p>"8. The site exists in premises for sport club that is used during implementation. Accordingly , safety measures to protect the people, buildings and utilities will be strickly applied including steel fence. The unit rates include all such costs.</p> <p>9.Painting after grinding and filling all the voids with putty, applying primer coat and hammer paint. In case of galvanized steel the primer should be poly zinc.</p> <p>10- the contractor shall consider the safety measurements including internal and external scaffolding.</p> <p>11- the price include testing the roof for leakage"</p>				
1/1	<p>For Beit Hanoun playground, supply, install and fix a mild steel structure shed for the spectator of playground according to the drawings, specifications and the Engineer instructions, price including.</p> <ul style="list-style-type: none"> - steel columns and base plates including the needed demolishing and adjusting the level of the existing concrete columns and casting and finishing the columns according to the engineer instructions. - covering from top and sides with 0.55mm thick galvanized corrugated roof sheets, including Galvanized steel screw with PVC rubber to prevent leakage. considering that 10% of the covering top and sides will be clear (polycarbonate sheets) - Drainage system of 4" UPVC PIPES SN8 with required fittings, gutters according to the drawings. - Closing all openings according to specifications, drawings and the engineer instructions. <p>Measurement on the horizontal projection Only</p>	m2	710		

Item No.	Description	Unit	Quantity	Unit Rate US \$ (Numbers	Total Amount US \$
1/2	Ditto, but for Palestine playground	m2	680		
1/3	supply, install and paint steel gate including ironmongery, hardware, locks and all requirement as latches,...etc. as per specifications , drawings and the engineer instructions	No.	1		
	Total				

Total in numbers

Total in letters

Name of the contractor

Authorized signature

Signature and Sealing.....

Title

Telephone.....

Fax

Mobile