



July 15, 2018

**RFQ-455-18- REHABILITATION WORKS OF BAIJI EDUCATION DIRECTORATE**  
**BUILDING-SALAHDIEN GOVERNORATE**

**SITE VISIT QUESTIONS AND ANSWERS**

Item No.	QUESTION	UNDP RESPONSE
1	General Clarification	All the material must be supplied according to Iraqi Standard Specifications.
2	Civil Works - Item 4 – What kind of false ceiling tiles do we have to consider?	As detailed in the BOQs, Gypsum board false ceiling.
3	Civil Works – Item 8 - Do we have to remove the existing steel doors?	No, the existing steel doors must be repaired and operated.
4	Civil Works – Item 29 – What is the thickness of steel Columns?	As detailed in the BOQs, 3mm thick.