



KINGDOM OF SAUDI ARABIA THE SAUDI FUND FOR DEVELOPMENT (SFD)

PROJECT NAME

Reconstruction and repair works of more than 150 effected houses for non-refugees and Rehabilitation and Furniture for field playgrounds and a culture center

Lot#11B

Covering for the spectatpr in Al-dorra playground

DONATED BY

Kingdom of Saudi Arabia through the Saudi Fund for Development (SFD)

EMPLOYER

United Nations Releif and Works Agency (UNRWA)
Through United Nations Development Programme (UNDP/PAPP)

EMPLOYER

United Nations Releif and Works Agency (UNRWA)
Through United Nations Development Programme (UNDP/PAPP)



B.O.Q



SECTION 8 PRICE SCHEDULE (Bill of Quantities)

- 1. The Price Schedule must provide a detailed cost breakdown for each item.
- 2. Technical descriptions for each proposed item must provide sufficient detail to
- 3. All prices/rates quoted must be exclusive of all taxes, since the United Nations,
- 4. In addition to the hard copy, if possible please provide also the information on

Covering for the spectatpr in Khanyounis playground

Item				Unit Rate	Total
No.	Description	Unit	Quantity	US \$	Amount
				(Numbers	US \$
	the contractor shall visit the site and take into consideration all – direct and				
	indirect works and expenses required for the completion of the coming				
	items.				
	All works must be according to drawings, specification and engineer				
	instructions. Rates shall include:				
	"1.Submitting samples for approval of material, accerrories, color, shop				
	drawings and method statement.				
	2. the contractor shall consider the privacy of each site and the Engineer				
	will approve the method statement according to circumastances of each				
	site.				
	3. in case there is a need to remove any obstical in the site to access the				
	equiments and machinery, the contractor shall remove the obstical after the				
	engineer approval and must restore the status quo at the contractor				
	expense.				
	4. take all precautions to keep the adjacent buildings and existing infrastructure utilities safe. And repair any damage that may occur in the				
	site. Any damages to any utility or structure will be repaired at the				
	contractor's expense."				
	5. Cleaning the site and removing all debris and rubbles to approved dump				
	site.				
	"6. All required Tests should be accommedated by an approved lab.				
	7. more than one contractor may work in the site. the contractor				
	responsibility is to coordinate with the other contractors."				
	"8. The site exists in premises for sport club that is used during				
	implementation. Accordingly, safety measures to protect the people,				
	buildings and utilities will be strickly applied including steel fence. The				
	unit rates include all such costs.				
	9. Painting after grinding and filling all the voids with putty, applying				
	primer coat and hammer paint. In case of galvanized steel the primer				
	should be poly zinc.				
	10- the contractor shall consider the safety measurements including				
	internal and external scafolding.				
	11- the price include testing the roof for leackage"				
	Supply, install and fix a mild steel structure shed for the spectator of				
	playground according to the drawings, specifications and the Engineer				
	instructions, price including.				
	- steel columns and base plates including the needed demolishing and				
	adjusting the level of the existing concrete columns and casting and				
	finishing the columns according to the engineer instructions.				
1/1	- covering from top and sides with 0.55mm thick galvanized corrugated		000		
	roof sheets, including Galvanized steel screw with PVC rubber to prevent	m2	920		
	leakage. considering that 10% of the covering top and sides will be clear				
	(polycarbonate sheets)				
	- Draingse system of 4" UPVC PIPES SN8 with required fittings, gutters				
	according to the drawings.				
	- Closing all openings according to specifications, drawings and the				
	engineer instructions. Measurement on the horizantal projection Only				
-					
	Total				

Total in numbers
Total in letters
Name of the contractor
Authorized signature
Signature and Sealing
Title
Telephone
Fax
Mobile