

**REQUEST FOR QUOTATION (RFQ)
(Works)**

DESCRIPTION: Rehabilitation of 1. Al Nogoom Alzahira School, 2. Ebn Al Nnafees School, 3. Mohmed Elkot School, Tripoli Center Municipality, Tripoli, Libya	DATE: July 18, 2018
	REFERENCE: RFQ/LBY/SFL/2018/049

We kindly request you to submit your quotation for the following works, as detailed in Annex 1 of this RFQ. Quotations may be submitted on or before **01st August 2018, 14.00 hours** Tripoli, Libya time, ref. www.greenwichmeantime.com, and via email at tenders.ly@undp.org or hand delivered to the address below:

United Nations Development Programme
Libya Country Office
Palm City Residence,
Sidi Abduljaleel, Janzour Area, Tripoli, Libya

An organized site visit is also arranged on 24th July 2018 at the below timing:

- | | |
|------------------------------|---------------------------|
| 1. Al Nogoom Alzahira School | - 10:00 hrs (Libya Time). |
| 2. Ebn Al Nnafees School | - 12:00 hrs (Libya Time). |
| 3. Mohmed Elkot School | - 14:00 hrs (Libya Time). |

Focal Person(s): Mr. Ala Dhiem, Project Coordinator, Dr. Mohamed Ewaze, Field Engineer
Phone number: +218 91795 6527; + 218 919683397

Quotations submitted by email must be limited to a maximum of 5MB, transmissions. They must be free from any form of virus or corrupted contents, or the quotations shall be rejected.

It shall remain your responsibility to ensure that your quotation will reach the address above on or before the deadline. Quotations that are received by UNDP after the deadline indicated above, for whatever reason, shall not be considered for evaluation. If you are submitting your quotation by email, kindly ensure that they are signed and in the .pdf format, and free from any virus or corrupted files.

Please take note of the following requirements and conditions pertaining to the supply of the abovementioned works:

Place of contract	Tripoli, Libya Rehabilitation of 1. Al Nogoom Alzahira School, 2. Ebn Al Nnafees School, 3. Mohmed Elkot School- Tripoli Center Municipality, Tripoli, Libya						
Preferred Currency of Quotation	United States Dollars (US\$)						
Site visit	An organized site visit is also arranged on 24 th July 2018 at the below timing: <table border="0"> <tr> <td>1. Al Nogoom Alzahira School</td> <td>- 10:00 hrs (Libya Time).</td> </tr> <tr> <td>2. Ebn Al Nnafees School</td> <td>- 12:00 hrs (Libya Time).</td> </tr> <tr> <td>3. Mohmed Elkot School</td> <td>- 14:00 hrs (Libya Time).</td> </tr> </table> Focal Person(s): Mr. Ala Dhiem, Project Coordinator, Dr. Mohamed Ewaze, Field Engineer, Phone number: +218 91795 6527; + 218 919683397	1. Al Nogoom Alzahira School	- 10:00 hrs (Libya Time).	2. Ebn Al Nnafees School	- 12:00 hrs (Libya Time).	3. Mohmed Elkot School	- 14:00 hrs (Libya Time).
1. Al Nogoom Alzahira School	- 10:00 hrs (Libya Time).						
2. Ebn Al Nnafees School	- 12:00 hrs (Libya Time).						
3. Mohmed Elkot School	- 14:00 hrs (Libya Time).						
Period of Validity of Quotes	<u>90 days - commencing on the submission date</u> In exceptional circumstances, UNDP may request the Offeror to extend the validity of the Quotation beyond what has been initially indicated in this RFQ. The Offeror shall then confirm the extension in writing, without any modification whatsoever on the Quotation.						

Advanced Payment upon signing of contract	Except when the interests of UNDP so require, it is the UNDP's preference to make no advanced payment(s) on contracts (i.e., payments without having received any outputs). In the event that the Bidder requires an advanced payment upon contract signature, and if such request is duly accepted by UNDP, and the said advanced payment exceeds 20% of the total Bid price or exceed the amount of USD 30,000.00 UNDP shall require the Bidder to submit a Bank Guarantee in the same amount as the advanced payment.
Liquidated Damages	Will be imposed under the following conditions: Percentage of contract price per day of delay up to maximum duration of 01 calendar month: 5% per day Max. limit of delay: 15%
Quotation shall include the following:	<p>a. <u>Cover Letter</u>: A cover letter that lists the lead contact person with contact information, confirmation of acceptance to the General Terms & Conditions for Civil Works (signed/stamped)</p> <p>b. <u>General Information</u>: Include a description of the firm/company's history and experience to demonstrate that the firm/company has the capacity to undertake the works.</p> <p>c. <u>Business Licenses</u>: Valid business license in general construction works. Interested bidders must have appropriate permission/registration from relevant Government body to operate in Libya (copy must be provided with the quote)</p> <p>d. <u>Experience</u>: List and value of similar projects performed in past, plus client's contact details who may be contacted for further information on those contracts.</p> <p>A minimum number of similar 2 contracts implemented in past. <u>Copies of contracts and completion certificates (handover of work) to be provided.</u></p> <p>e. <u>Project Schedule</u>: An outline of the firm/company's proposed timeline reflecting start and completion dates of works including:</p> <p>f. List of proposed personnel with CV's showing relevant experience and qualification.</p> <p>g. Signed/stamped Annex 2 (<u>FORM FOR SUBMITTING SUPPLIER'S QUOTATION</u>) and Annex 2A (<u>BILL OF QUANTITIES</u>)</p>
Evaluation method to be used in selecting the most responsive Bid	Lowest priced offer of technically qualified/responsive quotation

Evaluation Criteria	<p>1. Minimum no. of years of experience in construction (civil works)/renovation works: 3 (three)</p> <p>2. Capacity to undertake mixture of the construction and renovation works, including previous experience with same types of works, availability of equipment and materials and current workload.</p> <p>2.1. The company should have completed at least two similar in nature contracts with the contract value of USD 100,000.00 for each contract. (Copies of contracts and/or completion certificates (handover of work) to be provided.</p> <p>2.2. Qualifications and suitability of the key personnel proposed for the contract including their previous experience with same type of assignment.</p> <ul style="list-style-type: none"> • Civil Engineer/Project Manager - shall have a Degree in Civil engineering and minimum of 5 years of experience of work. • Electrician - with a diploma and minimum of 3 years of experience of work of an equivalent nature. • Plumber with a minimum of 3 years of experience of work of an equivalent nature). <p>3. Submission of Implementation Timeline/Meeting the works completion deadline of <u>120</u> days or shorter.</p> <p>4. Acceptance of General Terms & Conditions for Civil Works.</p>
Maximum Expected duration of contract	The successful vendor shall complete the works within 120 days from the award of contract. Offeror's technical approach shall fully comply with the specifications, drawings and BOQ.
All documentations, including catalogs, instructions and operating manuals, shall be in this language	<p>English</p> <p>Documents provided in other languages must be translated into English</p>
Deadline for the Submission of Quotation	On or before 01 st August 2018, 14.00 hours Tripoli, Libya time, ref. www.greenwichmeantime.com
Partial Quotes	Not permitted
UNDP will award to	One and only one Vendor
Type of Contract to be Signed	Contract for works
Conditions for Release of Payment	Submission of invoice and acceptance/certification by UNDP Engineer
Annexes to this RFQ	<p>Scope of Works (Annex 1)</p> <p>Form for Submission of Quotation including the BOQ (Annex 2)</p> <p>Specifications (Annex 3)</p> <p>General Terms and Conditions for Civil Works (Annex 4).</p> <p>Non-acceptance of the terms of the General Terms and Conditions (GTC) shall be grounds for disqualification from this procurement process.</p>

Request for clarification	<p>Offerors requesting clarification of any of the items, technical requirements or conditions stipulated in this RFQ shall communicate in writing with UNDP office to procurement.ly@undp.org stating the RFQ reference number: RFQ/LBY/SFL /2018/049</p> <p>All the enquiries should be made five days prior to deadline. Any delay in UNDP's response shall be not used as a reason for extending the deadline for submission, unless UNDP determines that such an extension is necessary and communicates a new deadline to the offerors.</p>
---------------------------	--

The quotation that complies with all of the specifications, requirements and offers the lowest price, as well as all other evaluation criteria indicated, shall be selected. Any offer that does not meet the requirements shall be rejected.

Any discrepancy between the unit price and the total price (obtained by multiplying the unit price and quantity) shall be re-computed by UNDP. The unit price shall prevail, and the total price shall be corrected. If the supplier does not accept the final price based on UNDP's re-computation and correction of errors, its quotation will be rejected.

At any time during the validity of the quotation, no price variation due to escalation, inflation, fluctuation in exchange rates, or any other market factors shall be accepted by UNDP after it has received the quotation. At the time of award of Contract or Purchase Order, UNDP reserves the right to vary (increase or decrease) the quantity of services and/or goods, by up to a maximum twenty-five per cent (25%) of the total offer, without any change in the unit price or other terms and conditions.

Any Contract/Purchase Order that will be issued as a result of this RFQ shall be subject to the General Terms and Conditions attached hereto. The mere act of submission of a quotation implies that the vendor accepts without question the General Terms and Conditions of UNDP herein attached as Annex 4.

UNDP is not bound to accept any quotation, nor award a Contract/Purchase Order, nor be responsible for any costs associated with a Supplier's preparation and submission of a quotation, regardless of the outcome or the manner of conducting the selection process.

Please be advised that UNDP's vendor protest procedure is intended to afford an opportunity to appeal for persons or firms not awarded a purchase order or contract in a competitive procurement process.


In the event that you believe you have not been fairly treated, you can find detailed information about vendor protest procedures in the following link:
<http://www.undp.org/content/undp/en/home/operations/procurement/protestandsanctions/>

UNDP encourages every prospective Vendor to avoid and prevent conflicts of interest, by disclosing to UNDP if you, or any of your affiliates or personnel, were involved in the preparation of the requirements, design, specifications, cost estimates, and other information used in this RFQ.

UNDP implements a zero tolerance on fraud and other proscribed practices and is committed to identifying and addressing all such acts and practices against UNDP, as well as third parties involved in UNDP activities. UNDP expects its suppliers to adhere to the UN Supplier Code of Conduct found in this link: http://www.un.org/depts/ptd/pdf/conduct_english.pdf

Thank you and we look forward to receiving your quotation.

Yours sincerely,



Mohammed Salih,
 Programme Coordinator
 UNDP Libya

Scope of Work

1. **Name of Project: Rehabilitation of Al Nogoom Alzahira School**
Location: Tripoli Center Municipality, Tripoli, Libya.

Scope of work:

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

School Building:

- Approximate size - " large " - 60 m x 50m, Two Floors.
- Approximate floor area – 3000 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete central staircase for access from ground floor to first floor.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 2 male, 2 females.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical / lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

2. **Name of Project: Rehabilitation of Ebn Al Nnafees School**
Location: Tripoli Center Municipality

Scope of Work

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

School Building:

- Approximate size - " Small" - 35 m x 25m, Two Floors.
- Approximate floor area – 900 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete central staircase for access from ground floor to first floor.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: Wood.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 1 male, 1 female, 1.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.

- Electrical / lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

3. Name of Project: Rehabilitation of Mohamed Elkot School
Location: Tripoli Center Municipality

Scope of Work

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

School Building:

- Approximate size - " Medium" - 50 m x 20m.
- Approximate floor area – 1000 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete central staircase for access from ground floor to the first floor.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 1 male, 1 female.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical / lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

FORM FOR SUBMITTING SUPPLIER'S QUOTATION

We, the undersigned, hereby accept in full the UNDP General Terms and Conditions, and hereby offer to perform the works as per the summary provided below and attached priced BoQ in conformity with the specification and requirements of UNDP as per RFQ Reference No. **RFQ/LBY/SFL/2018/049- Rehabilitation of 1. Al Nogoom Alzahira School, 2. Ebn Al Nnafees School, 3. Mohamed Elkot School- Tripoli Center Municipality, Tripoli, Libya**

Description:	Total (US\$)
1. Al Nogoom Alzahira School (as per priced BOQ – Annex 2A)	
2. Ebn Al Nnafees School (as per priced BOQ – Annex 2A)	
3. Mohamed Elkot School (as per priced BOQ – Annex 2A)	
Grand Total	

Currency: United States Dollars

All other information that we have not provided automatically implies our full compliance with the requirements, terms and conditions of the RFQ.

Company Name: _____

Contact Person: _____

Position: _____

Email: _____

Mobile Number: _____

Address: _____

Authorised Signature: _____ Date: _____

BILL OF QUANTITIES

Rehabilitation of 1. Al Nogoom Alzahira School, 2. Ebn Al Nnafees School, 3. Mohmed Elkot School- Tripoli Center Municipality, Tripoli, Libya.

RFQ Reference Number: RFQ/LBY/SFL/2018/049

1. Al Nogoom Alzahira School

Item	Description	Unit	Qty	Rate in USD	Amount in USD
A	Demolishing and Preparing				
A1	Demolish and remove damaged floor and roof tiles, hand wash basins, glazed fireclay European and Estrin W.C. suites, doors, windows including meters etc bell the tiles and preparing surfaces for new tiling works. The surplus should be removed to approved dump arsenal as directed by Engineer.	Lump. S	1		
B	Concrete Works				
	1. All form works and shuttering in any form, shape and size. Making chamfered and curved edges, allowing for and making grooves and sleeves and the like; removal of forms and cleaning of all exposed tie wires and rods; making good the harmed surfaces and edges and all surface finishing. 2. Supplying, Casting, vibrating and curing as per specifications. 3. Approved additives and admixtures. 4. Incurred costs on Concrete Mix Designs, Sample taking, testing and providing test results certificates, storing and saving of samples, and preparation of bar bending schedules and workshops. 5. Supplying reinforcement of any grade, size and length as detailed in the drawings, storing on site including cutting, bending and fixing in position and providing all tying wires, spacers, shop drawings, testing and bar bending schedules. 6. Steel bars used for alignment and fixing of reinforcement works, and extra steel added to assure proper detailing and safety.	Note			
B1	Supply and cast smooth finished slopped concrete screed (of mix 0.8 m3 gravel, 0.4 m3 sand, and 250 Kg cement). The screed shall be slopped at minimum 1% and the thickness shall be minimum 5 cm at the water drains. The work shall also include cement fillet (triangles) at roof parapets, complete ready for installation of the waterproofing membrane; all in accordance specifications, drawings and the Engineer instructions.	SQ.M	100		
C	Plastering Works				
C1	Supply and make external plastering 25 mm thick. The work includes rough 15 mm primer rendering with cement sand mortar (1:3) mix and metal mesh at concrete block work joints, edges and openings, finishing 10 mm coat with 350 Kg cement+ 580 Kg limestone powder + 1170 Kg sand mix, and Tyrolean finish of required colors.	SQ.M	150		
D	Painting Works				
D1	Internal painting for internal walls and ceiling, one under coat primer and min. 2-coats of emulsion paint with all required works.	SQ.M	250		
D2	Supply & paint water proof colored (Acrylic Elastic) for exterior school walls, one under coat primer and min. 2-coats of paint with all required works.	SQ.M	150		
D3	Painting of existing wood works (both sided, edges and frame), one under coat primer and min. 2-coats of oil paint for doors, and windows, including rubbing off old paints with all required works. The rate should be paid for overall one plain face of the works.	SQ.M	50		

D4	Painting of existing metal works (both sided, edges and frame), one under coat, primer and min. 2 coats of oil-based paint including rubbing off old paint, surface preparation as per Engineer instructions. The rate should be paid for overall one plain face of the works.	SQ.M	10		
E	Tiling and Marble Works				
	<ul style="list-style-type: none"> All tiling works shall be measured net in square meters, deducting all openings and voids more than 0.25 m.s. Rate shall include preparation of surfaces under tiles, sand with cement mortar, finish to falls and cross falls, special tile pieces for edges and plastic spacers, pointing and cleaning; all as per specifications and engineer approval. 				
E1	Supply and install cement tiles for roofs, size 200mm X 200mm X 20mm, similar to the existing, installed with cement sand mortar made of 250 Kg cement + 1 M3 sand, including skirting of the same type, slopes toward rain gutters and all required works.	SQ.M	100		
E2	Careful cleaning and polishing of existing roof tiles, including grouting tile joints using white cement grout and all required works.	SQ.M	950		
F	Doors, Windows and Metals Works				
	The work shall include supply, fabricate and installation of doors, windows, made out of approved timber to be finish as per the respective specification and the existing doors and windows.	Note			
F1	Maintenance for all internal wooden doors with different sizes. The work includes replacing all damaged parts with new one (except locks), frames fixation and all needed iron monger and hardware for frames and leaves and rubbing off old paints, and all required works.	SQ.M	45		
F2	Supply and fix wooden doors' lock with handle, including removing of old lock and all required works.	No	20		
F3	Supply and fix steel protection grill for windows, size 1850 X 1100 mm, made from approved sections, similar to the existing, including decorations, all iron monger and hardware, painting with approved paints, and all required works.	No	80		
F4	Supply and fix aluminum windows' handle, similar to the existing, including removing of old one as directed by Engineer.	No	60		
F5	Supply and fix clear glass 4 mm thick, similar to the existing, for broken windows.	SQ.M	10		
G	Insulation and Expansion Joints Works				
G1	Supply and fix aluminum cover strips of 150 mm width for expansion joints, including all required works.	Lin.M	22		
G2	Supply and install single layer bituminous sheet 4mm thick for bath rooms floor insulation, lay with 75mm side laps and 100mm end laps, raised 200mm at floor edges and comply with ASTM D751.	SQ.M	100		
	Total for Civil works carried to summary				
H	Plumbing & Sanitary Works				
	Plasticized polyvinyl chloride (uPVC) pipes shall be used in the plumbing installation and they must confirm in every respect to the requirements of BS 4514.	Note			
H1	Supply and install Poly Propylene (PPR) pipes 1/2", for potable water network. The work includes all tees, bends, and all related work accessories and fittings.	Lin.M	20		
H2	Ditto, but pipe size 3/4".	Lin.M	30		
H3	Ditto, but pipe size 1".	Lin.M	30		

H4	Supply and fix white glazed fireclay European W.C. suite made of vitreous china to BS 3402 (grade A), complete with 10-liter double action flushing ceramic cistern, and fixed chromium plated tap 1/2", including all water supply pipes 16mm, angle valves, UPVC drainage pipe connecting to the nearest manhole or sewage header and all related work accessories and fittings.	No	2		
H5	Supply and fix chromium plated mixer for hand wash basin. The work includes water supply pipes 16mm and all related work accessories and fittings.	No	4		
H6	Supply and fix 10-liter plastic flushing cistern for Eastern W.C. suite, including all required works.	No	5		
H7	Supply and fix chromium plated water tap 1/2" diameter, including removal of old ones and all required works.	No	6		
H8	Supply and fix chromium plated waste trap for hand washing basins and kitchen sink, including removal of old ones and all required works.	No	4		
H9	Supply and fix PPR valves of 1/2, 3/4 and 1" diameter and remove old ones, including all required works.	No	3		
H10	Supply and fix flushing cistern set for European W.C. suite, including all related work accessories and fittings.	No	5		
H11	Supply and install PVC tank for potable water, of 2000 liters capacity, including the electrical floating valve and all related work accessories and fittings according to the specifications, and Engineer instructions.	No	1		
H12	Careful cleaning of blocked waste water pipes and sewage manholes, according to the specifications, and Engineer instructions.	Lum.S	1		
	Total for Mechanical works carried to summary				
I	Electrical Works				
	Unless otherwise stated, Rates in Bill of Quantities shall include all necessary materials Cables, conduits, PVC sunk box, bulbs, switches etc.) and labor required to complete the electrical installation to good working order.	Note			
I1	Supply and install connect and commission, flexible electrical wires of 750 V grade and comply with BS 6500 Table 12, insulated with PVC of 10 SQ.M size, according to the specifications, and Engineer instructions.	Lin.M	100		
I2	Ditto, but 2.5 SQ.M size.	Lin.M	200		
I3	Supply and install single pole 16 A, 220V, lighting switch, the work includes removal of old ones and all required works.	No	20		
I4	Supply and install single pole 16 A, 220V, socket outlet. The work includes the earthing cable and removal of old ones and all required works.	No	20		
I5	Supply and install fluorescent lighting fixture 2 X 20-watt water proof type IP 65, for toilets., including 60 cm day light lamps, 3 X 1.5 SQ.M wires, conduits, chock coils, starters, capacitors, clamps, bolts, and all needed accessories.	No	6		
I6	Supply and fix electrical air extractor, size 300 X 300 mm. The work includes all related work accessories and fittings.	No	2		
I7	Supplying and fix external spotlight with 1000-watt halogen lamp. The work includes all related work accessories and fittings.	No	4		
	Total for Electrical works carried to summary				

2. Ebn Al Nnafees School

Item	Description	Unit	Qty	Rate in USD	Amount in USD
A	Demolishing and Preparing				
A1	Demolish and remove damaged, glazed fireclay European WC chromium plated mixer, water tap doors and windows including meters ... The surplus should be removed to approved dump arsenal as directed by Engineer.	Lum.S	1		
B	Painting Works				
B1	Internal painting for internal walls and ceiling, one under coat primer and min. 2-coats of emulsion paint with all required works.	SQ.M	200		
B2	Painting of existing wood works (both sided, edges and frame), one under coat primer and min. 2-coats of oil paint for doors, and windows, including rubbing off old paints with all required works. The rate should be paid for overall one plain face of the works.	SQ.M	70		
B3	Painting of existing metal works (both sided, edges and frame), one under coat, primer and min. 2 coats of oil-based paint including rubbing off old paint, surface preparation as per Engineer instructions. The rate should be paid for overall one plain face of the works.	SQ.M	20		
C	Doors, Windows and Metals Works				
	The work shall include supply, fabricate and installation of doors, windows, made out of approved timber to be finish as per the respective specification and the existing doors and windows.	Note			
C1	Supply and fix interior UPVC windows, overall size 1450 X 1150 mm with frame, constructed of approved profiles and 2 openable leaves and 4mm clear glass, including handle, all iron monger and hardware, and all required works.	No	1		
C2	Ditto, but overall size 1000 X 1150 mm with frame.	No	1		
C3	Supply and fix interior Swedish wood door, overall size 1000 X 2100 X 45 mm thick, with frame, similar to the existing, constructed of 2 panel made of wood chipboards and internal supporting ribs, stiles and rails from Swedish wood grade 1, including door lock with handle, approved paints, and removal of damaged doors and all required works.	No	2		
C4	Maintenance for all internal wooden doors with different sizes. The work includes replacing all damaged parts with new one (except locks), frames fixation and all needed iron monger and hardware for frames and leaves and rubbing off old paints, and all required works.	SQ.M	20		
C5	Supply and fix wooden doors' lock with handle, including removing of old lock and all required works.	No	15		
C6	Maintenance for all internal steel works with different sizes. The work includes replacing all damaged parts with new one (except locks), frames fixation and all needed iron monger and hardware for frames and leaves and rubbing off old paints, and all required works.	SQ.M	10		
C7	Supply and fix steel doors' lock, including removing of old lock and all required works.	No	4		
C8	Maintenance for wooden windows with different sizes, includes replacing all damaged parts with new one, frames fixation and all needed iron monger and hardware for frames and leaves and rubbing off old paints, and all required works.	SQ.M	50		
C9	Supply and fix wooden windows' leaf, overall size 500 X 1100 X 45 mm thick, made of Swedish wood and 4mm clear glass, including handle, all iron monger and hardware, and all required works.	No	2		
C10	Supply and fix wooden windows' handle, including removing of old one as directed by Engineer.	No	25		
C11	Supply and fix clear glass 4 mm thick, similar to the existing, for broken windows.	SQ.M	15		

	Total for Civil works carried to summary				
D	Plumbing & Sanitary Works				
	Plasticized polyvinyl chloride (uPVC) pipes shall be used in the plumbing installation and they must conform in every respect to the requirements of BS 4514.	Note			
D1	Supply and install Poly Propylene (PPR) pipes 3/4", for potable water network. The work includes all tees, bends, and all related work accessories and fittings.	Lin.M	30		
D2	Ditto, but pipe size 1".	Lin.M	40		
D3	Supply and fix white glazed fireclay European W.C. suite made of vitreous china to BS 3402 (grade A), complete with 10-liter double action flushing ceramic cistern, and fixed chromium plated tap 1/2", including all water supply pipes 16mm, angle valves, UPVC drainage pipe connecting to the nearest manhole or sewage header and all related work accessories and fittings.	No	2		
D4	Supply and fix chromium plated mixer for hand wash basin. The work includes water supply pipes 16mm and all related work accessories and fittings.	No	5		
D5	Supply and fix 10-liter plastic flushing cistern for Eastern W.C. suite, including all required works.	No	2		
D6	Supply and fix chromium plated water tap 1/2" diameter, including removal of old ones and all required works.	No	6		
D7	Supply and fix chromium plated waste trap for hand washing basins and kitchen sink, including removal of old ones and all required works.	No	5		
D8	Supply and fix PPR valves of 1/2, 3/4 and 1" diameter and remove old ones, including all required works.	No	5		
D9	Supply and fix flushing cistern set for European W.C. suite, including all related work accessories and fittings.	No	3		
D10	Supply and fix electrical water heater, 80 liters capacity, 0.8 Mpa pressure, provided with temperature gauges, including water supply pipes 16mm, chromium plated control valve, non-return valve and all required works.	No	1		
D11	Supply and install PVC tank for potable water, of 2000 liters capacity, including the electrical floating valve and all related work accessories and fittings according to the specifications, and Engineer instructions.	No	1		
D12	Careful cleaning of blocked waste water pipes and sewage manholes, according to the specifications, and Engineer instructions.	Lum.S	1		
	Total for Mechanical works carried to summary				
E	Electrical Works				
	Unless otherwise stated, Rates in Bill of Quantities shall include all necessary materials Cables, conduits, PVC sunk box, bulbs, switches etc.) and labor required to complete the electrical installation to good working order.	Note			
E1	Supply and install connect and commission, flexible electrical wires of 750 V grade and comply with BS 6500 Table 12, insulated with PVC of 10 mm ² size, according to the specifications, and Engineer instructions.	Lin.M	100		
E2	Ditto, but 2.5 mm ² size.	Lin.M	200		
E3	Supply and install single pole 16 A, 220V, lighting switch, the work includes removal of old ones and all required works.	No	20		
E4	Supply and install single pole 16 A, 220V, socket outlet. The work includes the earthing cable and removal of old ones and all required works.	No	20		
E5	Supply and install fluorescent lighting fixture 2 X 40 watt with plastic cover, including 120 cm day light lamps, 3 X 1.5 mm ² wires, conduits, chock coils, starters, capacitors, clamps, bolts, and all needed accessories.	No	40		

E6	Ditto, but 2 X 20-watt water proof type IP 65, for toilets.	No	6		
E7	Supply and fix electrical air extractor, size 300 X 300 mm. The work includes all related work accessories and fittings.	No	2		
	Total for Electrical works carried to summary				

3. Mohamed Elkot School

Item	Description	Unit	Qty	Rate in USD	Amount in USD
A	Demolishing and Preparing				
A1	Demolish and remove damaged floor and roof tiles, hand wash basins, glazed fireclay European and Estrin W.C. suites, doors, windows including meters etc bell the tiles and preparing surfaces for new tiling works. The surplus should be removed to approved dump arsenal as directed by Engineer.	Lum.S	1		
B	Painting Works				
B1	Internal painting for internal walls and ceiling one under coat primer and min. 2-coats of emulsion paint with all required works.	SQ.M	250		
B2	Internal painting for internal walls, one under coat primer and min. 2-coats of oil paint with all required works. The work shall also include supply and application of one coat of putty with rubbing.	SQ.M	100		
C	Doors, Windows and Metals Works				
C1	Maintenance for existing aluminum doors, overall size 650 X 2150 mm complete with frame, constructed from approved profiles, consist of 2 panels. The work includes replacing all damaged parts with new ones, frames fixation and all required works according to technical specification and Engineer instruction.	No	16		
C2	Supply and fix aluminum doors' lock with handle, including removing of old lock and all required works.	No	16		
C3	Supply and fix clear glass 4 mm thick, similar to the existing, for broken windows.	SQ.M	10		
	Total for Civil works carried to summary				
D	Plumbing & Sanitary Works				
	Plasticized polyvinyl chloride (uPVC) pipes shall be used in the plumbing installation and they must confirm in every respect to the requirements of BS 4514.	Note			
D1	Supply, fix and test wire braided flexible hose, for connecting water mixers and water heaters with feeding pipes of 1/2" nominal size and not less than 400 mm in length, be capable of high pressures of cold and hot water, similar to the existing, according to technical specification and Engineer instruction.	No	18		
D2	Build single gully chamber complete, internal dimensions 500 X 450 mm and 150 mm wall thickness with suitable heavy duty grating and frame as per Engineer instructions.	No	2		
D3	Supply and fix chromium plated mixer for hand wash basin. The work includes water supply pipes 16mm and all related work accessories and fittings.	No	9		
D4	Supply and fix 10-liter plastic flushing cistern for Eastern W.C. suite, including all required works.	No	10		
D5	Supply and fix chromium plated water tap 1/2" diameter, including removal of old ones and all required works.	No	15		
D6	Supply and fix chromium plated waste trap for hand washing basins and kitchen sink, including removal of old ones and all required works.	No	9		

D7	Supply and install heavy duty cast iron manhole cover of 800 mm dia. The work includes adjustment of existing manhole level and proper bonding of old and new concrete using special approved bonding material.	No	1		
D8	Supply and fix flushing cistern set for European W.C. suite, including all related work accessories and fittings.	No	5		
D9	Supply and install UPVC pipes 4" for surface rain water drainage. The work includes trench excavation, backfilling, levelling to slope, connecting to existing manholes, all tees, bends, and all related work accessories and fittings.	Lin.M	25		
D10	Careful cleaning of blocked waste water pipes and sewage manholes, according to the specifications, and Engineer instructions.	Lum.S	1		
	Total for Mechanical works carried to summary				

Summary	
	Amount in USD
Grand Total for Al Nogoom Alzahira School	
Grand Total for Ebn Al Nnafees School	
Grand Total for Mohmed Elkot School	
Grand total in words USD	
Name of the contractor:	
Signature and stamp of the contractor	
Date:	

Specifications

Attached

UNDP General Conditions of Contract for Civil Works

Attached