

United Nations Development Programme

Addendum No. 1 dated 15 July 2018

[ITB-PAL-0000049629]

Pre-bid Meeting Minutes – Addendum No 1

PAL 10- 00099288 / Reconstruction and repair works of more than 150 effected houses for non-refugees and Rehabilitation and Furniture for 5 field playgrounds and a culture center

LOT 7: Installation of Stadium Lighting System for three playgrounds

Issue Date: 4 July 2018

Closing Date & time: 26 July 2018 @ 12.00 P.M.

Extended Closing Date & time: N/A

Dear Bidders,

This correspondence pertaining to the above-mentioned project should be considered as an integral part of the tender documents. Below please find the UNDP/PAPP clarifications and an official reply to all inquiries raised by participant bidders following the pre-bid meeting/site visit which was held on **15 July 2018**.

The following clarifications are considered as Addendum No. 1 to the Invitation to Bid, which shall be deemed to form and be read as part of the tender:

1. All participating Bidders shall provide all Evaluation Criteria Requirements as shown in the Invitation to Bid.
2. Unit rate in USD not including VAT.
3. Unit prices shall include any Bank Charges due to payments transfer.
4. Contractors shall provide labor insurance with an amount of 15% of the contract value, all as per resulting contract terms and conditions. Also, the project insurance must include all materials with its values in USD.
5. The delay penalties will be deducted from each payment made to the contractor of an amount of USD500 for each day of delay in accordance to the approved time schedule for the project and updates. If the contractor doesn't comply to the approved time frame schedule UNDP is entitled to terminate the contract without any financial obligations resulting from termination of the contract process.
6. Payments to the contractors will be according to the submitted cash flow diagram.
7. All imported materials or equipment, submitted by the contractor as substitute to the specified, will be accepted and considered equally approved as long as they are:
 - equal in quality, durability and efficiency, all to UNDP engineer judgment.
 - represented in the country by a reputable, qualified and credible agent.
8. Winning Contractor will be responsible for the submission of safety procedure plan for approval. Safety measures are an important part of the project. All workers, engineers and visitors on site shall use safety tools and wear Safety uniforms, to be all in accordance with contract Safety requirements (Section 12 of the ITB) and UNDP' Engineer instructions. The bidders shall include in their prices the provision of the necessary insurances for the project in accordance with the general terms and condition of contract, and enough to cover the expected risk in the works. As per clause 23 of the general conditions, the contractor is obligated to furnish the insurance policies before commencing the Works.
9. Working hours in the project is from 8 a.m. to 3 p.m. Sunday through Thursday. Any extension of time will not be authorized unless presented in the work plan and approved by UNDP supervisor.
10. Bidders shall furnish actual price analysis for all items in the Bill of Quantities, cash flow and time schedule.

N12

United Nations Development Programme

Addendum No. 1 dated 15 July 2018

[ITB-PAL-0000049629]

11. The Winning Contractor shall be responsible for supplying, installing and fixing Three (3) signboards of size 350x200cm to be located on places indicated by UNDP Engineer. At the end of project, the contractor will supply and install one Karara marble board for each site location, of size 120x 100x 3 cm including all logos and necessary engraved text to be installed on each site.
12. The contractor shall consider gender equality when recruiting its technical staff.
13. **One Coordinator and one fresh engineer** will be paid an amount of **USD 800 per month for each one**. they will be appointed by the supervision and report directly to the supervision team and will attend from commencement of mobilization works until the preliminary handing over certificate is signed.
14. the bidders should include provision of transport facility (a rented car with valid third-party insurance and licenses model 2012 with at least 1400 CC motor) to be available on site 24/24 hours to serve for the movement of the supervision team including supply of fuel for the car (**at least 1200 NIS per month**). The car must be available from commencement of mobilization works until the preliminary handing over certificate is signed.
15. The Wining Contractor shall secure all materials within the mobilization period that doesn't exceed 7 days.
16. In case UNDP imposes suspension longer than one (1) month on the project at one incidence at a time, only the following will be paid for:
 - Security guard for the project if needed.
 - Cost of extension of insurance policy and bank guarantees.
 - Salary of the project manager.All project equipment will not be compensated for, as well as any incurring costs related to staff or subcontractors. The maximum period of suspension will not be more than 60 days at maximum. When suspension is released, the Contractor will be allowed seven (7) days for re-mobilization and the period of contract will be extended accordingly.
17. UNDP has the right to exclude any bidder who has current work load that may put the implementation of the project under risk.
18. UNDP confirms that the technical staff should be engaged on site on full time basis and have the sufficient experience and capabilities of carrying out their duties. UNDP will deduct the amount of USD 25 for each day of the absence of any member of technical staff in the interim payments to the contractor and these discounts non-refundable.
19. The contractor shall take his precautions during the excavation, there is existing infrastructure and facilities (pavements with all layers, sewer, electrical or water networks etc.) he should remove them safely without affecting the service and reinstall them as specified and as per engineer instruction. In case any damage occurred to the infrastructure and facilities, the contractor should remedy this damage on his own expense.
20. Since more than one Contractor may be available on site at the same time, the Wining Contractor shall coordinate with the other Contractors to facilitate accessibility and other work-related issues.
21. **The contractor should take into his consideration the local market price for all needed materials with the same specification mentioned in the contract. And the winning contractor must secure all construction materials from the local markets within the mobilization period and during the implementation of the project and store them in his stores or in stores at site.**
22. The contractor is responsible to secure all materials needed for the work as per contract documents. UNDP will not consider any financial obligations resulting from any change in the market prices as stated in the tender documents.

NID

United Nations Development Programme

Addendum No. 1 dated 15 July 2018

[ITB-PAL-0000049629]

23. In case the contractor will supply dual use materials through the UNDP Access Coordination Unit. UNDP will calculate the differences on the materials and apply deductions based on the submitted price analysis by the contractor for all items.
24. The Contractor must provide a full analysis of cost of materials and should be presented in a separate line for each item separately and submit the schedule for the amounts of concrete used in the project.
25. In case of UNDP will facilitate the coordination of access to materials required for the project (dual-use materials such as Cement, aggregate and steel reinforcement), the contractor will follow the procedures of the UNDP as following:
 - A- The Wining Contractor shall secure all materials within the mobilization period and store them in UNDP stores. The quantities delivered to the site will not exceed the consumption of activities for one day. All relevant transport expenses are deemed included within the unit price of items.
 - B- The Contractor shall provide an accurate inventory of the quantities of materials that need coordination and of dual-use previously mentioned to be reviewed and approved by the United Nations Development Programme UNDP.
 - C- Before giving the order to commence work, a plan of action for the supply of materials in batches adequate with the implementation schedule of activities at the site. The time between the entry of materials and their use in the project work for should not exceed two weeks. The materials will be transferred under the supervision of UNDP to UNDP stores at Karni industrial zone where it will be stored and will be discharged according to the work plan and schedule only in the quantities needed for work. The coordination process of the materials will be done in stages such that not to exceed the time limit for the use of materials in two weeks. Cement will be stored specifically in UNDP stores in Karni industrial zone and is used as needed to work the quantity per day so as not to keep any amount of cement outside UNDP stores beyond the daily project work is completed. It is not allowed for any amount of cement to stay at the work site or factory after the completion of the daily works and the contractor shall transfer the remaining cement to the UNDP stores in Karni at his own costs.
 - D- The contractor shall not be allowed to use the dual-use items without taking the written consent and under the clear and comprehensive control of UNDP engineers and UNDP team of coordination for materials. A comprehensive action coordination plan within the concrete factories and site with all approved documentation for the process of using the material will be prepared to constitute the allocated measures to be followed in that regards.
 - E- In case of defected dual use materials, the contractor will prepare a plan for disposal. He will only implement the plan after authorized control, monitoring and documentation of UNDP access coordination team and after taking approvals on where and how to dispose of these materials.
 - F- The Contractor is fully responsible for any costs related to materials' upload, download at the Israeli border crossings such as Karim Shalom and the UNDP stores in Karni industrial zone. In addition, he will be bearing all costs of the transport of materials from the warehouse at the Karni to different work sites in the project or to approve factories if necessary that are expected on daily basis at the time of utilizing dual use materials. The above-mentioned costs include expenses of equipment and labour used in the loading and unloading.
 - G- UNDP access and supervision teams will be monitoring and examining the materials used in the manufacturing and job mixing ratios to ensure the quality of the mixture at the manufacturing factories and the Contractor will facilitate the task of the engineers inside theses factories.



United Nations Development Programme

Addendum No. 1 dated 15 July 2018

[ITB-PAL-0000049629]

- H- After the end of the project, excess quantities of materials will be returned to the stores of UNDP and the contractor can sell the surplus to any other contractor who have approval for accessing materials for approved projects in full coordination with UNDP.
26. In case there is any conflict in tender documents. It will be explained according to the employer view..
27. The contractor shall submit commitment (stamp and signature) to preserve the material within the site or factories. In case of any violations or misuse of dual use materials accessed UNDP without prejudice will terminate the contract and the contractor will be excluded from involvement in projects of UNDP in the future.
28. The Contractor is fully responsible for the protection and preservation of the quantities supplied materials, either on-site or factories. The Contractor shall bear all relevant costs in that regards.
29. Contractor's previous and/or current performance with UNDP and any other organization one of the main criteria in the evaluation of the contractors and can be a strong basis for refusing the bid.
30. Any debris and unused materials resulted from activities should be transferred to dump site or any location is directed by the engineer.
31. The contractor should submit detailed work plan includes traffic plan, working hours, safety measures, materials storage area, method of disposal of rubble safely and concrete works in the trenches to take the approval of the supervisor engineer in coordination with the authorized partners & stakeholders.
32. After completion of the project, the contractor must submit as built drawings on computer CD (3No.s Auto Cad) and three copies of prints (A2).
Also, the contractor should contract with one of the certified GIS (surveying) offices to survey all projects elements for each lot taking into consideration the following:
- Surveying should be accomplished using accurate GPS receivers or Total station.
 - All project elements should have x,y,z coordinates along with attribute information.
 - The attribute information will be identified in coordination with Project Owner and UNDP.
 - The coordinates should be referenced to the coordinate system adopted by the relevant local authorities.
 - All surveying works should conform to the accuracy standards adopted by the relevant local authorities and UNDP.
 - Two formats of measurements should be submitted: one in AutoCAD format (*.dwg) and another in GIS format (ArcGIS Geodatabase *.gdb)
33. The contractors must coordinate and arrange with all responsible parties such as Municipalities, GEDCO, Authorities, ministries, Pal Tel, etc. regarding to the daily work activities, the contractor is responsible to perform the required tasks and must abide to local rules and norms at his expenses. UNDP will not bear any responsibility to such arrangements.
34. The Contractor must provide work plan explaining all the work activities (supplying & installation) in parallel so that he can finish in the specified time frame of the project.
35. The Contractor shall take the written approval from the supervisor engineer for commencement any activity in the project., the Engineer has the right to reject all the works implemented without his prior approval.
36. After receipt of materials from UNDP warehouse, the materials were under the contractor's responsibility, and need to be stored and secured in the stores and thus the contractor will bear any damage that may occur to the material in the stores or on-site.
37. The contractor shall take his precautions that the sites exist in premises for sport club that is used during implementation. Accordingly, safety measures to protect the people, buildings and utilities will be strictly applied including **steel fence**. The unit rates include all such costs.
38. For the fuel tank, it must be full with Fuel on the handing over day, the commissioning will be on the contractor dues.
39. For item (1.2): **Additional gear: Hot restrike** is not included in the specifications for the item.



United Nations Development Programme

Addendum No. 1 dated 15 July 2018

[ITB-PAL-0000049629]

40. The contractor must submit full detailed documents, CV's for the subcontractor for the technical evaluation criteria. The subcontractor official documents should include proofs of implementation of similar works in a timely manner meeting quality and timeframe.
41. The acceptance of the contractor's offer will take into consideration the capacity as well as the experience of his subcontractor for similar works.
42. Contractor's or subcontractor previous and/or current performance with UNDP and any other organization is one of the main criteria in the evaluation of the contractors and can be a strong basis for refusing the bid.
43. The Brand of the lighting Stadium Tower is BABTAINÉ LIGHTING or Equivalent.
44. The contractor must provide FAT certificates and hot dipping galvanization test certificates for each lighting Stadium Tower before supplying.
45. For Items (1.2 & 1.3): the products must be European made and has obtained the ENEC European Certificate of Conformity and the contractor must provide the certificates before the supplying.
46. For item (1.2): the electric gear is 400V/50Hz power supply for each unit.
47. For item (1.2): the lumen of the Metal Halide Floodlight unit is 200,000 Lm – 210,000 lumens or more.
48. The Contractor must provide all supported documents with the tenders for the technical evaluation, such as Drawings, Catalogues for products and equipment's such as (Metal Halide Floodlight, LED Flood Lights, Stadium Poles, Generator, Lightning system), country of origin certificate for all materials and must indicating the proposed type in Catalogues with reference tag number and must be stamped by the supplier.
49. The unit rates include solving all the obstacles that will face in the site
50. The unit rates of items shall include such costs for safely measures/dismantling/ reinstalling/ demolishing/ proper storage and removal of materials/items/utilities/protection of existing items, devices or any kind of obstacles requires to complete different contract items. The price shall also include any needed reinstatement activities for the existing tiles and pavements to professionally work activities, the price shall also include costs for the removed of any surplus unwanted materials to locations identified by the engineer.
51. The contractor must submit warranties for items not less than one year.
52. The site visit was conducted in 16 July 2018.

Interested bidders shall acknowledge receipt of this addendum/pre-bid minutes by returning/including it, signed and stamped, with their bids.

For your kind attention and reference,

Sincerely Yours,

Khaled Shahwan
Deputy Special Representative (Operations)