



July 26, 2018

**ADDENDUM 01**

**RFQ 540/18 - Rehabilitation of Sinjar Water Directorate-Sinjar District-Ninawa Governorate**

Site Visit

Following clarifications were sought. Please see the responses

Item No.	Bidders Questions	UNDP Response
5. Civil works -	How to solve roof leaking?	As per our BoQ in item (no.5) the bidder should Supply of materials, tools and manpower to repair wall cracks and remove the damaged cement plastering of external walls & fence by removing the damaged cement plastering minimum 35cm at each side of the crack, then treat the cracks with crack filler approved by manufacture with cement mortar 1:3 and using SBR at a rate of 200gr per m2, later putting a layer of metal chicken mesh 10 cm overlap each side on the area with 3 layers of cement plastering 1:3. All needed works to complete the job, will be included within the price.
8 Civil works - Gypsum plastering with crack repairing  9. Civil works	How to repair cracks?	<b>i. Cracked cement plastering will be solved as clarified below:</b> Supply of materials, tools and manpower to repair wall cracks and remove the damaged cement plastering of external walls & fence by removing the damaged cement plastering minimum 35cm at each side of the crack, then treat the cracks with crack filler approved by manufacture with cement mortar 1:3 and using SBR at a rate of 200gr per m2,

Cement plastering with crack repairing		<p>later putting a layer of metal chicken mesh 10 cm overlap each side on the area with 3 layers of cement plastering 1:3. All needed works to complete the job, will be included within the price.(as per item no.9)</p> <p><b>ii. Cracked Gypsum Plastering will be solved as clarified below:</b></p> <p>Supply of all necessary materials, tools and manpower to remove the damaged gypsum plastering of internal walls &amp; ceiling and plastering with new gypsum plastering in 2 layers minimum thickness 20mm. The work includes repairing of wall cracks by removing the damaged gypsum plastering 25cm at each side of the crack, then filling the cracks with cement mortar 1:3 and using SBR at a rate of 200gr per m2, later putting a layer of plastic mesh on the area under the gypsum plastering. All needed works to complete the job, will be included within the price. (as per item no.8)</p>
--	--	---

This Addendum -01 forms an integral part of the RFQ-540/18. All other Terms and Conditions in this RFQ will remain unchanged.

Yours sincerely,

**Piero Emanuele Franceschetti**

Head of Service Center, UNDP, Iraq