

Annex 1

Scope of Work

1. Name of Project: Rehabilitation of Omar Almokhtar School Location: Souq Al Khamees Municipality

Scope of Work

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

School Building:

- Approximate size "Medium" 35mx35m &35 m x 30m, one floor.
- Approximate floor area 1500 m2.
- Structure: Reinforced concrete foundations, columns and beams
- Reinforced concrete basement over the full building area.
- Reinforced concrete central staircase for access from ground floor to the roof.
- Walls brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wood.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 2 male, 1 female.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical/lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

2. Name of Project: Rehabilitation of Saidi Bireesh School Location: Souq Al Khamees Municipality

Scope of Work

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

School Building:

- Approximate size "Medium" 70 m x 30 m, one Floor.
- Approximate floor area 1200 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete central staircase for access from ground floor to the roof
- Reinforced concrete basement over the full building area.
- Walls brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab with thick concrete layer for rain sewage
- Toilets: 2 males, 1 female.
- Kitchen facilities: 1 tea room.

RFQ/LBY/SFL/2018/064



- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical/lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

3. Name of Project: Rehabilitation of Shohada Aljaria School Location: Soug Al Khamees Municipality

Scope of Work

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

School Building:

- Approximate size "Large" 60 m x 60 m, one floor.
- Approximate floor area 1700 m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete central staircase for access from ground floor to the roof.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 2 males, 1 female.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical/lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

RFQ/LBY/SFL/2018/064 2