



September 4th, 2018

**ITB-643-18 Renovation of Al Sanharib Bridge in East Mosul-Ninawa Governorate**

**SITE VISIT QUESTIONS AND ANSWERS**

<b>Item No.</b>	<b>QUESTION</b>	<b>UNDP RESPONSE</b>
1	The related work paragraph does not exist within the BoQ for the contractor shall create a proper alternate route (detour access road) before blocking the site and maintain it until the project handover. Work shall be done according to the directions of general Directorate of roads and bridges in Nineveh.	The information is detailed in the bid document Annex 5 General Conditions of Contract – Clause 5: General Duties/Powers of Engineer.
2	How can lifting 4 girder beams using special hydraulic jacks and setting up new elastomeric pads (300 mm x 400 mm x 470 mm) and aligning the shifted spans?	The lifting shall be from one side only for the girders using special hydraulic jacks and the lift shall be only for the height of 3-4 cm and then setting up new elastomeric pads according to # 5 in the BoQ
3	Are all tests required for the girder beams in #6 and #7 in the BoQ?	Yes, all tests are required for the girder beams in # 6 and # 7 in the BoQ and load test in the factory very important test.