

### Scope of Work

- 1. Name of Project: Rehabilitation of Hateen School**  
**Location of School: Shohada al Dinar- Beni Walid**  
**Number of Class Room: 10 Classrooms**

#### Objective Services:

Provide all materials and transport to site, construct/erect all structures as per attached Drawings, Bill of Quantities and Specifications. Structures are described briefly below:

#### School Building:

- Approximate size - " medium" - 60 m x 60, two floors.
- Approximate floor area –3400m2.
- Structure: Reinforced concrete foundations, columns and beams.
- Reinforced concrete side staircase for access from ground floor to another up floors.
- Walls - brick masonry.
- Wheelchair ramp: stone masonry sides with concrete ramp.
- Windows: wooden.
- Doors: timber frame external, steel security doors.
- Floors: Ceramic floor tiles in toilets, in-situ color chips elsewhere.
- Wall finishes- internal and external - plaster and paint.
- Rainwater disposal: Concealed GS gutter and downpipes.
- Roof structure: Reinforced concrete slab
- Toilets: 2 males, 2female.
- Kitchen facilities: 1 tea room.
- Plumbing: GI water supply pipes, bronze valves, PVC sewage/sanitation pipes, ceramic toilets, sinks, steel sinks in kitchen.
- Electrical/lighting: Concealed conduits, fluorescent lighting throughout.
- Security: Steel security bars on all windows, steel doors at main entrance and safe room, steel shutters on safe room windows.

#### Required Task:

- Internal painting for internal ceiling and walls, painting for metal and wooden works.
- Fabricate and installation of doors, windows.
- Plumbing and Sanitary Works
- Electrical Works include all necessary materials Cables, conduits, PVC sunk box, bulbs, switches etc.) and labor required to complete the electrical installation to good working order.