

Question and Answer No. 6

ITB-804/18-Rehabilitation of Ibn Al Atheer Hospital Building, East Mosul, Ninewa Governorate

No.	Question submitted by bidders	Answer by Technical and Procurement Teams
1	ITB_804_18-BOQ-30122018.xlsx /Electrical works/P Grounding: As per the ITB_804_18-BOQ-30122018"Electrical Item/P/Grounding/5, theater control panel shown in grounding section. Please clarify if theater control panel will be provided by contractor or only grounding system required for panel. If contractor will provide the theater control panel please provide the detail drawings and specification.	Surgical Control panel shall be supplied and installed with all required programming, grounding and wiring needed as specified and shown in the drawings. For more specifications refer to Technical specifications section EL.09 Surgical Control Panel.
2	ITB_804_18-BOQ-30122018.xlsx /Electrical works/K DIESEL GENERATORS: Please confirm that Will one each 45000 liter fuel tank be connected to three generators?	Each Prime Generator shall need 45000 LTR fuel Tank. Meaning 3 Fuel tanks with 45000 LTR capacity each.