



Empowered lives.
Resilient nations.

August 06th, 2019

ADDENDUM 01

**ITB-192-19 - Rehabilitation of 293 Housing Units in Al Abar Neighborhood-Al Rabeea
Area-West Mosul, Ninewa Governorate**

Site Visit: Following clarifications were sought. Please see the responses

Item	Bidders Questions	UNDP Response
1	Who is the person who determines the security situation of the house?	The local mukhtar will determine the security situation which will be discussed with the UNDP focal engineer and final decision will be made.
2	What about repair steel and wooden doors and windows?	Please refer to the BOQs attached with the Tender. All works should be done in accordance with the BOQs.
3	What is the period to handover the houses from UNDP engineers?	The houses will be handed over after signing of the contract. The period will be within 12 to 16 days after signing of the contract.
4	What about balance?	UNDP engineers will be making a balance for all forms isolated
5	What difference between re-inforced concrete and repair slab?	Repair slab: Is repairing damaged part of slab measuring in square meter Ranforced concrete: Is casting all the slab and measuring in cubic meter
6	Details of fluorescent with wiring and old wiring?	Fluorescent with wiring: Means installing fluorescent lamp with its base with new wiring 2*1.5mm with switch 6 A Fluorescent old wiring: Means installing Fluorescent lamp with its base only without needing for wire and switch

This Addendum-01 forms an integral part of the ITB-192-19. All other Terms and Conditions in this ITB will remain unchanged

Yours sincerely,

Ijaz Hussain

Head of procurement, UNDP, Iraq