




D1 D2



DOORS SCHEDULE

DOORS SCHEDULE				
WIDTH	HEIGHT	TYPE	QTY	DESCRIPTION
3'-4"	7'-2"	D1	7PCS	HARD WOOD PANEL
3'-0"	7'-2"	D2	2PCS	HARD WOOD PANEL

WINDOWS SCHEDULE



W1 W2 W3

WINDOWS SCHEDULE				
WIDTH	HEIGHT	TYPE	QTY	DESCRIPTION
6'-0"	4'-0"	W1	2PCS	SLIDING GLASS WINDOW
3'-0"	4'-0"	W2	8PCS	SLIDING GLASS WINDOW
2'-0"	2'-0"	W3	2PCS	SLIDING GLASS WINDOW

DWG No. 14 OF 22	PROJECT	RENOVATION OF POLICE DEPOT	REVISED BY	UNDP-LIBERIA	DRAWING TITLE
	OWNER	UNDP-LIBERIA	DRAWN BY	UNDP-LIBERIA	**DOORS & WINDOWS SCHEDULE**
CAT. A / SHTNo. 14	LOCATION	GREENVILLE CITY SINOE COUNTY	CHECKED BY	XXX	
	DATE	JULY 2019	SCALE	N/A	