

BOQ

Ref n°:	DESCRIPTION OF WORKS	Unit	Quantity	Unit priceTTC	total priceTTC
	<u>0.INSTALATION DE CHANTIER</u>				
0.1	Execution File and Laboratory Tests.	Ft	1		-
0.2	Site Installation - cleaning of places in progress and after completion of work and refolding of equipment,	Ft	1		-
	SOUS TOTAL				-
	<u>I.TERRASSEMENT- EARTHWORKS-</u>				
1.1	Search Rill	m ³	10		-
1.2	Remblais -embankments	m ³	15		-
	SOUS TOTAL 1				-
	<u>II. MIXED ARMED AND CONCRETE CONCRETE</u>				
2.1	Reinforced concrete in elevation	m ³	13		-
2.2	Floors in B.A of 10 cm-	m ³	10		-
2.3	Roof en B.A d'ép 15 cm -Floors in B.A of 15 cm-	m ³	13		-
	SOUS TOTAL2				-
	<u>III-MACONNERIE-MASONRY-</u>				
3.1	Walls inside and outside 20 x 20 x 40	m ²	70		-
3.2	Walls inside and outside 15 x 20 x 40	m ²	160		-
	SOUS TOTAL 3				-
	<u>IV-ENDUITS COATING</u>				
4.1	COATINGS FOR WALLS	m ²	500		-
	SOUS TOTAL 4				-
	<u>V- WORK CARPENTRY</u>				
5.1	Exterior doors in wood (Door entre) de (1,20 x 2,20)	U	1		-
5.2	Interior door (0,90 x 2,20)	U	3		-
5.3	Interior door (0,80 x 2,20)	U	3		-
5.4	Windows (1,20 x 1,20)	U	5		-
5.5	Windows (60 x 60)	U	2		-
	SOUS TOTAL 5				-
	<u>VI-PLUMBING SANITARY & EVACUATION</u>				
	Plumbing				
6.1	Supply and installation of wash basin	U	1		-
6.2	Supply and installation of full English toilets	U	1		-
6.3	Siphon de sol de 100X100	U	1		-
6.4	General stop valve 30/34	U	1		-
6.5	Tap of 20/27	U	1		-
6.6	Ablution faucet including flexible 1.20 m	U	1		-
6.7	PVC pressure Ø25 for drinking water supply	ml	1		-
6.8	Evacuation				
6.9	PVC Ø75	ml	1		-
7	PVC Ø110	ml	1		-
7.1	PVC Ø125	ml	1		-
7.2	Regard en BA de 50X50	U	1		-
	SOUS TOTAL6				-

		<u>VII-ELECTRICITY</u>			
8.1	Disjoncteurs différentiel	ens	1		-
8.2	Prise de courant 2P+T 10/16 A	U	2		-
8.3	Prise de courant 2P+T 10/16 A etanche	U	2		-
8.4	Prise de courant 2P+T saillant de 32A	U	3		-
8.5	Prise télévision	U	3		-
8.7	Prise téléphone	U	3		-
8.8	Brasseur d'air	U	3		-
8.9	Reglette simple de 1,20 m	U	5		-
9	Applique mural muni d'un hulot de 40 w	U	4		-
9.1	Applique mural étanche muni d'un hulot de 40 w	U	4		-
9.2	Regard de mise à la terre y compris liaison equipotentiel et cinturage	U	1		-
		<u>SOUS TOTAL 7</u>			-
		<u>VIII-flooring</u>			
10	Glazed stoneware tile	m ²	60		-
10.1	Non-slip sandstone	m ²	12		-
10.2	ceramic baseboards 10cm high	ml	60		-
10.3	wall ceramic baseboards 2cm high	ml	60		-
10.4		<u>SOUS TOTAL 8</u>			
		<u>IXPAINT</u>			
11	Interior plaster-	m2	125		
11.1	Vinyl painting on interior walls and ceilings	m ²	500		
		<u>SOUS TOTAL 9</u>			
		<u>Total générale</u>			

RECAPITULATIF

<i>N° C</i>	<i>DESIGNATION</i>	<i>Montant</i>
	INSTALLATION WORK	
1	TERRASSEMENT- EARTHWORKS	
2	MIXED ARMED CONCRETE	
3	MASONRY	
4	COATING	
5	WORKS CARPENTRY	
6	PLUMBING	
7	ELECTRICITY	
8	PAINT	
9	FLOORING	
<i>Total générale</i>		