

UNDP CYP RFQ 107/2019- Conservation of 3 Fountains in Nicosia Walled City

Clarifications no:1 dated 17 October 2019

	Questions	Answers
1	Is that kind of stone compatible with the original one, found on the island or can it be found in Turkey? Do you have any suggestions?	As mentioned in the Terms of reference “stone with severe damage and/or deterioration should be replaced with compatible stone of corresponding mechanical and physical characteristics with the existing sand stones. The type of stone has to be proposed by the contractor and approved by UNDP.
2	What are the jobs included in the "Water Management" issue that is sated in page 2 clause 9. Is there a plumbing job to connect the fountain to the drinkable water main pipeline	Item 9 of the Description of Services required for LOT 3 refers to rainwater drainage management. No works should be undertaken to connect the fountains with the water network within the framework of this project. Nevertheless, works on the fountains have to ensure proper rainwater drainage management for the basins (and roofs) of the fountains as described in the works description for each lot.