

				Amendment-1a-Annex-1-RFQ-BD-2019-028	
				BOQ & Bidder's Compliance -Annex 1	
			Renovation and refurbishment work of LIUPC Project Office (5th Floor, IDB Bhaban)		
S/N	Items	Quantity	Units	Specification	Bidders Compliance (Yes/No)
	Design and management services				
BOARD WORKS					
1	Full Height Cabinet	160	sft	Supply, Fitting & Fixing of Full Height Cabinet made with 18mm Gorjon Ply Board (from Partex Star OR EQUIVALENT) and light Grey Matt enamel Paint Finishing with all necessary undercoatings with front cabinet door made with 18mm White TEXTURED MELAMINE BOARD including all accessories. (Height @ 18th floor 9'-6" & @ 19th Floor 12'-6" and depth 16")	
2	Low Height Cabinet	308	sft	Supply, Fitting & Fixing of Full Height Cabinet made with 18mm Gorjon Ply Board (from Partex Star OR EQUIVALENT) and light Grey Matt enamel Paint Finishing with all necessary undercoatings with front cabinet door made with 18mm White TEXTURED MELAMINE BOARD including all accessories. (Height 36" and depth 16")	
3	Feature Wall	115	sft	Reception Front wall custom made feature work as a designed front wall made with 12mm particle board fixed as 1" thick louver on wall with engraved letter cutting works as per approved design.	
4	Full Height partition (Dry Wall)	224	sft	Supply, Fitting & Fixing of Dry wall partition made with 12mm Gypsum board with minimum 3 hours fire rating pasted on both side and Structure made with 3" Metal C Profile & 2"X2" Farin channel, including all other hardwares & accessories.	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (Yes/No)
5	Drop Wall Partition (Dry Wall)	256	sft	Supply, Fitting & Fixing of Dry wall partition made with 12mm Gypsum board with minimum 3 hours fire rating pasted on both side and Structure made with 3" Metal C Profile & 2"X2" Farin channel, including all other hardwares & accessories.	
	Total Board Works				
Glass Works					
7	Glass Door	14	nos	Supply, Fitting & Fixing of 3'x8' custom ordered glass door with white glass , locally tempered with all door accessories(the floor spring should have the load capicity from 80~100kgs & min. 2 years of warranty) and custom made 48" long wooden door handles with lacquer finishing.	
8	Glass partition	1430	sft	Supply, Fitting & Fixing of 10mm Chines tempered glass (with colored film) line finish with Silicon and installation with MS Hollow box sized 1"X2" and fixed with SS (Stainless Steel) U channel or Aluminium Profile Box.	
9	Glass writing board	20	sft	Supply, Fitting & Fixing of 10mm Chines non-tempered glass with SS (Stainless Steel) knob on wall surface	
	Total Glass Works				
CUSTOM MADE FURNITURE					
10	Office workstation	26	nos	Supply, Fitting & Fixing of prefabricated workstations as per design with white melamine top and metal legs with frame and movable side desks with fabric seating provision on top and 16" high fabric partitions in between (minimum table top size required as 48"X24") cable cap and trays are included	
11	Cabin Work station	6	nos	Supply, Fitting & Fixing of prefabricated workstations as per design with white melamine top and metal legs with frame and side desks (minimum table top size required as 30"X60") cable cap, trays & all other accessories are included	
12	Center Table	6	nos	Supply, Fitting & Fixing of Custom made center Table sized 2ft diameter 10mm tempered glass on top ; SS (Stainless Steel) support with matt finishing and SS glass knobs	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (Yes/No)
13	Conference Table	1	nos	Supply, Fitting & Fixing of meeting Table sized 4'x 16' ; made with Teak veneer board with lacquer polish finishing or HPL with metal Structure with integrated power & Data ports	
14	Mini meeting table	1	nos	Supply, Fitting & Fixing of Custom made Table sized 36" diameter; 10mm tempered glass top on SS (Stainless Steel) support with matt finishing and SS glass knobs or prefabricated metal framing.	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (Yes/No)
15	Pantry Table	1	nos	Supply, Fitting & Fixing of Pantry table sized 15ftx2ft made with 18mm Marine Ply Board (from Partex Star or equivalent) Board with matt enamel paint finising & black 12 mm chinese tiles work top fixed with adhesive.	
16	Chair (mini meting room)	4	pcs	Supply, Fitting & Fixing of imported designer chair as per design	
17	Three Seater Sofa	1	pcs	Supply, Fitting & Fixing of prefabricated sofa set as per design, made with fabric or artificial leather with SS or wooden legs.	
18	Single Seater Sofa	9	pcs	Supply, Fitting & Fixing of prefabricated sofa set as per design, made with fabric or artificial leather with SS or wooden legs.	
	Total Custom made Furniture				
OTHERS					
19	Signage	20	pcs	Supply, Fitting & Fixing of Different Logos, signages or branding materials with acrylic (5mm) or wooden laser cut encrpteions or framings at different locations of the floor	
20	Painting & Photographs	7	nos	Supply, Fitting & Fixing of Different sized custom printed paintings and photographs with carosine wooden framing with 2" white plastic board borders	
21	Lamp shade/ light	3	set	Supply, Fitting & Fixing of imported lights with two years of waranty as shown in the picture on break out corner	
22	Planter box	1	nos	Supply, Fitting & Fixing of 192"X16"X16" sized planter box made with 18mm PVC board and matt enamel white paint finish at outside and matt enamel black paint finish at inside	
23	Planter box (type -2)	8	nos	Supply, Fitting & Fixing of 48"x12"x12" sized planter box made with 18mm PVC board with matt enamel white paint finish at outside and matt enamel black paint finish at inside and 48"x12"x18" frame made with 12 mm solid bar with 1"x 1" angle with powder coat finish with indoor plants and stones	
24	Planter box (type -3)	16	nos	Supply, Fitting & Fixing of 16"X16"X16" sized planter box made with 3/4" plain partex board and matt enamel white paint finish at outside and matt enamel black paint finish at inside	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (Yes/No)
25	Paint Works	3800	sft	Supply, Fitting & Fixing of all wall washable luxury silk or easy wash paint work with all necessary undercoatings	
26	Floor Cutting	3000	sft	Three phase mosaic cut with machine for polishing and glossiness of the mosaic floor	
27	Miscellaneous works	1	job	regular site cleaning; site mobilization;head Carrying from outdoor to site, trasnportations;etc	
	Total Others works				
	TOTAL				

INTERNAL ELECTRICAL WORKS

SL. NO.	DESCRIPTION OF ITEMS	UNIT	QUANTITY	Bidders Compliance (Yes/No)
1.0	PVC PIPE			
i)	3/4" PVC Pipe	Rft.	1,000.00	
ii)	1" PVC Pipe.	Rft.	1,200.00	
iii)	3/4" PVC Bend.	Doz.	6.00	
iv)	3/4" PVC Socket.	Doz.	8.00	
v)	3/4" Circular Box.	Doz.	4.00	
vi)	1" Circular Box.	Doz.	4.00	
vii)	1" PVC Bend.	Doz.	3.00	
viii)	1" PVC Socket.	Doz.	3.00	
2.0	CABLE-BRB / PARADISE/BBS/EQUIVALENT			
ii)	Cable : 1C/1.5 Rm(BYA) pvc insulated non-sheathed single core cable	Coil	20.00	
iv)	Cable : 1C/2.5 rm.(BYA)-pvc insulated non-sheathed single core cable	Coil	12.00	
v)	Cable : 1C/4.0 rm.(BYA) pvc insulated non-sheathed single core cable	Coil	16.00	
vi)	Cable : 1C/10 rm(BYA) pvc insulated non-sheathed single core cable	Coil	2.00	
vii)	Cable : Internet Cat-6 ethernet cable (PANDUIT or equivalent)	Box	3.00	
3.0	SWITCH MK TYPE/ART DNA/SCHNEIDER/LEGRAND/ EQUIVALENT			
i)	One Gange Switch	Nos.	3.00	
ii)	Two Gange Switch	Nos.	5.00	
iii)	Three Gange Switch	Nos.	15.00	
iv)	20A DP Switch	Nos.	2.00	
4.0	SOCKET MK TYPE/ART DNA/SCHNEIDER/LEGRAND/ EQUIVALENT			
i)	10A 2 Pin Socket	Nos.	40.00	
ii)	13A 3 Pin Combined Socket	Nos.	75.00	
iii)	TV Socket.	Nos.	2.00	
iv)	Data Socket. (Double)	Nos.	35.00	
5.0	LIGHT FIXTURE			
i)	LED Panel Light-28 watt	Nos.	95.00	
ii)	COB 10/12watt conceal spot light (Light Color :Daylight :4000k) CREE / Equivalent	Nos.	25.00	
iii)	LED Track Light (Light Color :Daylight :4000k) Chipset: CREE / Equivalent	Nos.	15.00	
6.0				
i)	Plastic Box. MK	Nos.	195.00	

Note:

1. The bidder will prepare the work plan accordingly. Work plan to be prepared as per the flow of activities described under

Annex-5

Key Persons for carrying out this assignment

- Team Leader must have minimum 5 years of experience in leading the team with Diploma in Architecture
- The Site Engineer/s must have 2 years of working experience in similar task with Diploma in Engineering

Other Conditions to comply:

1. Any faulty product during delivery would be replaced immediately
2. Repair and replacement of any damaged items within 6 months after final handover
3. Applicable warranty as per BOQ above will be considered

The Bidders have to include all costs connected with the execution of works into their price offer (such as supply of all materials and equipment, travel, living allowances, salary of staff, stationary, etc.).