# Q & A sent through email

Assignment Name:

### RFQ/UNDP/EU/008/2015 Renovation of SPO Project Office, Building C, 5<sup>th</sup> Floor, Ministry of Agriculture

#### <u>Closing Date and Time:</u> Thursday, 19 March 2015 , at close of business Jakarta Local Time

## **TO ALL INTERESTED BIDDERS**

#### Here below are Answers to Questions raised regarding the above assignment:

NO	Q & A	
1	Q	The BOQ, page 11- described that the downlight is using LED 120cm but in Annex 4 Drawing said it using TL. Please explain. LED Stripe or TL?
	А	It must use TL
2	Q	For sprinkle in existing building, can we remove them? As there is drop ceiling in the in the area that will be designed.
	A	The sprinkle can not be removed but it can be lowered below level of drop ceiling. The speaker and smoke detector can be remove
3	Q	Whether or not placement of coffee table is near the entrance to the lounge area? As it did not explain in Annex 4 Drawing but it's mentioned in the BOQ.
	Α	The coffee table should be removed from BOQ
4	Q	Please explain what model of roller blind required in BOQ (Supply install plantation). Roller blind or vertical blind?
	А	Please delete roller blind in BOQ.
		It must use roller blind
5	Q	Please inform whether the renovation work will be started after working hours (during the week end) or on Saturday and Sunday only?
	A	The renovation work is from Monday – Friday after 5pm till evening time. For Saturday – Sunday can be arranged with building management
6	Q	The requirement of glass partition in working area is not mentioned in BOQ, please explain whether the glass partition have to be covered by film sticker or sandblast?
	А	It has to be covered by film sticket
7	Q	Please explain brand and color preference for parquet floor

	А	There is no specific brand. The thickness is 8 mm
8	Q	Please explain alternate 1 and alternate 2 in matrix content of furniture & if the desk in alternative 2 is build in?
	A	If bidder can not provide requirement as alternate 1 then use alternate 2. In Alternate 1: it is split desk, Alternate 2: connecting desk.
9	Q	Is there a new panel? If yes, please inform the posititon
	А	Not necessary, the panel straight to AHU on the 5th floor
10	Q	How long is the length of new cable lane to existing panel?
	А	± 50 - 60 meter
11	Q	Please inform whether the position of data outlet is under the desk of floor
	А	Floor
12	Q	Please explain the position of outdoor unit AC, how long is the pipe
	А	It is located outside the window with 2-3m length
13	Q	Please inform the location of AC disposal pipe?
	А	Outside the window
14	Q	If the position of the outlet is under the desk, is there a need to provide duet cable?
	А	Outlet is on the floor

Jakarta, 16 March 2015