



UNITED NATIONS DEVELOPMENT PROGRAMME

ITB 2015-203

PAL10-PAL10-00000049740: Construction of 300 Residential Units in Rafah
Package # 16 (External painting)

Electronic copy of the BOQ shall be submitted along with the signed hard copy thereof. In case of any discrepancy between the soft and the hard copies, the hard copy shall prevail.

B.o.Q.

Item No.	Description	Unit	Quantity	Unit Rate US \$ (letters)	Unit Rate US \$	Total Amount US \$
	<p>Rates include:</p> <p>1-The Contractor shall visit the Site and investigate all the items.</p> <p>2-Colors need to be approved by engineer before work.</p> <p>3-All the painting materials used should be approved and tested by approved local laboratory and they should have the final approval from the supervisor engineer for each batch of paints delivered to the site.</p> <p>4-The price includes Scraping all flacked off paint, repairing all cracks, completing the plaster and preparing the walls according to specifications and engineer instructions before the commencement paint.</p> <p>5-The surface must be dry and clean from the sand dust, etc before painting.</p> <p>6- All painting works should provide the required coverage.</p> <p>7- All painting works must be according to the specifications, drawings and supervisor engineer instructions.</p> <p>8-The Price includes cover all furniture, windows and doors by polyethylen sheets in order to preserve them clean. Price includes cleaning of the site. and all the structural facilities(Doors, windows, electrical, A.C. & plumbing Fixtures) and Polishing the tiles and repair any defect occurring through work on his own expensive.</p> <p>9-The work includes dismantle and reinstall Electrical fitting& any equipments, fittings and etc. that may disturb the work. all according to the engineer instructions.</p> <p>10- Price include any needed issues to protect existing works such as tiles, manholes,..etc before commeneceement activities.</p> <p>11- Providing scaffolding and all necessary to mitigate safety measurments.</p>					
1	Supply and Paint, external decorations with one coat of Pendrole primer and at least two coats of External quality of colored emulsion (Weather Shield) or equal approved as specification and drawings	M ²	54000			
2	Painting after smoothing and filling all the voids with putty, primer coat, undercoat and at least two oil coats for steel single door SD1 (110 x230cm) for entrance, complete with frame -painting for the internal and external sides	No.	100			
	Total					-

Summery:

Bill No	Description	Total (Us \$)
Bill No (1)	Painting WORKS	
VAT (0%)		
Total		

Total in numbers

Total in letters

Name of the contractor

Authorized signature

Signature and Sealing

Title

Telephone

Fax

Mobile