

## QUESTIONS AND ANSWERS REPORT

<b><u>To:</u></b>	Bidders / Offerors
<b><u>From:</u></b>	UNDP Lebanon
<b><u>Subject:</u></b>	Extension of Water Network in Myriata, Zgarta Caza
<b><u>Reference:</u></b>	LEB/CO RFQ/215/15
<b><u>Date:</u></b>	04/12/2015

UNDP Lebanon Procurement Unit has received several questions regarding the subject Tendering Procedure. All questions received to-date are documented below with respective answers.

Questions and Answers		
1	<p><b>Q.</b> After checking item 3.22 concrete encasement as shown in drawings, the quantity given in the B.O.Q. is not reasonable it is very low. The lean concrete in the drawings is not listed in the B.O.Q</p> <p><b>A.</b> <b>Regarding the low concrete encasement quantity issue, please note that I have mentioned this item in case we have any crossings less than 30 cm between the water network and other existing utilities on site, and no data about these utilities are available to determine the actual concrete encasement quantity. The contractor shall determine this quantity if needed on site after approval of the engineer on site.</b></p> <p><b>Concerning the lean concrete, it is included in air release and washout valves items in the BOQ as blinding concrete</b></p>	
2	<p><b>Q.</b> In the BOQ, Item No. (2.1-A) we have "cutting of pavement roads"; the question is: in which item the asphalt works included?</p> <p><b>A.</b> <b>The municipality will be asphaltting after completion of works. Accordingly, we have an item for asphalt cutting but no items for re-asphalting</b></p>	