

SCHEDULE OF FINISHES- PHCC-SDC KOBBEH

	Location					
Finishes	Main Entrance corridor	Reception area	Exam room's Corridor, waiting area	Waiting area for childrens	All Exam rooms, filing room, sterilization room, pharmacy,nursing ,manager room	Toilets
C-Ceiling	C1- Gypsum board suspended ceiling, at -35 cm from ceiling, Plaster and paint anti bacterial white color mat finish	C1- Gypsum board suspended ceiling, at -35 cm from ceiling, Plaster and paint anti bacterial white color mat finish	C1- Gypsum board suspended ceiling, at 35 cm from ceiling, Plaster and paint anti bacterial white color mat finish	C1- Gypsum board suspended ceiling, at -35 cm from ceiling, Plaster and paint anti bacterial white color mat finish	C1- Gypsum board suspended ceiling, at -20 cm from ceiling, Plaster and paint anti bacterial white color mat finish	C2-Aluminium strips suspended ceiling
W- Walls	W1-Plaster and paint satin white color antibacterial	W1-Plaster and paint satin white color antibacterial	W1-Plaster and paint satin white color antibacterial	W2-Plaster and paint satin yellow color antibacterial with a special design, protective foam to wall angles and columns	W1-Plaster and paint satin white color antibacterial	W3-Glazed ceramic wall tiles 400*200 x 8mm thickness
F-Floor	F1-Terrazo tiles and Linoleum mist grey color	F1-Terrazo tiles and Linoleum mist grey color	F1-Terrazo tiles and Linoleum mist grey color	F1-Terrazo tiles and Linoleum mist grey color and mat foam puzzle	F1-Terrazo tiles and Linoleum mist grey color	F2-Anti slippery, Unglazed ceramic floor tiles 400 x 200 x 8mm thickness
S-Skirting	S1-Linoleum	S1-Linoleum	S1-Linoleum	S1-Linoleum	S1-Linoleum	S1-Linoleum