

Attachment-I-

Title: HATAY REYHANLI SOLID WASTE TRANSFER STATION

REVISED BILL OF QUANTITY FOR CONSTRUCTION WORKS

NO	POSE NUMBER	UNIT	TYPE OF WORKS	QUANTITY	UNIT PRICE (\$)	AMOUNT (\$)
1	15.140/İB-4	m ³	Granitometric sand-graveling (08 009 / İB-2) in each of the categories is hand-tightened to make trenches and foundation pavement, pipe basin bedding and pipe linings	159,600		
2	23.255/İB-6	Each	Ductile casting and replacement of flue-ducts in sewerage constructions (spherical graphite cast iron)	4,000		
3	23.255/İB-7	kg	In the construction of sewage and rainfalls; Ductile iron grating	2.720,300		
4	23.260/İB-1	m	Construction of reinforced concrete gauze with post of 2 63 m height and protective fences	210,300		
5	B-15.044	km	Leveling and fine-reglacing on all kinds of grounds (on the road)	0,300		
6	INS-001	m ²	Construction of polyurethane paint	201,210		
7	INS-002	Pcs	Bunker manufacturing and assembly from galvanized and steel	1,000		
8	INS-003	Pcs	Making traffic signs	8,000		
9	INS-004	Pcs	Construction site signboard with foot pedestal	1,000		
10	INS-005	Pcs	False acacia, tar backing, bonnet, pine tree trunks and planting	16,000		
11	INS-006	Pcs	Container security club installation and installation (270x270)	1,000		
12	INS-007	Pcs	Container installation and assembly 3x7m (2 rooms, wc-shower, kitchen)	2,000		
13	KGM/15.150/K	m ³	Figure (Sand, Gravel, Crushed stone, Stabilize etc.)	1.956,000		
14	KGM/16.122/K-H	m ³	Concrete Coating of Ditches (Medium Refuge and Splitting Hint) (with C 20/25 Ready Mixed Concrete Filler)	27,703		
15	KGM/16.139/K	m ³	Prefabricated Drainage Pile Construction and Replacement (with C 30/37 Ready Mixed Concrete Filler)	2,560		
16	KGM/2205	m ³	Watering and squeezing all kinds of soil	20,349		
17	KGM/2540/K	m ³	Refuge, Surrounding Surroundings, Heat Exchangers and Plain Soils (plant or warehouse)	235,810		
18	KGM/37.556/K	Da	Grass seed sowing	235,810		
19	KGM/60.206	m ²	Crosswalks with double-component paint, warning of deceleration and drawing of strip lines (2 mm thickness)	60,000		
20	KGM/6000	m ³	Subcontracting with Crushed Material from Crusher	978,000		

Attachment-I-

Title: HATAY REYHANLI SOLID WASTE TRANSFER STATION

REVISED BILL OF QUANTITY FOR CONSTRUCTION WORKS

21	KGM/6040	m ³	Foundation construction [with crushed and screened quarry stone (1 inch)]	978,000		
22	MSB.521/B2	m ²	Roof coating with painted trapezoidal section sheet	283,260		
23	N.YF.01	Ton	Cement transfer	0,160		
24	N.YF.03	m ³	Sand, Gravel transporter	3.059,364		
25	N.YF.04	m ³	Fine plaster sand	0,399		
26	N.YF.05	Ton	Wire mesh stell transportation	30,861		
27	N.YF.07	Ton	Iron transfer	106,412		
28	N.YF.08	Ton	Iron sheet transport	3,962		
29	N.YF.15	m ³	Concrete parquet, borders, lawn, gutter, transport	21,131		
30	N.YF.26	Ton	Profile transport	3,143		
31	N.YF.27	m ³	Stabilize and transport crushed stone	1.956,000		
32	N.YF.32	Ton	Transportation of truck excavation material outside the construction site boundaries	7.351,242		
33	Y.15.006/1A	m ³	Excavation of soft and hard hull with machine (free excavation)	531,200		
34	Y.15.006/2B	m ³	Excavation of soft and hard hulls at every depth and width with the machine (Deep excavation)	1.066,896		
35	Y.15.014/2B	m ³	Excavation of hard rocks at every depth and width using explosive material with machine (Deep excavation)	1.066,896		
36	Y.15.014/4A	m ³	Hard rock excavation without using explosives (free excavation)	531,200		
37	Y.15.140/04	m ³	Supply of gravel and flooring, irrigation and compression by machine.	2.884,464		
38	Y.16.050/12	m ³	Concreting of C 12/15 compressive strength class concrete being manufactured at a concrete plant or purchased (including concrete transport)	109,848		
39	Y.16.050/15	m ³	Concreting of C 25/30 compressive strength class concrete being manufactured at a concrete plant or purchased (including concrete transport)	792,600		
40	Y.16.050/16	m ³	Concreting of C 30/37 compressive strength class concrete being manufactured at a concrete plant or purchased (including concrete transport)	952,937		
41	Y.17.301/03	m	1,50 m in height Ø 4.5 mm in diameter 50 x 150 mm eye spacing min. 3 fenced hot-dipped galvanized fence with electrostatic polyester powder painted panel tether (application on the wall with 2.5 m gap)	97,200		
42	Y.18.460/24	m	Ø 200 mm nominal diameter, PVC-based corduroy drainage pipe and its replacement	292,770		

Attachment-I-

Title: HATAY REYHANLI SOLID WASTE TRANSFER STATION

REVISED BILL OF QUANTITY FOR CONSTRUCTION WORKS

43	Y.21.001/03	m ²	Production of reinforced concrete plain surface form works with plywood	2.991,146		
44	Y.21.050/C11	m ³	Mold Scaffolding of steel pipes (0,00 - 4,00 m)	635,583		
45	Y.21.050/C12	m ³	Mold scaffolding from steel pipe (4,01-6,00 m)	1.296,627		
46	Y.21.050/C13	m ³	Mold scaffolding from steel pipe (between 6,01-8,00m)	641,449		
47	Y.23.010	Ton	Replacement of rolled steel mesh 1,500-3,000 kg / m2 (including 3,000 kg / m2)	30,108		
48	Y.23.014	Ton	Cutting, bending and placement of Ø 8- Ø 12 mm deformed concrete steel bars	27,103		
49	Y.23.015	Ton	Cutting, bending and placement of Ø 14- Ø 28 mm deformed concrete steel bars	72,854		
50	Y.23.071	Ton	The preparation and replacement of all kinds of profiled iron individually or in combination (looms made in love, scrap pavers, continuous beams, individual roof looms and tiles used in simple manner, lentals, scrap pavers)	0,481		
51	Y.23.176	kg	Making and replacing various iron works from lama and profile iron	4.778,090		
52	Y.26.017/021	m ²	Covering with 6 cm high white cement steam cured concrete paving stone (every size, color and desende)	153,000		
53	Y.26.017/065	m	50 x 20 x 10 cm normal cement steam cured concrete borders (pricey, every color)	200,000		
54	Y.26.017/067	m	75 x 30 x 15 cm normal cement steam cured concrete borders (pricey, every color)	65,000		
55	Y.26.017/125	m	30 x 10 x free size cm sized white cement steam cured concrete slab laying (every color)	134,000		
CONSTRUCTION WORKS SUB-TOTAL						