



**CONSERVATION WORKS AT AGIOS PHILON (AYFILON) ARCHAEOLOGICAL SITE  
LOCATED IN KARPASIA/KARPAZ**

**REF: UNDP-RFQ-121/2017**

**Clarification no: 1, dated 15 November 2017**

No	Questions	Answers
<b>Q1</b>	Is engineering site office not included in BOQ?	Bill item no. 3 under the General & Preliminary; requirement is added. (REV. 1)
<b>Q2</b>	In BOQ sch_A only cleaning the pit inside church is included (item d) what about cistern and well mouth?	Cistern & well mouth is added to the bills as item 1e' under Schedule A. (REV. 1)
<b>Q3</b>	In BOQ sch_A Item (n).... River sand is not available? All the quarries are closed... Should we consider yellow sand collected from sea shore?	Sea sand is saline and acidic and not compatible with the alkaline nature of the covering materials. A request will be made for obtaining river sand.
<b>Q4</b>	In BOQ sch_B- Item 1.b "... 10x20 galvanized frame (6m) ..." ... What 6m is means here? Perimeter of frame or linear length of frame? BOQ amount shows 65 No's.	Each 'No' corresponds to a 6m length of iron element.
<b>Q5</b>	Two gates (one for disabled access and one for main entrance) are mentioned in drawings but no money allowed in BOQ.	Gates are considered within the quantities of the metal elements item 1a of Schedule A.
<b>Q6</b>	Specs and drawings specify North limit wall to be raised to 1mt however nothing allowed in BOQ.	Item 1a of Schedule A is envisaged to cover this activity of stone works.