

Bid Bulletin 03
IRQ-ITB-213/19

**Rehabilitation of Oncology Hospital in Al Shifaa Hospital Complex-
West Mosul-Ninawa Governorate**

Questions	Answers
1. Does it required to add the sentence "The bid security's validity is 150 days from the date of bid submission deadline" at the end of the bid security form?	<p>Please refer to Data Sheet, Point # 6 (Bid Security). Yes, you can add the sentence, however, you can also ensure that while making the bid security it should remain valid for 150 days from the date of deadline.</p> <p>Bid Security Validity: 150 Days from the date of deadline.</p> <p>IMPORTANT: Please note if the submitted bid security's validity is less than 150 days from the date of bid submission deadline, the bid will be rejected.</p>
2. Does there a need to stamp the drawings?	Stamping on the drawings is not required at this stage however, selected bidder will be required to stamp all drawings once the contract is awarded.
3. Does the bid security must carry the name of the JV or the name of any party of the JV?	The bid security could be in the name of the lead party or JV partners.
4. Please we need the technical specifications for high voltage ring main unit (RMU).	Kindly refer to electrical compliance sheets. Also, it is complying with Iraqi standard D07 attached.
5. Please we need the technical specifications for lighting fixtures (L19, L20 & L21).	<p>L19 : 60cm x 60cm fluorescent lighting fixture, as per Linear Accelerator Specialist and previous coordination with him.</p> <p>L20 : 50w halogen down light, as per Linear Accelerator Specialist and previous coordination with him.</p> <p>L21 : Linear fluorescent lighting fixture, with emergency kit for 3 hours duration. as per Linear Accelerator Specialist and previous coordination with him.</p>
6. Are the low voltage diesel generators units (4x1250 KVA) are using indoor or outdoor?	The Gen sets are located indoor in the electrical service building in the site. Please refer to the drawings
7. Are the units mentioned above are individual to be used as emergency to main or units are synchronizing back up if main fails?	The Gen sets are prime type and they are synchronized .
8. Does the uploaded structural drawings are the complete set of structural drawings?	Yes.
9. We need clear description and details of the underground structure that needs demolishing. Same thing for all parts needs demolishing.	All existing building to be demolished including the existing foundation, it's very clear in the scope of work. The contractor should visit the site to estimate his efforts and cost.
10. Please advise about the related drawing for the Item# 15.34.11.1 Medical gas terminal unit	Please refer to the drawings EL 202 / EL 203 specification section 15480 clause 2.6 /L5.