

Amendment-1a-Annex-1-RFQ-BD-2019-027

BOQ & Bidder's Compliance -Annex 1

Interior project of 14th Floor @ IDB Bhaban, Dhaka

S/N	Items	Quantity	Units	Specification	Bidders Compliance (yes/ No)
Design & Management Services					
BOARD WORKS					
1	Full Height Cabinet	316	sft	Supply, Fitting & Fixing of Full Height Cabinet made with 18mm Gorjon Ply Board (from Partex Star OR EQUIVALENT) and light Grey Matt enamel Paint Finishing with all necessary under-coatings with front cabinet door made with 18mm White TEXTURED MELAMINE BOARD including all accessories. (Height 9.5' and depth 16")	
2	Low Height Cabinet (Type-01)	300	sft	Supply, Fitting & Fixing of Full Height Cabinet made with 18mm Gorjon Ply Board (from Partex Star OR EQUIVALENT) and light Grey Matt enamel Paint Finishing with all necessary undercoatings with front cabinet door made with 18mm White TEXTURED MELAMINE BOARD including all accessories. (Height 42" and depth 16")	
3	Low Height Cabinet (Type 02)	52	sft	Supply, Fitting & Fixing of Full Height Cabinet made with 18mm Gorjon Ply Board (from Partex Star OR EQUIVALENT) and light Grey Matt enamel Paint Finishing with all necessary undercoatings with front cabinet door made with 18mm White TEXTURED MELAMINE BOARD including all accessories. (Height 30" and depth 16")	
4	pantry cabinet	38	sft	Supply, Fitting & Fixing of Pantry Cabinet made with 18mm Marine Ply Board and light Grey Matt enamel Paint Finishing with all necessary undercoatings with front cabinet door made with 18mm Melamine boards including all accessories.	
5	Feature Wall	360	sft	Reception & other wall custom made feature works as a designed wall made with 18mm and 12mm particle board and STRING ART works, Glass Logo and other works as per design.	
6	Full Height partition (Dry Wall)	2119	sft	Supply, Fitting & Fixing of Dry wall partition made with 12mm Gypsum board with minimum 3 hours fire rating pasted on both side and Structure made with 3" Metal C Profile & 2"X2" Farin channel, including all other hardwares & accessories.	
7	Drop Wall Partition (Dry Wall)	103	sft	Supply, Fitting & Fixing of Dry wall partition made with 12mm Gypsum board with minimum 3 hours fire rating pasted on both side and Structure made with 3" Metal C Profile & 2"X2" Farin channel, including all other hardwares & accessories.	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (yes/ No)
	Total Board Works				
Glass Works					
8	Glass Door	5	nos	Supply, Fitting & Fixing of 3'x8' custom ordered glass door with white glass , locally tempered with all door accessories(the floor spring should have the load capacity from 80~100kgs & min. 2 years of warranty) and custom made 48" long wooden door handles with lacquer finishing.	
9	Glass feature wall	110	sft	Supply, Fitting & Fixing of 16mm sandwiched customized sized tempered freestanding white glass installation with MS Frame support at the top & fixed with SS U channel or Aluminium Profile box	
10	Glass partition	748	sft	Supply, Fitting & Fixing of 10mm Chines tempered glass (with colored film) line finish with Silicon and installation with MS Hollow box sized 1"X2" and fixed with SS (Stainless Steel) U channel or Aluminium Profile Box.	
11	Glass writing board	25	sft	Supply, Fitting & Fixing of 10mm Chines non-tempered glass with SS (Stainless Steel) knob on wall surface or on free standing screening surfaces	
	Total Glass Works				
CUSTOM MADE FURNITURE				some special feature light	
12	Workstation	16	nos	Supply, Fitting & Fixing of prefabricated workstations as per design with white melamine top and metal legs with frame and movable side desks (minimum table top size required as 72"X72" L shaped) cable cap, trays & all other accessories are included	
13	Workstation partitions	140	rft	Supply, Fitting & Fixing of Workstation partitions with a maximum height of 54" and thickness is 2" (42" heightened solid partition made with 18mm textured Melamine board pasted on both side and 12" heightened 10mm White glass on top). Inside, the structure is made with 1"X1" hollow metal box.	
14	portable Hot Desks	9	nos	Supply, Fitting & Fixing of pre-fabricated portable hot desks (folded options can be added) as per design (table sizes and shapes can be varied as per availability of design and sizes) power & Data ports	
15	Executive Desks	1	nos	Supply, Fitting & Fixing of Table sized (8'X7'X30") prefabricated Executive desks with side desk and drawer unit as per design with power & data ports	
16	Center Table	6	nos	Supply, Fitting & Fixing of pre-fabricated Tables sized 2ft diameter 10mm tempered glass on top ; SS (Stainless Steel) support with matt finishing and SS glass knobs	
17	Conference Table (5'X16')	1	nos	Supply, Fitting & Fixing of pre-fabricated Board meeting Table sized 5'X16' with melamine top & metal or Aluminum	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (yes/ No)
				Structured meeting table and comes with integrated power & Data ports	
18	Chair	40	nos	Supply, Fitting & Fixing of desk & meeting room chairs with minimum one year Warranty	
19	Round table (30" diameter)	1	nos	Supply, Fitting & Fixing of pre-fabricated Table sized 30" diameter 10mm tempered glass top on SS (Stainless Steel) support with matt finishing and SS glass knobs or imported Aluminum framing.	
20	Round table (36" Diameter)	4	nos	Supply, Fitting & Fixing of pre-fabricated Table sized 36" diameter ; 10mm tempered glass top on SS (Stainless Steel) support with matt finishing and SS glass knobs or imported Aluminum framing.	
21	Reception Desk @ Lift Lobby	1	pcs	Supply, Fitting & Fixing of designed custom made reception desk with 6' length and 42" height made with 18mm Gorjon ply board with drawer unit and DUCO paint finishing.	
22	Single Seater Sofa	9	pcs	Supply, Fitting & Fixing of single seater relax sofa as per design, made with fabric or artificial leather with SS legs.	
23	Sofa set (2+2+1 seater)	2	sets	Supply, Fitting & Fixing of sofa set as per design, made with fabric or artificial leather with SS legs.	
24	breakout corner high chair	2	pcs	Supply, Fitting & Fixing of stool with standard height as per design with wooden or Metal legs	
25	breakout corner long couch	1	pcs	Supply, Fitting & Fixing of designed custom made sofa couch made with gorjon & Mehgoni wooden frame and Burma teak wood/ SS(matt) leg with imported fabric covers from Weavers	
26	Low Height seaters	3	pcs	Supply, Fitting & Fixing of imported low heights round or square stools made with high quality fabric or artificial leather and SS legs	
		Total Custom-made Furniture			
OTHERS					
27	Signage & Logo	22	pcs	Supply, Fitting & Fixing of Different Logos, signages or branding materials with acrylic (5mm) or wooden laser cut encripteions or framings at different locations of each floor and UNRCO and UN logo at major locations	
28	Lamp shade/ light	2	pcs	Supply, Fitting & Fixing of imported tripod stand lamps with minimum of one years of waranty as per design	
29	Resource corner with stepped seating with Cabinet	0	job	Supply, fitting & Fixing of Custom-made Resource corner gallery seating made with 18mm Barma Teak Veneer Ply board outside and 1"X2" Grojon wood framing inside and open book cabinet at back and colorful couison seatings on top as per design. Size of the gallery is 17'X6'X4'	
30	Screening Work	2	pcs	Supply, Fitting & Fixing of metal screenig works with 2"X2" hollow metal box border and 1"X2" hollow metal box in the	

S/N	Items	Quantity	Units	Specification	Bidders Compliance (yes/ No)
				middle with powder coated matt finishing and both side white writing boards fixed with the screen as per design	
31	Chair for discussion tables & silent rooms	19	pcs	Supply, Fitting & Fixing of imported designer chairs as per design	
32	roller blinds	1725	sft	Supply, fitting, fixing of Imported (Malaysian) vertical roller blinds with high quality finishings custom sized as per window sizes	
33	Paint Works	5354	sft	Supply, Fitting & Fixing of all wall washable luxury silk or easy clean paint work with necessary undercoating	
34			Dismantling & Miscellaneous Works		
	Glass Partition & Glass Door Dismantling	2400	sft	Existing Glass partition and Glass door dismantling work rubbish cleaning & carrying out of the building premises.	
	Dry wall (Gypsum & Partex Board) Partition Dismantling	3200	sft	Existing Dry wall partitions dismantling work rubbish cleaning & carrying out of the building premises.	
	Miscellaneous Works	1	job	Regular Site cleaning, site maintenance, carrying & Lifting costs etc.	
	Total Others works				
34	Electrical & IT Works			Detail Given Below	

ESTIMATED BILL OF QUANTITIES FOR ELECTRICAL & COMMUNICATION SYSTEM

UNDP OFFICE AT DHAKA, BANGLADESH

14TH FLOOR

INTERNAL ELECTRICAL WORKS

SL. NO.	DESCRIPTION OF ITEMS		UNIT	QUANTITY
1.0				
	PVC PIPE			
	i)	3/4" PVC Pipe	Rft.	840.00
	ii)	1" PVC Pipe.	Rft.	960.00
	iii)	3/4" PVC Bend.	Doz.	6.00

	iv)	3/4" PVC Socket.	Doz.	8.00
	v)	3/4" Circular Box.	Doz.	4.00
	vi)	1" Circular Box.	Doz.	4.00
	vii)	1" PVC Bend.	Doz.	3.00
	viii)	1" PVC Socket.	Doz.	3.00
2.0	CABLE-BRB / PARADISE/BBS/EQUIVELENT			
	ii)	Cable: 1C/1.5 Rm (BYA) pvc insulated non-sheathed single core cable	Coil	20.00
	iv)	Cable: 1C/2.5 rm. (BYA)-pvc insulated non-sheathed single core cable	Coil	10.00
	v)	Cable: 1C/4.0 rm. (BYA) pvc insulated non-sheathed single core cable	Coil	15.00
	vi)	Cable: 1C/10 rm (BYA) pvc insulated non-sheathed single core cable	Coil	2.00
	vii)	Cable: Internet Cat-6 ethernet cable (PANDUIT or equivalent)	Box	3.00
3.0	SWITCH MK /ART DNA/SCHNEIDER/LEGRAND/ EQUIVALENT			
	i)	One Gang Switch	Nos.	3.00
	ii)	Two Gang Switch	Nos.	5.00
	iii)	Three Gang Switch	Nos.	15.00
	iv)	20A DP Switch	Nos.	2.00
4.0	SOCKET MK /ART DNA/SCHNEIDER/LEGRAND/ EQUIVALENT			
	i)	10A 2 Pin Socket	Nos.	52.00
	ii)	13A 3 Pin Combined Socket	Nos.	82.00
	vi)	TV Socket.	Nos.	3.00
	vii)	Data Socket. (Double)	Nos.	35.00
5.0	LIGHT FIXTURE			
	i)	COB 10/12watt conceal spot light, (Light Color :Daylight :4000k) Chipset: CREE / Equivalent	Nos.	12.00
	ii)	LED Hanging dish Lamp (Light Color :Daylight :4000k) Chipset: CREE / Equivalent	Nos.	4.00
	iii)	LED Track Light COB (12~15W) (Light Color :Daylight :4000k) Chipset: CREE / Equivalent with 48" long Aluminium Track Channel	Nos.	40.00
6.0				
	i)	Plastic Box. MK	Nos.	195.00

Note:

1. The bidder will prepare the work plan accordingly. Work plan to be prepared as per the flow of activities described under Annex-5

Key Persons for carrying out this assignment

- Team Leader must have minimum 5 years of experience in leading the team with Diploma in Architecture
- The Site Engineer/s must have 2 years of working experience in similar task with Diploma in Engineering

Other Conditions to comply:

1. Any faulty product during delivery would be replaced immediately
2. Repair and replacement of any damaged items within 6 months after final handover
3. Applicable warranty as per BOQ above will be considered

The Bidders have to include all costs connected with the execution of works into their price offer (such as supply of all materials and equipment, travel, living allowances, salary of staff, stationary, etc.).