MINISTRY OF LOCAL GOVERMENT, PUBLIC WORKS AND NATIONAL HOUSING -VARIOUS CENTRES
SCHEDULES OF MATERIALS FOR : LOW COST BOARDING FACILITIES ABLUTIONS.
DESCRIPTION OF WORKS:CONSTRUCTION OF AN ABLUTION BLOCK

UNIT	QTY	MATERIAL DESCRIPTION	UNIT PRICE	TOTAL
m3	10	river sand		$ -
m3	5	19mm concrete stones		$ -
bags	100	PC 15 cement		$ -
m3	15	pit sand		$ -
no	15000	common bricks		$ -
rolls	30	115mm brick force x20m roll		$ -
rolls	20	230mm brick force x20m roll		$ -
sheets	5	2.4 x 6m S193 mesh wire		$ -
tins	4	5ltr termite poison		$ -
rolls	5	115mm DPC X20m roll		$ -
lens	20	114mm x 38mm x 6m R/S timber		$ -
lens	4	150mm x50mm x 6m R/S timber		$ -
sheets	15	2.1m enduirite asbestos sheets		$ -
sheets	6	2.7m enduirite asbestos sheets		$ -
kgs	4	AC roof nails c/w washers		$ -
no	2	fibreglass toilet pan		$ -
tin	3	20ltr interior/exterior PVA paint ivory		$ -
tin	1	5ltr PVA int/ext black paint		$ -
tins	5	5ltr dove grey gloss paint		$ -
tin	1	1ltr universal undercoat		$ -
tins	2	2ltr steel primer		$ -
tin	1	5ltr carbolineum		$ -
tin	1	5ltr turpentine		$ -
m	100	250 micron black polythene paper		$ -
no	4	110mm PVC vent pipe		$ -
roll	12	breeze blocks 600 x 600		$ -
no	4	washing sinks 700 x 500		$ -
no				$ -
no				$ -
no				$ -
no				$ -
no				$ -
no				$ -
pkts				$ -
		TOTAL		**$ -**
