1- DO NOT SCALE THIS DRAWINGS (DIMENSIONS SHOULD BE CALCULATED NEVER SCALED).
2- ALL DIMENSIONS ARE IN MILLIMETER UNLESS OTHERWISE INDICATED.
3- ALL LEVELS ARE IN METERS UNLESS OTHERWISE INDICATED.
4- THIS DWG. IS TO BE READ IN CONJUNCTION WITH ALL OTHER ARCHITECHTURAL, STRUCTURAL, ELECTRICAL, MECHANICAL,&B.O.Q.
5- LEVELS ON ARCHITECTURAL DRAWINGS ARE FOR INFORMATION ONLY THE FINISH FLOOR LEVEL (F.F.L) IN THE ARCHITECTURAL DRAWINGS IS THE BASIS OF ALL LEVELS IN ALL OTHER TRADES (STRUCTURAL, ELECTRICAL, MECHANICAL...)

±0.00=1124.60

LINE OF BUILDING EXPANSION

SLOPPING RETAINING WALL FROM 1 M TO 5 M

SLOPPING RETAINING WALL FROM 1 M TO 5 M

-0.295
1124.305

-0.289
1124.311

INCINERATOR
DISPOSAL PIT
WASTE
PREP AREA
RECYCLE
SHOWERS AND TOILETS
JUNCTION
LOCKERS
STORAGE
BATTERY CHARGING
BATTERY SHORE FOR SOLAR PANEL BATTERIES
5640 AIR HANDLING UNIT 4.5X2.7 m
5640 AIR HANDLING UNIT 4.5X2.7 m
5640 CHILLED WATER PUMP ROOM 6m. X 3m
5640 CHILLED WATER STORAGE TANK 3 x 20m
AIR COOLED CHILLER
GENERATOR ROOM
MAIN LV ROOM
TRANSFORMER ROOM
UNDERGROUND FUEL TANK ROOM
Proposed Gate
WALK IN COOLER
LOCKERS
WAREHOUSE FLOOR AREA =2560M²
3996 PALLET LOCATIONS
ADDED: 324 PALLET LOCATIONS
PROPOSED TO BE ADDED
QUARANTINE CAGE
ACCESS CONTROLLED DOOR
TURNSTILE
HAZARD STORE
RECEIVING
REFUSE
DISPATCH
DOCK LEVELLER
3000mm x 3000mm DOOR
Water Borehole
TRUCK DROP OFF
UNDERGROUND STORM TANK
FF + IRRIGATION WATER TANK 360m³ FIRE FIGHTING AND 120m³ IRRIGATION 8m...x 15m...AREA 4m. WATER HEIGHT 4.5m. CONCRETE HEIGHT
UNDERGROUND WATER TANK POTABLE WATER TANK 90m³ 7m. X 4.5m. AREA 3m. WATER HEIGHT 4.5m. CONCRETE HEIGHT
UNDERGROUND PUMP ROOM 7m. X 9m. 4.5m. CONCRETE HEIGHT
RMU ROOM
Proposed Chainlink Fence
MESH CHAIN FENCE

-0.848
1123.752

RECEIVING ENTRANCE/EXIT

MESH CHAIN FENCE

DISPATCH ENTRANCE/EXIT

STAFF/ VISITORS ENTRANCE/EXIT

-1.491
1123.109

1122.5
1122.0
1121.5
1121.0
1120.0

**Proposed Street Level: 1123.134**

| INDEX | DATE | DESCRIPTION | DESIGNED BY | CHECKED BY | APPROVED BY |
|---|---|---|---|---|---|
| R6 | | | | | |
| R5 | | | | | |
| R4 | | | | | |
| R3 | | | | | |
| R2 | | | | | |
| R1 | | | | | |
| 0 | 04-06-20 | PRELIMINARY DESIGN | Y.A | M.M | M.ASEER |

THIS DRAWING IS THE PROPERTY OF COSMOS-E
AND MUST NOT BE REPRODUCED OR ITS CONTENTS DIVULGED WITHOUT WRITTEN PERMISSION

CLIENT

NatPharm
Access to Affordable Quality Medicines

MAIN CONSULTANT
COSMOS E
PROJECT DIRECTOR
Dr. MOHAMED HASANIN SERROR
DESIGN MANAGERS
Dr. MOHAMED ELADLY
80 ISMAILWA ELHABY (EXTRO), MASREN SHERATON, HELIOPOLIS, CAIRO, EGYPT.
Tel: (2002)26967760 - (2010)06809055 Fax(2002)26967761 P.code 11361
E-mail: info@cosmos-eg.com WEB : www.cosmos-eg.com

PROJECT TITLE
ZIMBABWE ( MUTARE ) MEDICAL WAREHOUSE

DRAWING TITLE
GROUND FLOOR PLAN GENERAL LAYOUT

PROJECT NO. Z2016
SCALE: 1:150

DRAWING NO. Z2016-0010-ADE-0012-0
PROJECT NUMBER | BUILDING NO. | DOC. DESCRIPTION | DOC. NUMBER | REV.