THE WORKS ARE FOR THE SUPPLY AND INSTALLATION OF ELEVATED ALLUMINIUM TANK FOR KERR JAIN, KERR NJUGARI AND KERR WALLY

Tank Capacity: 40 m3

Description	Units	Quantity	Unit Cost (GMD)	Total Cost (GMD)
Elevated Water tank of 40 M3 Capacity and Tower Hight of 6M Including Material for Civil and Installation -Bolted Aluminum Tank of 40 m3 capacity -Reinforced PVC Liner, Food grade quality -Mat protection Between shell and liner -Internal Ladder in composite PVC, food grade -Galvanized steel pipe works arrangement 3'' -U-PVC pipe works arrangement 2'' for drain and over flow water level indicator	No	1		
Transport cost -Civil Works - Installation Cost	LS	1		
TOTAL				-