

Bid Bulletin 01

IRQ-ITB-032-21

ITB-032-21 Rehabilitation of -Al Hussein Water Complex -Hay Al Hussein sub district, Basra Governorate-Iraq. GPS: 30.47912 N , 47.78802 E.

Questions	Answers
Bidder requested if there is any alternative source for providing the daily demanded water to the local beneficiaries during the Rehabilitation period of Al Hussein water Complex	Yes, there is an alternative source for providing the daily demanded water to the local beneficiaries during the Rehabilitation period of Al Hussein water Complex and this is the EU's (Sectoral section) responsibility, as they will put in advance a work plan to avoid shortage in providing the daily demand of water.
Bidder requested to change the spec. of the supplied low lift pumps (Ea.=3) in item # (2-c) in the BOQs from double section pump - to N- section pump .	EU. Agreed to change the supplied low lift pumps spec. followed by changing the spec. listed in the Compliance Sheet-Annex A- (item# 2) correspondingly.
Bidder requested if there is any prepared design or engineering drawings for the proposed supplied and installed Key Span Shade listed in item # (6) in the BOQs.	This is the contractor's responsibility to submit full design and engineering drawings for this item.
Bidder requested about the main title of item # (7) in the BOQs is a KEY SPAN SHADE for Chlorine Cylinders Unit or a Normal steel shade for Chlorine Cylinders Unit .	This is typo, as the required work in item # (7 & 7-a) listed in the BOQs is to install Normal steel shade for Chlorine Cylinders Unit (main title of this item must be corrected to (Normal Steel SHADE for . Chlorine Cylinders Unit).
Bidder requested is there any prepared design or engineering drawings for the (Normal steel shade for Chlorine Cylinders Unit) . Listed in item # (7-b) in the BOQs.	This is the contractor's responsibility to submit full design and engineering drawings
Bidder requested is there any prepared design or engineering drawings for the steel structure of the supplied and installed 3 tons crane listed in item # (7-c) in the BOQs	This is the contractor's responsibility to submit full design and engineering drawings, and to note that the new installed steel structure in this location should be as an extension and connected to the existing one.