

**Planning the parking lots in the  
central zone of Ungheni city  
(Alexandru cel Bun Street and  
Mihai Eminescu Street)**

Form No. 1  
WinCmeta

(name of the site)

**List with quantities of works**

**Bid value: USD**

No crt.	Symbol of the norm and resource code	Name of works	Unit of measure	Volume
1	2	3	4	5
		<b>1. Chapter I. Preparatory works</b>		
		<b>1.1. Demolishing the access paths and sidewalks</b>		
1	DI109	Mechanized scrapping of the asphalt concrete coating	m <sup>3</sup>	34.20
2	DG03A	Removing the sidewalks from existing pavement H=0.04 m	m <sup>2</sup>	97.00
3	TsC03F1	Loading the demolished material, road coating made of asphaltic concrete with the excavator of 0.40 m <sup>3</sup> , K=0.8	100 m <sup>3</sup>	0.381
4	TsI51A5	Transportation with the dumper of 10 t at a distance of 5 km	t	83.80
		<b>1.2. Demolishing the existing edging</b>		
5	DG04B	Dismantling stone or concrete borders of any size, placed on concrete	m	298.00
6	TsC03B1	Demolishing the concrete foundation	100 m <sup>3</sup>	0.14
7	TsC02D1	Loading the waste with the excavator of 0.25 m <sup>3</sup> , K=0.8	100 m <sup>3</sup>	0.271
8	TsI51A5	Transportation with the dumper of 10 t at a distance of 5 km	t	59.70
		<b>1.3. Demolishing the existing monolith concrete bulwark</b>		
9	PJ04B	Destroying the existing monolith concrete bulwark	m <sup>3</sup>	54.00
10	TsC03F1	Loading with the excavator of 0.40 m <sup>3</sup> , K=0.8	100 m <sup>3</sup>	0.54
11	TsI51A5	Transportation with the dumper of 10 t at a distance of 5 km	t	118.80

1	2	3	4	5
		<b>1.4. Resetting the wells at the project level</b>		
12	DG06B	Demolishing the concrete rings	m <sup>3</sup>	0.029
13	TsC02D1	Mechanical loading with the excavator of 0.25 m <sup>3</sup> , K=0.8	100 m <sup>3</sup>	0.001
14	TsI50A5	Transporting with the dumper of 5 t at a distance of 5 km	t	0.06
15	RpAcF04A	Pouring the walls of the manholes made of simple concrete, with depth of 2-4 m	m <sup>3</sup>	0.65
16	AcE07C	Mounting iron or iron-concrete covers without the support element, at the manholes of the water and sewerage supply installations, carriageable type III A and B (Setting the heavy cast iron covers, Type D400 or Type TM)	pcs	5.00
		<b>Total chapter 1 Incl. salary</b>	<b>USD USD</b>	
		<b>2. Car parking, sidewalks, road installations and signs</b>		
		<b>2.1. Developing the parking for cars</b>		
17	TsC03B1	Mechanic digging with excavator of 0,40-0,70 m <sup>3</sup> , with internal combustion engine and hydraulic command, in grounds with natural humidity, and unloading on the field storage of cat. II.	100 m <sup>3</sup>	8.128
18	TsA20A	Hand digging of soil	m <sup>3</sup>	203.20
19	TsC03F1	Loading soil with the excavator of 0.40 m <sup>3</sup> , K=0.8	100 m <sup>3</sup>	10.16
20	TsI51A5	Transportation with the dumper of 10 t at a distance of 5 km	t	1 930.40
21	TsE05B	Finishing the surfaces with the self-grader in ground of category II	100 m <sup>2</sup>	18.13
22	TsE03A	Manual finishing the surfaces in ground of category II	100 m <sup>2</sup>	8.91
23	DI96	Compacting the earthwork in the ground of cat. II (foundation of the box), with pneumatic compactor of 25 t, 8 movements on one pathway (only the compactor)	100 m <sup>3</sup>	4.53
24	DI105	Compacting the ground of cat. II with	100 m <sup>3</sup>	2.23

1	2	3	4	5
		pneumatic knockers		
25	DA06A2	Draining layer of sand, h=10 cm (sand 270.4x1.1=297.44 m <sup>3</sup> )	m <sup>3</sup>	270.40
26	TsC54B	Developing the foundation layer from crushed stone M400, h=15 cm	m <sup>3</sup>	406.00
27	DE18A	Pavement made of precast concrete paving slabs laid H=8 cm, Bricks type, on a layer of dry cement and sand mixture of 10%, embroidered with dry mixture of cement and sand, 5 cm thick layer	m <sup>2</sup>	2 539.00
28	DE10A	Pre-manufactured concrete borders, for sidewalks 20x25 cm, on concrete foundation 30x15 cm BP100.30.15 (edging stone BP100.30.15 concrete base -0.044 m <sup>3</sup> )	m	716.00
29	TsC54B	Developing the foundation layer from crushed stone M400, hmed=5 cm	m <sup>3</sup>	4.00
30	D1119	Foundation made of monolith concrete, B15	m <sup>3</sup>	34.20
31	DE11A	Small edging, precast from concrete BP100.20.8, placed on a concrete foundation	m	64.00
32	TsD01A	Shoving the vegetal soils on verges, lateral ditches and green zones, 15 cm thick, manually	m <sup>3</sup>	106.00
33	TsH09C	Planting the lawns on the bank areas	100 m <sup>2</sup>	7.07
		<b>2.2. Setting out the sidewalk</b>		
34	TsC03B1	Mechanic digging with excavator of 0,40-0,70 m <sup>3</sup> , with internal combustion engine and hydraulic command, in grounds with natural humidity, and unloading on the field storage of cat. II.	100 m <sup>3</sup>	0.58
35	TsA20A	Hand digging of soil	m <sup>3</sup>	15.00
36	TsC03F1	Loading soil with the excavator of 0.40 m <sup>3</sup> , K=0.8	100 m <sup>3</sup>	0.73
37	TsI51A5	Transportation with the dumper of 10 t at a distance of 5 km	t	138.70
38	TsE05B	Finishing the surfaces with the self-grader in ground of category II	100 m <sup>2</sup>	2.78
39	TsE03A	Manual finishing the surfaces in ground of category II	100 m <sup>2</sup>	0.69

1	2	3	4	5
40	TsC54B	Developing the foundation layer from crushed stone M400, h=10 cm	m <sup>3</sup>	34.70
41	DE18A	Pavement made of precast concrete paving slabs laid H=6 cm, Bricks type, on a layer of dry cement and sand mixture of 10%, embroidered with dry mixture of cement and sand, 5 cm thick layer	m <sup>2</sup>	347.00
42	DE11A	Small edging, precast from concrete BP100.20.8, placed on a concrete foundation	m	179.00
<b>2.3. Installing road signs</b>				
43	DF18A	Planting the pillars SCM2.30 for industrially-manufactured metallic road traffic signs (concrete - 0.059 m3)	pcs	14.00
44	DF18A	Planting the pillars SCM1.30 for industrially-manufactured metallic road traffic signs (concrete - 0.058 m3)	pcs	3.00
45	DF19A	Assembling the road signs A700	pcs	3.00
46	DF19A	Assembling the road signs B700	pcs	14.00
47	DF19A	Assembling the road signs BH-350x700	pcs	14.00
<b>2.4. Setting out the road marking</b>				
48	DF17A	Setting the road marking (white), reflectorizing thermoplastic type	m <sup>2</sup>	115.00
<b>Total, chapter 2 Incl. salary</b>			<b>USD USD</b>	
<b>Total, chapter 1 + chapter 2 Incl. salary</b>			<b>USD USD</b>	
Social and health insurance, out of the salary 24%			USD	
Transportation costs, %			USD	
Total			USD	
Overhead costs, %			USD	
Total			USD	
Benefit, %			USD	
<b>Total costs, works Incl. salary</b>			<b>USD USD</b>	

Bidder

(position, signature, name, surname)

STAMP PLACE