

ITEM NO	DESCRIPTION	UNIT	TENDER AMOUNT		
			QUANTITY	RATE (M)	AMOUNT (M)
2	HEATING VENTILATION AND AIR CONDITIONING (HVAC)				
2.1	Supply, installation and commissioning of Split Air Conditioning Units complete with condensate drain pumps, Carrier or equal and approved. Split units to be inverters.				
2.1.1	2.5 kW wall mounted unit complete with condensate pump and all accessories required to furnish and complete the installation.	No	2		
2.1.2	3.5 kW wall mounted unit complete with condensate pump and all accessories required to furnish and complete the installation.	No	1		
2.1.3	10.5 kW ceiling mounted unit complete with all accessories required to furnish and complete the installation.	No	1		
2.1.4	Wireless remote control	No	4		
2.2	Major service on all existing Split Air Conditioning Units.				
2.2.1	Perform major service on 3.2 kW mid wall unit.	No	1		
2.2.2	Perform major service on 3.4 kW mid wall unit.	No	1		
2.3	Supply and installation of refrigeration piping complete with Armaflex insulation, condensate pipe. External piping should also be protected from direct sun and other weather elements.				
2.3.1	6.4mm Refrigeration piping complete with Armaflex insulation & fittings.	m	22		
2.3.2	9.52mm Refrigeration piping complete with Armaflex insulation & fittings.	m	22		
2.3.3	25mm PVC condensate piping	m	18		
2.3.4	50 x 50 mm PVC trunking with covers for refrigerants pipes	m	1		
2.3.5	50 x 50 mm PVC flat bend for refrigerants pipes	No	2		
2.4	Additions Any other items including the machinery that the contractor deems necessary for the successful and total completion of the work required for this item (particularly to be furnished)	Sum			
	TOTAL FOR BILL No. 2 IS CARRIED TO SUMMARY PAGE				

[illegible]

[illegible]

SUMMARY PAGE					
ITEM	DESCRIPTION				TOTAL AMOUNT (M)
1	Total for Bill No.1: Preliminary and General				
1.1	(a) Fixed amount				
1.2	(a) Adjustable with contract amount				
1.3	(b) Adjustable with contract period				
2	Total for Bill No 2: Heating, Ventilation and Air Conditioning				
3	Total for Bill No 3: Hot Water Generation				
4	Total for Bill No 4: Fire Protection and Emergency Evacuation				
5	Contingency : Provisional Sum to be expended as directed by the Engineer and deducted in whole or in part if not required.	Sum			15,000.00
SUB-TOTAL					
15% VAT					
TOTAL FOR RENOVATIONS FOR UN R.C RESIDENTIAL HOUSE					
Name of Contractor:..... Address and stamp.....Postal Address..... Telephone:.....Cell No:.....Email:..... Authorized Signature:.....Date:..... Designation:.....					