

ITEM	DESCRIPTION	UNIT	QTY	RATE ZMK	AMOUNT ZMK
Preamble The contractor shall take all due care to provide shoring, needling, strutting and all temporary works necessary for supporting the existing structure in the course of demolitions and construction until it becomes self supporting All debris should be removed from site as soon as possible to an approved tipping location and levelled and made environmentally safe The contractor shall hand over to the Employer on site all salvaged demolished materials if any. Contractor to bear in mind, cutting of trees has to be approved and controlled by UNDP Eng while on Site-Climate Change Action					
Substructure-All Provisional					
1	Mobilisation	item	1		-
2	Equipment				-
	Supply and install high quality playground made from high quality fiberglass or equal and approved steel. The work shall include supplying and installation of high quality children playground equipment as per Ref Images and Boq specifications and comply with ATM F1487-07 specifications, the price to include all necessary installation, painting and testing with traffic resistance ,environmental friendly material and walking comfort as approved by UNDP Engineer				-
	All rates shall include all trenches excavation, concreting bases deemed by contractor and Engineer to support each specific equipment specified and concrete support for installation. All Rates to Include Painting, either pre-painted or painted on site in assorted colours for Red, Blue, Yellow and Pink				-
	All rates shall include all trenches excavation, concreting bases deemed by contractor and Engineer to support each specific equipment specified and concrete support for installation.				-
					-
3	High Quality Steel Slide for ages 4-10: 3m high, 5m long effective sloping length with all support double base and 50x50 Steel Square tubes climbing stair spaced at 200mm with climbing handle as side guide support on steel slide and climber deemed fit for aforementioned ages. Ref img.un1	No.	2		-
4	Swing: 2.5m high effective height, 3m spacing between two supports, Swings, two swings per double support made of high quality 100mm round steel poles, steel crossbar and durable chain support hooked to crossbar and Durable PE plastic seats, as support for 2 swing seats as approved by UNDP Engineer Ref img.un2	No.	2		-
5	Seesaw: Moving up and down Seesaws play equipment with 360 degrees rotation, easy grip soft handle for hands, sturdy steel frame construction with attractive colors and all necessary works to be completed as drawing Ref img.un3	No.	2		-
	Merry-G-Round: 100mm thick deck powder coated, with 3 set handrails on top deck, milled out pocket for ball bearing with rebar welded on it to avoid slipping, including grease fittings for bearing and shaft lubrication. Merry-go-round to be 200mm above ground level with galvanised post. 50mm round handrails painted yellow and green. Supply and install 2.5m diameter merry-go-round complete with all accessories Ref img.un4	No	1		-
	Monkey Climber: High Quality Monkey Climber with 2m effective sloping height on each side, with 100mm support poles and 50mm monkey bars spaced at 0.35m with Reg img.UN5	No	2		-
	Flood Lights: Supply and mount on top poles (5m steel included on the fencing materials) stand Dual security Flood lights inbuilt solar powered 600w or more, water resistant	No	2		-

Sand Bed: Supply and spread high quality river sand around play park area as turf with atleast 80mm thickness,with sand containmnet around play area fence with 4 courses of block work m/n	item	1		-
Football Ptich: Excavate over-site in pickable material to remove vegetable soil average 150mm for the football pitch and Install two goal posts with nets	m2	2000		-
Netball Pitch: Excavate over-site in pickable material to remove vegetable soil average 150mm for the netball pitch and install 2 netball ring polls with nets	m2	1000		-
Lime 50kg bags for football and netball pitch markings	item	5		-
Total			ZMK	-
<u>SECURITY FENCE AROUND PLAY AREA</u>				
Install security Fence (fencing wire - 1.8m tall) wire with Razor wire and 2.5m steel poles, 9No steel poles with access gate and lock <i>(these are include 2 flood light poles of 5m).</i>	item	1		-

Total	ZMK			-
TO SUMMARY				
Mobilisation/Demobilisation	ZMK			
Equipment	ZMK			
Transport to site	ZMK			
TOTAL No. Site 1	ZMK			
Proposed Site Mayukwayukwa	No	1	ZMK	-
TOTAL BID	ZMK			