

UNV Bonn, 4. OG, Bereich Vorflur

Leistungsbeschreibung für den Bereich Schreinerarbeiten

- Lieferung und Montage von Raumteilern in unterschiedlichen Breiten (siehe Skizze), inkl. Aufmaß vor Ort sowie Baustelleneinrichtung und alle erforderlichen Arbeiten
- Höhe: ca. 2450 mm
 - 1x Breite 3280 mm
 - 1x Breite 3648 mm
 - 1x Breite 1066 mm
 - 1x Breite 2000 mm
 - 1x Breite 3350 mm
- Material:
 - ca. 40x70 mm starke Eiche Leimholz keilgezinkte Lamellen
 - Oberflächen geölt, die Lamellen werden durch das Decken- und Bodenbrett verschraubt
- Die Raumteiler werden vor Ort im Boden und der Abhang-Decke verschraubt (Überprüfung der Tragfähigkeit)
 - Ggfs. Schaffung einer tragfähigen Unterkonstruktion oberhalb der Abhang-Decke

Description of services for carpentry work

- Delivery and assembly of room dividers in different widths (see sketch), incl. measurement on site as well as site setup and all necessary work

- height: approx. 2450 mm

1x width 3280 mm

1x width 3648 mm

1x width 1066 mm

1x width 2000 mm

1x width 3350 mm

- Material:

Approx. 40x70 mm thick oak. Jointed lamellas.

surfaces oiled, the lamellas are screwed through the ceiling and floor boards

- The room dividers are screwed into the floor and the sloping ceiling on site
(checking the load-bearing capacity)

If necessary, creation of a load-bearing substructure above the slope ceiling

Signature:

B.O'Reilly

BERTRICE O'REILLY, EXECUTIVE ASSOCIATE, EAD

27.05.22

Martin Hart-Hansen

MARTIN HART-HANSEN
27/5/22