

UNV Bonn, 4. OG, Bereich Vorflur

Leistungsbeschreibung für den Bereich Malerarbeiten

- Einrichtung Baustelle / Bodenfläche abdecken
- Abklebarbeiten wie Türzargen/ Lichtband/ Lichtschalter/ Steckdosen usw.
- Demontage Türschilder / Hinweisschilder / Wanduhr
- Ca. 33 m² Vorsatzschale im Bereich Klinkerwand (Denkmalschutz) setzen, bei der Tiefe/Stärke der Schale auf den Zugang zum Flur Bereich Aufzüge beachten, Öffnung Doppelflügeltür
- Ca. 33 m² Malervlies aufbringen / verkleben
- Acrylversiegelung
- Ca. 140 m² Wand streichen in Caparol 3D-System PLUS, Farbe Onyx 15
- 3 Stützen á ca. 610 x 610 x H 2450 mm mit Folie passend zur Wandfarbe bekleben
- Entsorgung von Bauresten

Service description for the area of painting work

- Set up construction site / cover floor area
- masking work such as door frames / light strip / light switch / sockets, etc.
- Dismantling of door signs / information signs / wall clock
- Approx. 33 m² facing shell to be placed in the area of the clinker wall (monument protection), with the depth/thickness of the shell on the access to the corridor area elevators to be considered, opening double wing door
- Apply / glue approx. 33 m² painter's fleece
- Acrylic sealant

- Approx. 140 m² wall to be painted in Caparol 3D-System PLUS, color Onyx 15
- 3 supports á approx. 610 x 610 x H 2450 mm cover with foil matching the wall color
- Disposal of construction waste

Signature:

B. O'Reilly

BETTRICE O'REILLY, EXECUTIVE ASSOCIATE, E&D

27.05.22

MARTIN HART-HANSEN
27/5/22