

LOT 2 - EMBANKMENT STRUCTURE ON THE RIVER TSKHENISTKALI, VILLAGE CHALISTAVI, TSAGERI MUNICIPALITY

№	Normative number and code	Description of works, costs and equipment	Unit of Measurement	Quantity		Material				Wage		Tools and Equipment		Total
				Per standard unit	Total	Country of Origin	Brand	Unit Price	Total	Unit Price	Total	Unit Price	Total	
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
1	Engineering standards and rules IV-2-82 1-11-9	Procession of III group ground with excavator, for developing a Pit by pouring excavated ground next to it	1000 m3		28.48									
		Labour cost	man/hr.	9.96	283.70									
	Srf. 12-116	Excavator 0,65m3	man/hr.	22.30	635.19									
2	Engineering standards and rules IV-2-82 1-118-11	Compacting ground excavated from the cave. Ground should be compacted in layers of 0.30m	100 m3		284.68									
		Labour cost	man/hr.	13.40	3,814.71									
	Srf. 12-323	pneumatic compactor	machinery/hr.	13.00	3,700.84									
3	Engineering standards and rules IV-2-82 1-64-7	Manual surfacing of dam from river side for achieving project inclination of the slope	1000 m2		9.94									
		Labour cost	man/hour	77.00	765.44									
4	SN&R IV-2-82 1-32-3 t.n.3.50	Surfacing the cave surface for providing mattresses by bulldozer, moving for 30m	1000 m²		5.93									
	Srf. 12-141	bulldozer 180 horse force	machinery/hr.	0.27	1.61									
5	Engineering standards and rules IV-2-82 12-9-6	Spreading geo textile on leveled surface and its fixation with wooden stakes	100m2		158.69									

